## CORPUS SIGNORUM IMPERII ROMANI CORPUS OF SCULPTURE OF THE ROMAN WORLD

# **SLOVENIA**

VOLUME I, FASCICLE I

# **POETOVIO**

SARCOPHAGI and ASH CHESTS

BOJAN DJURIĆ

CSIR Slovenia I.1.

Poetovio: Sarcophagi and Ash Chests

Author: Bojan Djurić

Peer-review: Branka Migotti, Sanja Pilipović

Translation: Andreja Maver Cover photo by: Bojan Djurić Copy-editing: Andreja Maver

Published by: University of Ljubljana Press, Ptuj – Ormož Regional Museum, Slovenian Acade-

my of Science and Arts

Issued by: University of Ljubljana Press, Faculty of Arts

For the publisher: Gregor Majdič, rector of the UL, Aleksander Lorenčič, director of the

PMPO, Peter Štih, president of the SASA

For the issuer: Mojca Schlamberger Brezar, Dean of the Faculty of Arts, University of Ljubljana

Design and layout: Bora and Nives Zupančič

Printed by Collegium graphicum

Ljubljana, 2025 First Edition

Number of copies printed: 200

Price: 60 EUR



This work is licensed under a Creative Commons Attribution-ShareAlike 4.0 International License (except photographs).

The book was published with the support of the Slovenian Research and Innovation Agency (ARIS).

First e-edition. Publication is available in open access at / Publikacija je v digitalni obliki prosto dostopna na: https://ebooks.uni-lj.si/ZalozbaUL

DOI: 10.4312/9789612976378

Kataložna zapisa o publikaciji (CIP) pripravili v Narodni in univerzitetni knjižnici v Ljubljani

Tiskana knjiga COBISS.SI-ID=246759939 ISBN 978-961-297-638-5 (Založba Univerze v Ljubljani)

E-knjiga

COBISS.SI-ID=246670339

ISBN 978-961-297-637-8 (Založba Univerze v Ljubljani, PDF)

For Vida Brunčič and Prof. Jože Kastelic

## TABLE OF CONTENTS

Preface	6
Introduction	
History of research	7
Contexts	9
Territory of Poetovio	15
Materials	
Marble	17
Limestone	20
Formal structure	
Marble sarcophagi	21
	25
Norico-Pannonian volute	29
Sarcophagi of limestone	32
Ash chests of limestone	
Iconography	
Sarcophagi	34
Ash chests	34
Portraits or images of the deceased	36
Seasons – Tempora Anni	40
Eros (and Psyche)	43
Pairs of erotes	44
Mourning erotes	45
Attis or the mourning shepherd	46
Mythological motifs	47
Dionysian motifs	48
Conclusion	51
References	53
Catalogue	69
	116
	117
•	118
· · ·	119
	123
	127
0	130
·	133

## **PREFACE**

The decision to publish the Slovenian section of the *Corpus Signorum Imperii Romani* series dates back to the late 1970s, when François Braemer, then president of the international CSIR project, visited Prof. Jože Kastelic in Ljubljana. They foresaw the CSIR SLO to be published in five parts: two for the two Roman colonies on the territory of Slovenia (*Emona, Poetovio*), two for the two municipia (*Celeia, Neviodunum*) and one for the Slovenian part of the territories of *Aquileia* and *Tergeste*. The Slovenian part of the territory belonging to the municipium of *Salla* was to be incorporated into the Poetovio part.

The first volume, now before you, respects this division. It is the result of many years dedicated to studying the stone monuments of Poetovio in the context of the stone productions in Noricum and Pannonia. Only by considering the monuments in the appropriate context has it been possible to understand the dynamics of their production and distribution, as well as their iconographic and stylistic characteristics. Particular attention has been paid to analysing the stones from which the monuments were made. The specialist geological analyses have not been entirely concluded, but the available results nevertheless offer new and detailed insights into the structure and specificities of the stone monuments of Poetovio; without these analyses, our knowledge would be considerably more limited.

This publication would not have been possible without the kind support of the staff of the Ptuj – Ormož Regional Museum (PMPO). Throughout the many years of research, they welcomed my frequent visits to the now dismantled stone collection in the old Ferk Museum and to the museum storage facilities. The generous help of the museum's curators of archaeology, Mojca Vomer Gojkovič in particular, enabled me to exhaustively examine the more than a thousand stone monuments kept in the museum, which have been completely inaccessible to the general and professional public for some years now. The revision of the stone monuments, which Mojca and myself were preparing for several years, was interrupted in 2011 when all archaeological collections were removed from the building of the former Dominican Monastery, it still awaits more favourable times. For the purposes of completing this book, Ivan Žižek, Aleksandra Nestorović, Iva Ciglar and Luka Pukšič have granted me privileged access to some of the monuments, while Valerija Lešnik enabled me to peruse the museum records. I further wish to express my gratitude to the consecutive directors of the museum, namely Marjeta Ciglenečki, Boris Miočinović, Aleš Arih and Aleksander Lorenčič. For the information on the Poetovio monuments kept in other collections, my thanks go to Vesna Koprivnik from the Pokrajinski muzej Maribor, Bernhard Hebert and Stephan Karl from Graz and Manuela Laubenberger from the Kunsthistorisches Museum in Vienna. For the information and help with the monuments built into various buildings across Ptuj and elsewhere, I would like to thank Marija Lubšina Tušek, Ivan Tušek and Stanko Gojkovič from Ptuj, Mira Strmčnik and Mihela Kajzer from Maribor, Primož Predan from Slovenska Bistrica and Marija Javornik from Koritno near Oplotnica. I would like to thank Anja Ragolič for her immense help with some of the inscriptions and photographs. Special thanks go to Branka Migotti from Zagreb for numerous discussions and a critical review of the manuscript.

The late Harald W. Müller, from Spittal an der Drau, and Igor Rižnar from Ljubljana were crucial in identifying the rocks used in producing the stone monuments. My sincere thanks go to both.

I would also like to thank the many colleagues and others not mentioned by name who have contributed to the successful completion of this work, especially my students, who have devoted a considerable amount of their time to the study of the Poetovio monuments. It has been a pleasure to work with each and all of them.

The translation of the book was entrusted to Andreja Maver, who undertook the task with meticulous dedication. To her go my sincere thanks.

Coincidence would have it that the first volume of the CSIR SLO was completed in the year in which the University of Ljubljana celebrated its centenary of archaeological studies. That is, if one chooses to believe in coincidences.

## INTRODUCTION

## History of research

The sarcophagi and ash chests of Poetovio are a distinct and characteristic form of sepulchral monuments in this Roman town. They form part of an extensive stone production that mainly exploited the marble deposits in the Pohorje Mountains (Slovenia), to a lesser extent marble from Gummern (Austria). Miocene limestone was also used, albeit rarely, the origin of which has as yet not been positively identified.<sup>2</sup> The vast majority of the known stone products have survived in the modern-day city of Ptuj and its surroundings, and have been the subject of epigraphic studies and collection interests<sup>3</sup> since the early 16<sup>th</sup> century.<sup>4</sup> The more than four centuries of preponderantly epigraphic interest have decisively marked the pre-modern and modern perception of the Roman stone products as carriers of primarily historical information. The international project Corpus Signorum Imperii Romani, launched in 1963,<sup>5</sup> adopted the tradition of Espérandieu<sup>6</sup> and shifted the focus on the iconography of the stone monuments across the Roman provinces; this was the consequence of a general shift of interest in other aspects of the monuments that took place at that time. Today, the Ubi Erat Lupa online database<sup>7</sup> incorporates both the epigraphic and the iconographic aspects of the Roman stone monuments from across the Roman Empire. It is founded on the guidelines formulated by Alexander Conze<sup>8</sup> and, later on, the major AIDR-Wien project<sup>9</sup> and Arnold Schober as its main driving force. 10 Within this project, Erna Diez (Luz) 11 collaborated with Balduin Saria, <sup>12</sup> who was then engaged in reorganising the Ptuj Museum. <sup>13</sup> In the summer of 1943,

<sup>&</sup>lt;sup>1</sup> Quarry complexes have been identified at Šmartno na Pohorju/Frajhajm above Slovenska Bistrica, Hudinja above Vitanje and Črešnova above Zreče.

<sup>&</sup>lt;sup>2</sup> Most of the limestone presumably comes from the quarries at Kamenščak near Spodnji Duplek, along the River Drava. The large quarry complex at Reberca (the stone referred to as 'Barbara limestone') near Spodnja Korena and the complex at Osek near Sv. Trojica are also considered Roman in the archaeological literature.

<sup>&</sup>lt;sup>3</sup> Augustinus Prygl Tyfernus (1470/79–1535/37), Petrus Apianus (1495–1552).

<sup>&</sup>lt;sup>4</sup> For a historical overview of the interest in and study of the stone products, mainly inscriptions, see Pahič 1977a, 23–31.

<sup>&</sup>lt;sup>5</sup> https://www.corpussignorum.org/csir/home

<sup>&</sup>lt;sup>6</sup> Recueil général des bas-reliefs, statues et bustes de la Gaule romaine 1908–1938.

<sup>&</sup>lt;sup>7</sup> Friederike and Ortolf Harl, lupa.at (Bilddatenbank zu antiken Steindenkmälern).

<sup>&</sup>lt;sup>8</sup> During his time at the University of Vienna between 1869 and 1877. For the starting points of the online database, see Harl 2020.

<sup>&</sup>lt;sup>9</sup> Außenstelle Wien des Archäologischen Instituts des Deutschen Reiches; the name of the Österreichisches Archäologisches Institut (ÖAI) between 1939 and 1945.

<sup>&</sup>lt;sup>10</sup> The project entitled *Die römischen Steindenkmäler der Ostalpenländer (der Alpen- und Donaugaue)* in four volumes. The first volume (*Gau Steiermark*) was the responsibility of the Archaeologisch-epigraphische Seminar der Universität Graz, under the leadership of Arnold Schober and Balduin Saria (cf. Rindler 2004).

<sup>&</sup>lt;sup>11</sup> For her biography, see Gustmiedl-Schümann 2013 with references.

<sup>&</sup>lt;sup>12</sup> For his biography, see Mlinar 2019.

<sup>&</sup>lt;sup>13</sup> His guide to Ptuj and its surroundings was published several years later (Saria 1943).

she created a subject and photographic database of the monuments in and around Ptuj. <sup>14</sup> This corpus, planned during the war, was never completed due to the changes that occurred after the end of the war. <sup>15</sup> The stone monuments in the Ptuj museum were again photographed in 1957, <sup>16</sup> some also in 2005<sup>17</sup> and 2009, <sup>18</sup> and again when the archaeological collection was forced to be removed from the premises of the former Dominican Monastery, i.e. the old Ferk Museum, in 2011. <sup>19</sup> Stanko Pahič very meticulously recorded and published the stone monuments located outside Ptuj. <sup>20</sup> The stone monuments from Poetovio were most recently discussed by Anja Ragolič, who focused on the epigraphic evidence. <sup>21</sup>

Rajko Ložar was the first to systematically study the sarcophagi from Noricum and Pannonia,<sup>22</sup> on the initiative of his professor and mentor Arnold Schober.<sup>23</sup> He rightly included ash chests in the catalogue of his dissertation, arguing that the elongated shape of their chests is similar to that of the sarcophagi, and their size similar to that of the child sarcophagi.<sup>24</sup> The striking formal similarity with sarcophagi and ash chests, however, led him to erroneously include the inscription plate of a *collegium iuventutis*<sup>25</sup> and a slab of an aedicula tomb<sup>26</sup> in his catalogue for Poetovio.<sup>27</sup> Ložar's dissertation was never published and was therefore, it would appear, never used by later researchers. It is not mentioned in the first publication of the Roman sarcophagi in Yugoslavia by Aleksandrina Cermanović;<sup>28</sup> similarly as Ložar, her catalogue includes ash chests, which are consistently referred to as sarcophagi.<sup>29</sup> Erna Diez specifically studied the ash chests of Poetovio,<sup>30</sup> again without mentioning Ložar, and listed in her catalogue 25 ash chests<sup>31</sup> and four sarcophagi from Ptuj known to her at the time. In their overview of Roman sarcophagi from 1982, Guntram Koch and Hellmut Sichtermann summarised the extant knowledge,<sup>32</sup> though giving several erroneous identifications.<sup>33</sup>

<sup>&</sup>lt;sup>14</sup> Rindler 2004.

<sup>&</sup>lt;sup>15</sup> The surviving part of the work done in Ptuj is now kept in the Institut für Archäologie Graz (Rindler 2004, 346). Some of the photographs are included in the Ubi Erat Lupa database.

<sup>&</sup>lt;sup>16</sup> Photographer Srečo Habič on the request of Iva Mikl, curator at the Ptuj museum. The b/w 6  $\times$  9 cm negatives are held in the Heritage Information and Documentation Centre (InDoc Centre) at the Slovenian Ministry of Culture.

<sup>&</sup>lt;sup>17</sup> Ortolf Harl for the Ubi Erat Lupa online database. Copies of the digital photographs are kept in the PMPO.

<sup>&</sup>lt;sup>18</sup> Photographer Milan Pajk on the request of Bojan Djurić. Coloured slides 6 × 6 cm, taken with a Hasselblad 501c camera, kept in the PMPO.

<sup>&</sup>lt;sup>19</sup> Photographed by Bojan Djurić and Edisa Lozić, digital photographs also kept in the PMPO.

<sup>&</sup>lt;sup>20</sup> Pahič 1977a; photographs kept in the Maribor Regional Museum.

<sup>&</sup>lt;sup>21</sup> Ragolič 2023; the publication of the sepulchral monuments as the first part of *Inscriptiones latinae Sloveniae 2/1*. *Poetovio*.

<sup>&</sup>lt;sup>22</sup> Ložar 1927; for a discussion on his dissertation, see Šmid 2015.

<sup>&</sup>lt;sup>23</sup> For his biography, see Wlach 2014.

<sup>&</sup>lt;sup>24</sup> Ložar 1927, 48.

<sup>&</sup>lt;sup>25</sup> Graz, Universalmuseum Joanneum, Inv. No. 61; CIL III 4045; Hoffiler – Saria 1938, No. 341; Ložar 1927, No. 78.

<sup>&</sup>lt;sup>26</sup> PMPO RL 35; CIL III 13410; Hoffiler – Saria 1938, No. 393; Ložar 1927, No. 83.

<sup>&</sup>lt;sup>27</sup> It lists nine monuments, Nos. 75 to 83.

<sup>&</sup>lt;sup>28</sup> Only those from Noricum and Pannonia are published; Cermanović 1965.

<sup>&</sup>lt;sup>29</sup> Her catalogue for Pannonia includes seven monuments from the Ptuj area, erroneously also a slab with the relief of a nymph (Hoffiler – Saria 1938, No. 420; Lupa 6314).

Diez 1948; because of her cooperation with Arnold Schober (cf. Harl 2020; Wlach 2014, 462; Rindler 2004), she would very likely have been familiar with Ložar's dissertation.

No. 13 in her catalogue is not an ash chest.

<sup>&</sup>lt;sup>32</sup> Koch – Sichtermann 1982, 328–329.

Possessing a detailed knowledge of the monuments in the Ptuj museum, Erna Diez avoided such errors. See Diez 1948, 152–153.

In 2001, Bojan Djurić published two articles on the sarcophagi<sup>34</sup> and ash chests<sup>35</sup> of Poetovio, proposing a new interpretation of how the characteristic tripartite division of the chests on both sarcophagi and ash chests was created. In 2015, he also published the only frieze sarcophagus known in Pannonia.<sup>36</sup> The last to discuss the sarcophagi and ash chests of Poetovio together with those from Celeia was Erwin Pochmarski.<sup>37</sup> His analyses of the chronologically diagnostic iconographic elements on them have enabled a more precise dating of these monuments, though it should be noted that his overviews of the sarcophagi and ash chests from Poetovio include some examples that do not belong there.<sup>38</sup>

#### **Contexts**

From their creation onwards, Roman sarcophagi and ash chests were subject to different fates and reuses (Figure 5). Many were already reused in Late Antiquity,<sup>39</sup> a practice observable across the Roman Empire,<sup>40</sup> while others were reused later. They remained in such secondary functions at least throughout the medieval and modern periods. In Slovenia, they were recorded as such only from the 19<sup>th</sup> century onwards. Ash chests and their lids served as drinking troughs for livestock or as quench tanks in smithies; examples of these include the lid from Draženci,<sup>41</sup> ash chests from Ptuj,<sup>42</sup> Velika Nedelja,<sup>43</sup> Šmartno na Pohorju<sup>44</sup> and Maribor,<sup>45</sup> while one ash chest<sup>46</sup> was transformed into a wash basin in the Minorite Monastery in Ptuj towards the end of the 16<sup>th</sup> or beginning of the 17<sup>th</sup> century. Similarly for sarcophagi, one chest from Orešje<sup>47</sup> was also used as a drinking trough, while the bottom of another chest<sup>48</sup> was refashioned into a shallow wash basin in the Minorite Monastery in Ptuj. The bottom of a sarcophagus chest,<sup>49</sup> built into the west Renaissance roundel (bastion) of the Ptuj city walls, next to the Dominican Monastery, was reused as a firm footing for a heavy weapon.

Many of the known fragments of sarcophagi and ash chests have been recycled as building material (41% of all known pieces), most of them intentionally reduced to an appropriate size. They were

<sup>&</sup>lt;sup>34</sup> Djurić 2001b.

<sup>&</sup>lt;sup>35</sup> Djurić 2001a.

<sup>&</sup>lt;sup>36</sup> Djurić 2015. For several new and different identifications, see the descriptions in the catalogue below.

<sup>&</sup>lt;sup>37</sup> Pochmarski 2014b; 2015.

The relief block from Črešnjevec (Pochmarski 2014b, 355, Fig. 3; Kremer 2001, 207, No. 113; Lupa 4695) is part of an aedicula tomb, not an ash chest. The slab with the scene of Iphigenia escaping from Tauris, built into the church of St John the Baptist in Dravinjski vrh (Šubic 1975; Lupa 4275), is also part of an aedicula tomb rather than an ash chest as thought previously (correctly in Lupa 4275). The fragmented relief with a naked male figure with a cloak (Ptuj, Mestni stolp, RL 781, Lupa 4844) is part of a funerary stela. The slab with the depiction of a nymph held in PMMb (not in PMPO as stated in Lupa 6314) is not part of a sarcophagus (Pochmarski 2016; Pochmarski – Handy 2020, 53), as was revealed when the relief was removed from the wall of the museum in 2004.

<sup>&</sup>lt;sup>39</sup> An example is the ash chest lid (Cat. No. 99), which served as the base of an inhumation grave in the northern cemetery of Poetovio; Šubic 1967, 94.

<sup>&</sup>lt;sup>40</sup> See e.g. Murer 2018; 2022; Beutler 2019.

<sup>&</sup>lt;sup>41</sup> Cat. No. 125.

<sup>42</sup> Cat. No. 44; Cat. No. 89.

<sup>&</sup>lt;sup>43</sup> Cat. No. 49.

<sup>44</sup> Cat. No. 44.

<sup>45</sup> Cat. No. 44.

<sup>&</sup>lt;sup>46</sup> Cat. No. 48; now in the Minorite church in Ptuj.

<sup>&</sup>lt;sup>47</sup> Cat. No. 4.

<sup>&</sup>lt;sup>48</sup> Cat. No. 7.

<sup>&</sup>lt;sup>49</sup> The bottom (Cat. No. 21) was partially uncovered and documented in 2022, then left *in situ*.



Figure 1. Marble spolia used in the construction of Ptuj Castle, here shown in the east façade of the west tower



Figure 2. Foundations with marble spolia: Črešnjevec, church of St Michael, southwest corner of the first church (left), and Veliko Tinje, church of Sts Peter and Paul, northwest corner (right)



Figure 3. Marble spolia reused as building blocks in the south wall of the Romanesque church of St Michael in Črešnjevec





Figure 4. Quoins of marble spolia in the Romanesque bell tower of St Michael's church in Šmartno na Pohorju (left) and in the church of St Margaret of Antioch in Kebelj (right)




Figure 5. Various uses of the known sarcophagi and ash chests of Poetovio, expressed in percentage (key: 1 – primary use; 2 – secondary use in Antiquity; 3 – damaged in Antiquity; 4 – secondary use in post-Antiquity; 5 – building material; 6 – intentional display; 7 – unknown

employed to strengthen the foundations and corners of churches and their bell towers (Figures 1–4),<sup>50</sup> in many places also as ordinary construction material for buildings, both sacred and secular.<sup>51</sup> Intentional display of sarcophagi and ash chests was rare (8 or 6%) and mainly known from church facades, though the date when this occurred is unknown. Examples include the front of the frieze sarcophagus,<sup>52</sup> which was built into the south wall of the presbytery of the old church of St Martin in Hajdina, and the acroterium of a sarcophagus lid<sup>53</sup> built into the east wall of St Stephen's church in Spodnja Polskava. Particularly interesting among the ash chests is a fragment<sup>54</sup> in the presbytery of the church of the Dominican Monastery in Ptuj, built in the interior above the door leading from the presbytery to the monastery. Here, a pagan mourning erot was transformed into a Christian winged angel by removing his genitals.<sup>55</sup> An ash chest<sup>56</sup> was likely intentionally built into the north-east corner of the parish church in Studenice, with the inscription facing the visitor, similarly

<sup>&</sup>lt;sup>50</sup> Characteristic use in the Romanesque and Early Gothic churches in southern Pohorje (Šmartno na Pohorju, Veliko Tinje, Kebelj), where the local rock is mainly schistose gneiss that is unsuitable for the solid quoin masonry. Many of the marble pieces of sepulchral monuments used in these churches can be seen as evidence of the medieval trade in ancient spolia in the wider area of Ptuj.

In Ptuj for the construction of the church of St George, the west tower of Ptuj Castle and numerous medieval houses, in Črešnjevec for the church of St Michael and its precinct wall, similarly in Videm near Ptuj and nearby Dravinjski vrh. All the early churches in the wider area of Ptuj have built-in ancient spolia.

<sup>&</sup>lt;sup>52</sup> Cat. No. 1.

<sup>&</sup>lt;sup>53</sup> Cat. No. 32.

<sup>&</sup>lt;sup>54</sup> Cat. No. 59.

<sup>&</sup>lt;sup>55</sup> The identification as Psyche, as proposed by Hoffiler and Saria (1938) and accepted by Lupa 3776 (now changed), is erroneous.

<sup>&</sup>lt;sup>56</sup> Cat. No. 74.

as the lids with the images of the deceased in the west wall of St Margaret's church in Pernica<sup>57</sup> and in the north wall of the Marian church in Slivnica pri Mariboru.<sup>58</sup> Another possibly intentionally displayed piece is the lid fragment<sup>59</sup> with the images of three deceased built into the interior south wall of St Michael's church in Črešnjevec.

It is not possible to reliably establish how many sarcophagi and ash chests were broken up and thrown into limekilns from Late Antiquity onwards.<sup>60</sup> We can, however, propose an estimate using the calculations of Guntram Koch who attempted to calculate this share for the Attic sarcophagi,<sup>61</sup> and found that between one and two per cent survived.

The 130 known Poetovio sarcophagi and ash chests, or parts thereof, include at least 17 (13%) that were discovered in their original context in cemeteries, though we have almost no information on their stratigraphic position and exact location.<sup>62</sup> We are lacking stratigraphic data even when archaeologists were present at the discoveries.<sup>63</sup> Stratigraphic evidence is only available for a single sarcophagus,<sup>64</sup> which was found to be positioned 1.85 m below the surface<sup>65</sup> and not visible to the visitors to the cementery<sup>66</sup> (Figure 6). Examples with anathyrosis or a sunken centre<sup>67</sup> of the stand-




Figure 6. Stratigraphic position of a sarcophagus upon discovery (Cat. No. 3; Šubic 1972)

<sup>&</sup>lt;sup>57</sup> Cat. No. 98.

<sup>&</sup>lt;sup>58</sup> Cat. No. 99.

<sup>&</sup>lt;sup>59</sup> Cat. No. 103.

<sup>&</sup>lt;sup>60</sup> For the use of the sepulchral monuments of Poetovio in the production of lime already in Antiquity, see Tušek 1984.

<sup>61</sup> Koch 2015, 154–157.

<sup>&</sup>lt;sup>62</sup> The cemeteries of Poetovio, similarly as the building remains of the colony, are believed to have suffered greatly from an extremely negative attitude of the post-war city administrations and the vast majority of the inhabitants of Ptuj towards the archaeological remains of Poetovio.

<sup>63</sup> Sarcophagi: Cat. Nos. 2, 3, 80, 82.

<sup>&</sup>lt;sup>64</sup> Sarcophagus Cat. No. 3, excavated by Zorka Šubic.

The drawing of the stratigraphy shows that the top of the lidded sarcophagus was level with the ground and then covered with a layer of soil (colluvium/alluvium?), which casts some doubt on the excavator's published information on the depth of the cut made to receive the sarcophagus.

<sup>&</sup>lt;sup>66</sup> For the invisible sarcophagi, see Meinecke 2012.

<sup>&</sup>lt;sup>67</sup> A sarcophagus with a sunken underside is also less heavy.




Figure 7. Incidence of inscriptions and decorations on the known sarcophagi and ash chests of Poetovio, expressed in percentage

ing surface indicate that some sarcophagi and ash chests were placed on a flat footing rather than directly on or below ground.

Apart from the difference in the type of buried human remains (cremated or inhumed), the basic functional difference between sarcophagi and ash chests is that the latter are in fact primarily family tombs, similar to aedicula tombs, whereas sarcophagi are primarily (though not always) intended for a single deceased, sometimes two. Ash chests must therefore have been accessible for subsequent burial over a certain, lengthy period of time, not so sarcophagi. We could presume that sarcophagi were more commonly inaccessible/invisible compared with ash chests, with inscriptions and decoration playing no major role. Indirectly, examples of marble chests without inscription and decoration, which are twice as numerous among the known sarcophagi than among the ash chests, may speak in favour of the monument/grave being invisible to the viewer or passer-by (Figure 7). There is, however, another piece of indirect evidence, which seems more compelling. Most of the completely preserved sarcophagi and ash chests in Pannonia must have been in some manner inaccessible for medieval and later reuse of materials, especially marble, which was ideal for lime production. The sarcophagi and ash chests placed in crypts or buried under ground were hidden from looters, though they could also have been buried under the topsoil following a natural

<sup>&</sup>lt;sup>68</sup> In connection with the lavishly decorated 'invisible' Metropolitan sarcophagi, Katharina Meinecke notes that their decoration could be admired at the home of the deceased during the *exsequiae*, when the body was laid on display (Meinecke 2012, 102).

<sup>&</sup>lt;sup>69</sup> The inscription could also have been painted, though there is as yet no evidence of this.

The number only includes the ash chests and sarcophagi with a tripartite front.

The ash chest with the burial of a child unearthed in the eastern cemetery of Poetovio (Cat. No. 83; Tušek 1992a) could possibly be seen in the function of a sarcophagus.

A good example is the sarcophagus found in 1997 at Šid-Beljnjača (Pop Lazić 2008).

disaster. A good example of buried and completely preserved<sup>73</sup> sarcophagi are the Late Roman sarcophagi of Miocene limestone.<sup>74</sup> The completely surviving chests of marble should therefore also indicate their original position below ground, either buried or placed in crypts. Surprisingly, the share of known complete chests of the marble sarcophagi and ash chests of Poetovio is 31% for both,<sup>75</sup> suggesting that roughly a third were placed below ground and that we cannot ascertain a considerable difference in that regard between sarcophagi and ash chests.

## Territory of Poetovio

From the early 2<sup>nd</sup> century, *colonia Ulpia Traiana Poetovio* was a town on the River Drava in the province of Pannonia Superior, close to the border with the province of Noricum. At least from the early 1<sup>st</sup> century CE, a military fortress with *canabae* stood at the river crossing, the latter conferred the status of a *colonia* with the departure of the army under the reign of Trajan. The colony's administrative territory is difficult to define precisely, as there is little solid evidence on its boundaries.




Figure 8. Territory of Poetovio according to Horvat et al. 2003

<sup>73</sup> Preserved to this degree because the stone was unsuitable for lime production.

<sup>&</sup>lt;sup>74</sup> There are 13 known examples at Ptuj.

Nine of the 29 chests of sarcophagi and 16 of the 52 of ash chests.

A summary of the discussions and definitions of its boundaries since the beginning of the 20<sup>th</sup> century, together with a proposed map based on these definitions, was published in 2003 by a group of archaeologists led by Jana Horvat<sup>76</sup> (Figure 8). They proposed that the western boundary ran east of the foothills of the Pohorje Mt, crossed the Drava between Maribor and Starše, and continued



Figure 9. Territory of Poetovio according to Ragolič 2014

<sup>&</sup>lt;sup>76</sup> Horvat et al. 2003.

in a north-easterly direction to the River Mura that represented the boundary approximately up to Sveti Martin na Muri. From there on, the boundary continued in the area between Ludbreg and Varaždinske Toplice and southwards to the Kalnik Hills, then westwards below the mountains of Ivanščica (Ivančica), Donačka gora and Boč.

In a study specially dedicated to these boundaries from 2014,<sup>77</sup> Anja Ragolič proposed new boundaries for the Poetovio *ager* using the site catchment analysis and Thiessen polygons. According to this study, the territory includes the area of the eastern Pohorje Mt and the area of Maribor in the west, as well as the area south of Ivanščica (Ivančica) in the south (Figure 9).

In the various corpora of stone monuments, territory is the category that provides the formal framework. In cases where the territory is intersected by modern state boundaries, the corpus is usually divided along modern boundaries. In the case of Poetovio, its territory extends into Austria to the north and Croatia to the east and south, but neither sarcophagi nor ash chests have come to light in these parts. The corpus of monuments from the Slovenian part published in this catalogue is thus also the complete corpus of sarcophagi and ash chests from the territory of Poetovio as delimited above. With regard to its boundaries, we should emphasise that the administrative boundaries of Roman autonomous towns are of little relevance to the study of the stone products, which easily crossed boundaries by trade in one direction or the other. Crucial in this respect are the centres of production and the transport routes by which the products reached their customers and buyers. These centres are linked to the sources of the stone used, which may be the property of a town or not. The numbers of products of different categories according to urban territories is therefore irrelevant, as it tells us nothing of their production or their customers. The administrative territory is a completely arbitrary category in the study of the Roman stone monuments.

## **MATERIALS**

### Marble

Harald W. Müller analysed the marble used for the sarcophagi and ash chests from Poetovio in 2003 and 2004.<sup>80</sup> He performed the analyses of the sarcophagi found elsewhere in Pannonia (*Siscia, Aquae Balissae, Mursa, Sirmium*) between 2005 and 2008.<sup>81</sup>

#### Methodology

Using a diamond drill with a water-cooled bit, core samples measuring up to 4 cm in length and 12 mm in diameter were extracted from select monuments and prepared for laboratory analysis.

The outer layer of rock, approximately 1 cm thick, was removed and the cores cleaned in diluted nitric acid (HNO<sub>3</sub>) to eliminate impurities. After several rinses with distilled water, the sample was dried and ground to the analytical level in an agate mill.

<sup>&</sup>lt;sup>77</sup> Ragolič 2014.

<sup>&</sup>lt;sup>78</sup> E.g. Scarbantia: for the Hungarian part, see Farkas – Gabler 1994, for the Austrian part, see Krüger 1974.

<sup>&</sup>lt;sup>79</sup> E.g. Pochmarski 2014, 354.

<sup>&</sup>lt;sup>80</sup> The results were published in Djurić – Hebert et al. 2004.

The results for *Siscia* and *Aquae Balissae* were published in Migotti – Šašel Kos – Radman-Livaja 2018, those for *Mursa* in Djurić – Filipović – Müller 2009 and those for *Sirmium* in Djurić *et al.* 2006.

Stable isotope analyses (18O and 13C)

The  $^{18}$ O and  $^{13}$ C stable isotopes were identified relative to the PDB standard introduced by Craig (1957). The pulverised marble (50 mg per sample) was treated with 100% phosphoric acid ( $H_3PO_4$ ) at 25 °C in the interval of 24 hours. The obtained  $CO_2$  was collected in glass tubes, frozen to -70 °C with liquid nitrogen and then analysed. The  $\delta^{18}$ O values are given in permille and the  $\delta^{13}$ C values in relation to PDB; the results are given in Table 1. The analyses were conducted by Dr Michael Unterwurzacher, using the ThermoFisher Delta Plus XL and V PLUS MS (with the South Tyrolean Laas marble as the reference standard), and Dr Ana-Voica Bojar from Graz.

#### Chemical analyses

These were conducted using the ICP-MS technique, with 100 g of ground stone powder completely dissolved in a PTFE tube containing an acid mixture (5 ml HNO<sub>3</sub>-HClO<sub>4</sub> 1:1, 10 ml HF). After evaporation, the Na, Mg, Al, K, Sc, V, Cr, Fe, Mn, Co, Cu, Zn, Rb, Sr, Y, Cd, Ba, La, Ce, Eu, Hf, Th and U content was measured. Dr Heinz Fröschl performed the analyses at the Österreichisches Forschungszentrum Siebersdorf.

The identification of the marble origins is the prerequisite for identifying the production centres and rests on the assumption that there was a two-phase production process (first phase involving structurally defined part-finished products completed in the second phase) and that the part-finished products of different production centres were at least partially distinguishable from each other in terms of form. These production centres were generally located next to quarries, which then sent their products to various locations to be finished and delivered to the customers. This explanatory model allows the identification of the different types of products of individual stonemasonry workshops, their formal features and the spatial scope of their products. In principle, it also enables us to identify the workshops that finally decorated the stone products.

The 41 marble sarcophagi from Poetovio or their fragments include 25 that were analysed, which represents 61% (Figure 10). Their marble was found to originate from Pohorje (21 or 84%) and Gummern (3 or 12%), while the results for one sample (4%) were inconclusive.

The 86 marble ash chests from Poetovio or their fragments include 15 that were analysed, representing 17.4% (Figure 11). Their marble was found to originate from Pohorje (14 or 93%) and Gummern (1 or 7%).

The results of the marble analyses show that the main source of raw material for the sarcophagi and ash chests of Poetovio and its territory was the Pohorje quarries located between Šmartno na Pohorju and Hudinja above Vitanje. These quarries have been incompletely investigated, although some attempts have been made.<sup>82</sup> The attempts include the analyses of Harald W. Müller (Figure 12 and Table 1 on p. ?), which were the first archaeometric analyses of Pohorje marbles with the first ever integral publication of the analytical data.<sup>83</sup> Alongside Pohorje marbles, the second source was found to be the quarry at Gummern near Villach/Beljak, in Austrian Carinthia, which was undoubtedly the largest and most prominent quarry of Eastern Alpine marble in Antiquity.<sup>84</sup>

<sup>&</sup>lt;sup>82</sup> In addition to Harald W. Müller, archaeometric analyses of Pohorje marble have in recent years also been conducted by Simona Jarc (Jarc 2006) and Snježana Miletić (Miletić 2023).

<sup>83</sup> Müller 2004, 368–383.

<sup>84</sup> Müller 2007.

## SARCOPHAGI MARBLE




Figure 10. The  $\delta^{18}O$  and  $\delta^{13}C$  isotope diagram for Pohorje (blue) and Gummern marbles (green) used for the sarcophagi




Figure 11. The  $\delta^{18}{\rm O}$  and  $\delta^{13}{\rm C}$  isotope diagram for Pohorje (blue) and Gummern marbles (green) used for the ash chests




Figure 12. The  $\delta^{18}$ O in  $\delta^{13}$ C isotope diagram of the samples taken from the known Pohorje quarries plotted against the data fields of Pohorje (blue) and Gummern marbles (green) according to Müller

#### Limestone

All the limestone sarcophagi and ash chests were made of Neogene limestone. This is white to yellowish limestone largely composed of the detritus of lithotamnian algae, bryozoans, mollusc shells, echinoderms and foraminifera. In geologic literature, it is generally known as lithotamnian limestone or *Lethakalk*. All the sarcophagi and ash chests were sampled and thin sections made from the samples that were then used for palaeontological analyses. The limestones were found to be of Lower Badenian age differing in principle only in the proportion of extraclasts and the presence of pelagic foraminifera. The extraclasts, which mainly belong to polycrystalline and monomineralic quartz, are poorly rounded to sharp-edged with some larger grains, up to 5 mm in size, that are very well rounded, as well as carbonate grains. The extraclasts are predominantly also chloritised, i.e. weathered, and derived from metamorphic rocks. Badenian limestone in the Ptuj area lies on top of Lower Miocene clastites containing the above-described grains redeposited into Badenian limestone. This shows that the source of the rock is the lowest part of Badenian limestone cropping out along the River Drava between Kamenščak and Zgornji Duplek in the west, and Hrastovec in the east.<sup>85</sup>

<sup>85</sup> See Žnidarčič, Mioč 1989.


### FORMAL STRUCTURE

## Marble sarcophagi

The chest of a Poetovio marble sarcophagus is a more or less irregular rectangular block of Eastern Alpine marble, the size of which is not standardised, but fairly random within the basic parameters expressed in whole numbers: the length measures between 6 and 7 Roman feet (*pedes*), the height roughly between 2 and 2.5 *pedes* and the width between 3 and 4 *pedes*. None of the known sarcophagi have the length, height and width in whole numbers; this randomness is also observable in the size and proportions of their component parts.

A block of marble was carved into a chest with 13 to 21 cm thick sides and a bottom that is usually slightly thicker, measuring 15 to 36 cm (exceptionally 13–14 cm). Most surviving sarcophagus chests are roughly 2 m long, the longest measuring between 2.2 and 2.3 m (Figure 13). The two-metrelong chests weigh up to 1500 kg, while the sarcophagi in the longest group weigh 2500 to 3000 kg.

## SARCOPHAGI MARBLE






Figure 13. Diagrams showing the width, length and height of the chests of Pannonian marble sarcophagi

<sup>&</sup>lt;sup>86</sup> Only three of the sarcophagi from Ptuj survive as complete chests (Cat. Nos. 2, 3, 4). Considerably more numerous are the complete marble sarcophagi from other Pannonian towns, which offer a better insight into their production and structure (Szombathely 1, Sisak 1, Daruvar 1, Osijek 1, Szekszárd 1, Šid 2, Sremska Mitrovica 2, Kostolac 1).




Figure 14. Diagram showing the length and weight of the chests of Pannonian marble sarcophagi

The weight of the lids is unknown, only the two lids in the shape of slabs<sup>87</sup> can be estimated to weigh approximately 700 kg (Figure 14).

The exterior surfaces of the front and both short sides of the chests are precisely worked, whereas the rear is roughly dressed; this corresponds to the practice usual in the western part of the empire and related to their position within a cemetery. Some chests and lids<sup>88</sup> survive in the quarry state (Figures 15 and 16), which enables us to identify a two-phase production. They clearly show that the first phase involved defining the general structure of the sarcophagus with the inscription and decoration panels. A more or less roughly dressed stone mass is left in the decoration panels, to be carved later. The front panels are commonly given a moulded frame, while those on the short sides may be framed with a simple carved line. This simple approach is also observable on the only lid surviving in the quarry state.<sup>89</sup> The upper frame of the front decoration panels may be carved as a moulded Norico-Pannonian volute already in this phase,<sup>90</sup> while such volutes only exceptionally occur on the short sides.<sup>91</sup>





Figure 15. Examples of sarcophagi in the quarry production state (Cat. Nos. 4 and 3)

<sup>&</sup>lt;sup>87</sup> The lids of the sarcophagi with Cat. Nos. 2 and 3.

<sup>88</sup> Cat. Nos. 2, 3, 4, 12, 29.

<sup>89</sup> Cat. No. 29.

<sup>&</sup>lt;sup>90</sup> The upper frame is flat in Cat. Nos. 2 and 3.

<sup>&</sup>lt;sup>91</sup> Cat. No. 11.



Figure 16. Sarcophagus lid in the quarry production state (Cat. No. 29)

The chest interior exhibits the characteristic horizontal tool marks on the sides, probably of a double-pointed quarry pick, that become increasingly curved towards the bottom, while the tool marks on the bottom are those of a point. There are no chests with a raised headrest on the bottom. The upper or bedding surface of the sarcophagi consistently has a raised semicircular edge along the interior, serving to keep the lid in place (Figure 17). The exterior of the short sides also frequently (but not always) bears a clamp hole below the upper edge, which held an iron clamp fixed with lead. The mostly gabled (rarely hipped) lids have a coarsely dressed hollow interior and a flat and finely finished standing surface that rests on the chests. The flat lids, consisting of a simple slab, have a fairly wide and straight groove carved on the lower surface that corresponds with the raised edge on the sarcophagus' bedding surface.



Figure 17. Surface finish of the interior side and bottom, as well as bedding (Cat. Nos. 1 and 6)

The exterior structure of the chests shows, almost without exception, <sup>92</sup> a tripartite division of the front and undivided short sides. The three parts of the front, consisting of a large central panel, bearing the inscription, and two lateral decoration panels, predominantly follow the division into

<sup>&</sup>lt;sup>92</sup> The only true exception is the only known frieze sarcophagus from Pannonia (Cat. No. 1).

five equal parts – modules<sup>93</sup> (Figure 18). Within this division, the three central modules<sup>94</sup> are reserved for the inscription panel and the two lateral modules for the decoration panels. The size of the module is not measured, but rather determined by simple applied geometry using a length of rope (the equivalent of our compass) and a straightedge. The process of dividing an ABCD rectangle (Figure 20) into five equal rectangles involves several steps. First, the centre of the ABCD rectangle is determined by the diagonals AB and CD, through which the vertical  $(\alpha\beta)$  and horizontal ( $\beta\delta$ ) centre lines are drawn. The intersections of the diagonals A $\delta$  and D $\beta$ , and the diagonals By and  $C\alpha$ , together with the intersections of the diagonals  $C\delta$  and  $B\alpha$ , and  $A\beta$  and  $B\gamma$ , then determine all the modules. The central part that was intended for the inscription, which is the most important in the structure of the whole, extends to the boundary with the two lateral modules. Its frame may be constructed within the three central modules or reaches with the full width of the moulded frame into the lateral modules. The width of the lateral front panel within a lateral module is defined by the intersections of the diagonals  $A\beta - \alpha\gamma$  and  $C\alpha - \beta\gamma$  on one side and the intersections of  $D\beta - \alpha\delta$  and  $B\alpha - \beta\delta$  on the other side. The division of a rectangle into six modules is carried out in a similar way (Figure 19). The use of intersections to construct geometric schemes follows the principles formulated by Tons Brunes in the form of the eight-pointed star (Brunes star). 95




Figure 18. Dividing a rectangle into five equal parts (dashed line) using applied geometry (Brunes star)

Almost all% of the sarcophagus lids are gabled with four corner acroteria that are lower than the lid ridge. The ridge has a wide, flat and slightly raised top surface. Of the two slopes on either side, the front is usually carved to imitate tegulae and imbrices, whereas the rear slope is flat. The vertical front side of the lid may bear carved lines that outline the shape of the tegulae and imbrexes in sec-

<sup>&</sup>lt;sup>93</sup> The two exceptions with six modules are the low sarcophagi Cat. Nos. 2 and 3.

<sup>&</sup>lt;sup>94</sup> Four central modules in the sarcophagi Cat. Nos. 2 and 3.

<sup>95</sup> Kappraff 2000; 2002.

There are two surviving flat sarcophagus lids (Cat. Nos. 2 and 3), one very large and heavily damaged hipped lid found at Ljudski vrt in Ptuj (Cat. No. 39; Djurić 2019b) and another hipped lid with corner acroteria on a sarcophagus from Szekszárd (*Alisea*; Lupa 824).




Figure 19. Dividing a rectangle into six equal parts (dashed line) using applied geometry (Brunes star)




Figure 20. Dividing a rectangle into five equal parts (dashed line) and determining the width of the lateral front panels (dotted line) using applied geometry (Brunes star)

tion, but may also carry an inscription within a frame<sup>97</sup> or without it.<sup>98</sup> The acroteria bear decoration panels that are either one- (only on the front) or two-sided (on the front and sides).

#### Marble ash chests

The chest structure of most known ash chests is identical to that of the sarcophagi. It is a rectangular block of Eastern Alpine marble, the size of which is fairly random within the basic parameters expressed in whole numbers: the length measures between 2.5 and 4.5 Roman feet (pedes), the height roughly between 1.5 to nearly 2.5 pedes and the width between almost 2 to almost 3 pedes.

<sup>&</sup>lt;sup>97</sup> Cat. No. 31.

<sup>98</sup> Cat. No. 35; Cat. No. 28.

Some chests come close in size to those of sarcophagi, <sup>99</sup> but differ mainly in the kind of human remains they held and in some cases also the thickness of the bottom. None of the known ash chests have the length, height and width expressed in whole numbers; this randomness is also observable in the size and proportions of their component parts. Ash chests can be divided into three size groups: those measuring up to 3 *pedes* in length, those that are roughly 3.5 *pedes* long and a few that are roughly 4.5 *pedes* long (Figure 21). A block of marble was hollowed out into a chest with 8 to 15 cm thick sides and most frequently a substantial, more than 30 cm thick bottom. <sup>100</sup> This thickness also increases the overall weight, which falls within three groups: 300–500 kg, 500–750 kg and around 1000 kg (Figure 22). The weight of the lids is not known.

The chests are precisely worked on the front, many also on the short sides, whereas the rear sides that were hidden from view are more coarsely finished. A significant number of the chests and their fragments survive in the quarry state (Figure 23), thus revealing the same production process as the sarcophagi. The same process applies to the lids, of which we even have a complete block




Figure 21. Diagrams showing the width, length and height of the marble ash chests

<sup>&</sup>lt;sup>99</sup> Cat. No. 49.

Exceptionally 18 cm in the ash chest with Cat. No. 43.




Figure 22. Diagram showing the length and weight of the marble ash chests

with the stonemason's guidelines carved onto the intended lid (Figure 24), showing a phase in the production process even before the part-finished product was ready for decoration. The chest interior is dressed similarly as on the sarcophagi. The lid has a flat standing surface and its interior is hollowed out using a point chisel.

There are two basic chest forms of ash chests. A smaller number of ash chests have a low oblong chest with only an inscription panel on the front, while a much more substantial number has a higher chest with a tripartite front, akin to the sarcophagi. In the former, the moulded inscription panel may cover the whole front or not, in the latter case a coarsely dressed surface is left on either side. It is not possible to determine in which phase the inscription panel with a moulded frame was made, though




Figure 23. Examples of ash chests in the quarry production state: A – Ptuj (Cat. No. 81), B – Črešnjevec (Cat. No. 89)



Figure 24. A – basic design of an ash chest lid on a block of marble, Črešnjevec (Cat. No. 109); B – sunken underside of an ash chest lid, Veliko Tinje (Cat. No. 117)

we presume this already occurred during the quarry phase. This is clearly visible in the chests of the second form, many of which survive in the quarry state. In these, the inscription panels consistently have frames that are moulded on all four sides. The lateral decoration panels of the front rarely have moulded frames, mostly these frames are simple and flat. The upper sides of the frames in the lateral panels almost always take the shape of a Norico-Pannonian volute, also unmoulded. The panels on the short sides have a simple flat frame with a single exception, which has moulded frames on the front and both short sides, with a double Norico-Pannonian volute as the upper part of the frame. This example shows the close structural relation between the sarcophagi and the ash chests.

The external structure of the chest predominantly involves a tripartite front and undivided short sides. The division of the front into a larger central inscription panel and two lateral decoration panels consistently follows the division into four equal parts – modules (Figure 25). Within this division, the two central modules are reserved for the inscription panel and the two lateral modules for the decoration panels. The size of the module is not measured, but determined by simple applied geometry, as already described for the sarcophagi. The central part that was intended for the inscription, which is the most important in the structure of the whole, extends to the boundary with the two lateral modules. Its frame may be constructed within the two central modules or reaches with the full width of the moulded frame into the lateral modules.




Figure 25. Dividing a rectangle into four equal parts (dashed line) using applied geometry (Cat. No. 80)

As opposed to the sarcophagi, the lids of the ash chests are predominantly oriented perpendicularly to their length, thereby imitating the roof of a characteristic Norican aedicula tomb (naiskos)<sup>102</sup> and rendering the ash chest a reduction of the family aedicula tomb.<sup>103</sup> The width of the gabled lid is thus greater than its depth, and the ridge is short, flat and simple. The four corner acroteria are large, but lower than the ridge. The gabled lid is plain, in the fragment from Črešnjevec<sup>104</sup> with carved tegulae and imbrices. Some lids bear sculpture in the round; the lid from Pernica<sup>105</sup> has two reclining lions and the lid from Slovenska Bistrica<sup>106</sup> a reclining male figure. The front of the lid has a central decoration field in the tympanum, which is flanked by decoration fields within the corner acroteria. Acroteria can also hold decoration fields above the short sides.

There are also simple gabled lids without acroteria, for example the lid from Ptuj (Cat. No. 81) and

<sup>&</sup>lt;sup>101</sup> Cat. No. 49.

<sup>&</sup>lt;sup>102</sup> Kremer 2001.

<sup>&</sup>lt;sup>103</sup> Djurić 2001a.

<sup>104</sup> Cat. No. 105.

<sup>&</sup>lt;sup>105</sup> Cat. No. 98.

<sup>106</sup> Cat. No. 122.

probably also the three lid fragments from Ptuj (Dominican Monastery, Cat. No. 124), Laporje (Cat. No. 122) and Videm pri Ptuju (Cat. No. 123). There is even a small group of differently sized gabled lids with a longitudinal flat ridge and four corner acroteria, such as those associated with sarcophagi, though it is not possible to determine whether they belonged to ash chests or children's sarcophagi. The decoration panels in these examples are mainly in all the acroteria, in some cases also on the vertical longitudinal edges (Figure 26).





Figure 26. Perpendicular (A) and longitudinal forms (B) of ash chest lids

#### Norico-Pannonian volute

This is one of the forms of the upper frame of the decoration panels<sup>107</sup> characteristic of the funerary monuments (aedicula tombs, stelae, sarcophagi, ash chests, altars) and partly also votive altars made in the workshops that used Eastern Alpine marble in their production. The other forms, apart from a straight upper frame, are an arcuated and a pedimental frame. Arnold Schober<sup>108</sup> saw the 'Baroque' form of the Norico-Pannonian volute as a characteristically Norican motif. Unlike Antal Hekler who associated the volute with the Celtic formal tradition,<sup>109</sup> Schober sought its origins in the shape of the fronts of the Metropolitan altars with pulvini.<sup>110</sup> He linked the emergence of the volute to the stylistic change at the turn of the 1<sup>st</sup> to the 2<sup>nd</sup> century. Balduin Saria<sup>111</sup> and Rajko Ložar<sup>112</sup> sought the origin of the motif in the same, non-Roman direction as Hekler, though Ložar connected the origins of the volute with the architectural element of a round arch. Schober dated the appearance of the volute on Norican monuments in the Trajanic period,<sup>113</sup> while later researchers<sup>114</sup> provided an array of arguments that pushed it to the Late Antonine-Early Severan period. After the publication<sup>115</sup> of an altar with a Norico-Pannonian volute from Aquincum<sup>116</sup> dat-

<sup>&</sup>lt;sup>107</sup> It is very rarely associated with the inscription panels of marble sarcophagi (one is the sarcophagus from Šid-Bjelnjača) but it is very common on the travertine sarcophagi from *Aquincum* and *Brigetio*.

<sup>&</sup>lt;sup>108</sup> Schober 1923, 230–232.

<sup>&</sup>lt;sup>109</sup> Hekler 1912, 183.

At that time, the Roman Metropolitan altars with such forms were published in Altman 1905.

Saria (1933–34) sought it with the Thracians.

<sup>&</sup>lt;sup>112</sup> Ložar (1934) sought it deep in prehistory.

<sup>113</sup> Schober 1923, 230–231.

<sup>&</sup>lt;sup>114</sup> Cermanović 1965, 93; Kranz 1986, 111–112; Pochmarski-Nagele 1992, 188.

<sup>115</sup> Gesztelyi 1989–90.

<sup>116</sup> CIL III 3432; HD067977.

ed to CE 164, the age of the motif needed to be adapted,<sup>117</sup> while the discovery and publication<sup>118</sup> of a funerary stela from Odra near Zagreb, from the Hadrianic period, brought the emergence of the Norico-Pannonian volute chronologically very close to Schober's dating. The stylistic change that Schober referred to and with which he associated the creation of the Norico-Pannonian volute is most likely connected with the beginnings of a Greek (Thassian) workshop that operated in the Gummern quarry during the Hadrianic period (prior to CE 122).<sup>119</sup> The different uses of the volute and its formal development in the 2<sup>nd</sup> and 3<sup>rd</sup> centuries have not yet been the subject of a systematic study.<sup>120</sup>

The volute on the marble sarcophagi of Pannonia occurs almost without exception as the upper frame of the lateral front panels, only the sarcophagus from Osijek<sup>121</sup> has an arcuated upper frame in this position. The construction of the volute frame is most often derived from the combination of three aligned circles. Three circles of equal radii with centres A-B-C (Figure 27A) are aligned across the width of the panel. The two side circles define the side curves of the volute. The upper line of its central arch is defined by a circle of a double radius with its centre D located at the lowest point of the central circle, while the lower line is defined by a smaller circle with its centre D, the circumference of which is tangent to the circumferences of the two side circles. Connecting the individual segments of these circumferences creates a classic Norico-Pannonian volute (Figure 27B). This construction can be observed on the sarcophagi from Poetovio (Cat. Nos. 11, 12, 20) (Figure 28), Siscia, 122, Sirmium, 123 Šid-Beljnjača 124 and Alisca 125 Other variants of the Norico-Pannonian volute on the Pannonian marble sarcophagi with proportionally wider panels use the combination of four equal circles aligned on the upper frame (Figure 29); such construction is visible on the sarcophagi from Sirmium of the Norico-Pan-(Figure 30). The sarcophagi of the late 3rd and early 4th century 128 have a variant of the Norico-Pan-




Figure 27. Designing a Norico-Pannonian volute using a combination of three aligned circles

<sup>&</sup>lt;sup>117</sup> Kremer 2001, 19–20; Handy – Pochmarski 2014, 84.

Heger 2007; Rendić-Miočević 2013; Migotti – Šašel Kos – Radman-Livaja 2018, 85–86.

<sup>&</sup>lt;sup>119</sup> Djurić 2019.

<sup>&</sup>lt;sup>120</sup> The only existing discussion is still that by Ložar (1934).

<sup>&</sup>lt;sup>121</sup> Pochmarski 2019, 257, No. 10.

<sup>&</sup>lt;sup>122</sup> Zagreb, AMZg Inv. No. 349; Lupa 3803

<sup>&</sup>lt;sup>123</sup> Sremska Mitrovica, MS Inv. No. A388, Lupa 4342.

<sup>&</sup>lt;sup>124</sup> Sid, Gallery of Sava Sumanović, Lupa 36164.

<sup>&</sup>lt;sup>125</sup> Budapest, MNM Inv. No. 23.1849.1, Lupa 824.

<sup>&</sup>lt;sup>126</sup> Vienna, KHM Inv. No. I 162, Lupa 4353; Muzej Srema Inv. No. A977, Lupa 4341.

<sup>&</sup>lt;sup>127</sup> Budapest, MNM Inv. No. 62.84.1-2, Lupa 827; Pécs Tomb II.

Daruvar, AMZg Inv. No. KS959, Lupa 3811; Šid-Beljnjača, Gallery of Sava Šumanović Šid, Lupa 36164.




Figure 28. The analysis of the Norico-Pannonian volute on a sarcophagus (Cat. No. 12)




Figure 29. Designing a Norico-Pannonian volute using a combination of four aligned circles



Figure 30. The analysis of the Norico-Pannonian volute on a sarcophagus from Pécs (Lupa 827)

nonian volute characteristic of the Aquincum travertine sarcophagi. 129

All the ash chests from Poetovio with a tripartite front, except the small ash chest with a pedimental upper frame, <sup>130</sup> have a Norico-Pannonian volute constructed of three aligned circles in the lateral decoration panels. Their execution is frequently less precise and often unmoulded (Figure 31).

<sup>&</sup>lt;sup>129</sup> Variant 3, Pochmarski 2014.

<sup>&</sup>lt;sup>130</sup> Cat. No. 82, Šubic 153,1974.




Figure 31. The analysis of the Norico-Pannonian volute on an ash chest (Cat. No. 83)

## Sarcophagi of limestone

These are fairly regular blocks of Miocene limestone, measuring approximately 6.5 to 7 Roman feet (*pedes*) in length, 2 to 2.5 *pedes* in height and just under 3 *pedes* in width. Smaller blocks range from roughly 3.5 to 5.5 *pedes* in length. The thickness of the sides ranges between 13 and 16 cm. The size of the finished chests indicate that the basic measurement parameters were followed only approximately during production. The simple, undecorated chests most probably conformed to the actual size of the deceased. Their interior ranges between 5.5 and 6 (160 to 170 cm) in length and around 2 *pedes* (approximately 55 cm) in width (Figure 33). The lids could be either low gabled with a sharp ridge, <sup>131</sup> with corner acroteria, in one case even barrel-roofed with corner acroteria, or simple slabs. <sup>132</sup> The two-metre chests weigh up to 1800 kg, while the smaller (child) sarcophagi weigh around 1000 kg. The weight of the lids is unknown.

The chests (Figure 32) are entirely undecorated and, as revealed by some of those found *in situ*, <sup>133</sup> sunken into the ground to the level of the lid.



Figure 32. Sarcophagus with a barrel-shaped lid (PMPO RL 734)

<sup>&</sup>lt;sup>131</sup> PMPO RL 734/1.

<sup>&</sup>lt;sup>132</sup> Tušek 1986, Fig. 1.

<sup>&</sup>lt;sup>133</sup> Mikl Curk 1960–61a, 169; Tušek 1986, 343–345.




Figure 33. Diagrams showing the width, length and height of the limestone ash chests

## Ash chests of limestone

There are four positively identified ash chests made of limestone. Their chests are undecorated. The lids either extend beyond the edges or are flush with them, they are gabled with a sharp longitudinal ridge, a smooth surface and some with four plain corner acroteria. Part of such an ash chest is also the unusual undecorated lid from Hajdina (Cat. No. 129), which perpendicularly combines two gabled roofs with a flat ridge, resulting in a cross-gabled lid with four shared acroteria (Figure 34).



Figure 34. Lid of an ash chest from Hajdina (Cat. No. 129)

## **ICONOGRAPHY**

## Sarcophagi

The surprisingly substantial number of surviving sarcophagi – complete and even more fragments - from Poetovio and its territory, amounting to 41 in total, bear a relatively sparse yet quite diverse decoration. Exceptional among them is the only known frieze sarcophagus in Pannonia, depicting a banquet under grape vine. 134 Also remarkable is a fragment of the short side of a locally produced garland sarcophagus. 135 Of the 27 sarcophagi with a tripartite front, most are in the quarry phase of production (at least 8 or 30%), with the unfinished decoration of the lateral panels. In the lateral front panels, two sarcophagi depict the deceased and two show mourning erotes, are motifs that are in Pannonia most commonly found on the travertine sarcophagi of the Aquincum and Brigetio productions. <sup>138</sup> They are also known on several Pannonian marble sarcophagi. <sup>139</sup> Other motifs appear only in single instances, namely Season personification, <sup>140</sup> nude hero <sup>141</sup> and female servant. <sup>142</sup> These are similar to the array on the Norican aedicula tombs. 143 The more richly decorated sarcophagi also have decorated short sides. One sarcophagus has a Dionysian motif of a kantharos with two grape vines and two panthers, 144 one has the motif of Eros(?) and Psyche, 145 one a single eros<sup>146</sup> and one a pair of erotes holding an unidentified object.<sup>147</sup> On the 13 surviving lids, the most common motif is the acroterial depiction of the Seasons, busts of youthful personifications with attributes (4 or 31%), <sup>148</sup> with one example also holding the portrait of the deceased. <sup>149</sup> A single example has a gorgoneion in the triangular pediment of the lid. 150

#### Ash chests

The ash chests with a tripartite front, which were the only ones to be decorated, include 15 (43%) in the quarry phase of production, i.e. with unfinished decoration. Of the decorated ash chests, the predominant reliefs on the lateral panels of the front show the portraits of the deceased (11 or 31%), followed by mourning erotes (6 or 17%), Season personification are rare<sup>151</sup> (2 or 6%), while

<sup>&</sup>lt;sup>134</sup> Cat. No. 1; for an attempt at a 'Christian' interpretation of the depiction, see Šmid 2020.

<sup>135</sup> Cat. No. 22.

<sup>136</sup> Cat. Nos. 10, 20.

<sup>&</sup>lt;sup>137</sup> Cat. Nos. 3, 6.

<sup>&</sup>lt;sup>138</sup> See Djurić 2024.

<sup>139</sup> Deceased: Daruvar, Sisak, Šid, Pécs; erotes: Sremska Mitrovica, Pécs, Kostolac (unpublished).

<sup>&</sup>lt;sup>140</sup> Spring: Cat. No. 11.

<sup>&</sup>lt;sup>141</sup> Cat. No. 9.

Veliko Tinje (Cat. No. 19); the servant motif is also known on a sarcophagus from Sisak (Lupa 3803).

<sup>&</sup>lt;sup>143</sup> For the motifs on the tombs, see Walde 2005.

<sup>&</sup>lt;sup>144</sup> Cat. No. 17; for the motif, see Djurić 2020.

<sup>&</sup>lt;sup>145</sup> Cat. No. 11.

<sup>146</sup> Cat. No. 18.

<sup>&</sup>lt;sup>147</sup> Cat. No. 10.

<sup>&</sup>lt;sup>148</sup> Cat. Nos. 34, 30, 33, 40; such busts with attributes are on a sarcophagus from Szekszárd (MNM), which has only the attributes – baskets – depicted in the rear acroteria. The acroterium built into the church in Spodnja Polskava (Cat. No. 32) shows a Hora.

<sup>149</sup> Cat. No. 28.

<sup>150</sup> Cat. No. 30.

<sup>151</sup> Cat. Nos. 66, 59.

there are single examples with an 'Attis' or sad Easterner<sup>152</sup> and a Dionysian kantharos with vine.<sup>153</sup> On the short sides, the chests very frequently have the Dionysian motif of a kantharos with a pair of grape vines (5 examples), combined with a panther<sup>154</sup> or an eros and peacock<sup>155</sup> on the opposite short side, there is one example with a garland<sup>156</sup>, another example with an exceptional mythological scene depicting Theseus abandoning Ariadne on Naxos,<sup>157</sup> which is likely combined with the triumph of Dionysus on the opposite side and, finally, one example that has the portraits of the deceased on one and servants around a table on the other short side.<sup>158</sup>

The lids were primarily reserved for the portraits of the deceased. The 36 surviving lids include 14 (39%) that feature half-length depictions of the deceased in the pediment, rendering these ash chests essentially family tombs (for cremation burials). A special group of lids has the Dionysian motif of a kantharos from which two grape vines grow (3 or 8%) in the pediment, though their fragmentary state hinders the identification of potential acroteria. Other motifs found in the pediments include a Triton with a pair of dolphins, as well as a garland. In the acroteria, the most common motif is the personifications of the Seasons (7 or 19%) in the form of either busts or their attributes, are case also an eros holding a basket, followed by different mourning erotes (3 or 8%) and eros with a bow. Occurring as single examples are servants, dolphins, the head of an Easterner, planette and rosette. In rare cases, there are figures carved in the round on top of the lids — once a pair of lions and once a sleeping male figure. A special motif on both lids and chests is the stylised depiction of an ascia, in one case combined with a libella on the opposite short side.

```
Dravinjski vrh, Cat. No. 57; for the motif, see Cambi 2021.
```

<sup>&</sup>lt;sup>153</sup> Varaždin, Cat. No. 46.

<sup>&</sup>lt;sup>154</sup> Cat. No. 48.

<sup>&</sup>lt;sup>155</sup> Cat. No. 47.

<sup>&</sup>lt;sup>156</sup> Cat. No. 61.

<sup>&</sup>lt;sup>157</sup> Kebelj, Cat. No. 67.

<sup>&</sup>lt;sup>158</sup> Cat. No. 49.

<sup>&</sup>lt;sup>159</sup> For the concept, see Djurić 2001a.

Ptuj – Dominican Monastery (Cat. No. 125), Videm pri Ptuju (Cat. No. 124), Laporje (Cat. No. 123).

<sup>&</sup>lt;sup>161</sup> Črešnjevec, Cat. No. 106.

<sup>&</sup>lt;sup>162</sup> Slovenska Bistrica, Cat. No. 122.

<sup>&</sup>lt;sup>163</sup> Cat. Nos. 96; 126; 119; 100.

<sup>164</sup> Cat. Nos. 95, 102.

<sup>&</sup>lt;sup>165</sup> Slovenska Bistrica, Cat. No. 121.

<sup>&</sup>lt;sup>166</sup> Črešnjevec, Cat. No. 106.

Pernica (Cat. No. 98); the motif paired with Psyche is depicted in the gabled lid of a garland sarcophagus held in the Metropolitan Museum of Art in New York (see e.g. https://untappedcities.com/2022/12/14/met-museum-roman-sarcophagus/).

<sup>&</sup>lt;sup>168</sup> Pernica, Cat. No. 98.

<sup>&</sup>lt;sup>169</sup> Slovenska Bistrica, Cat. No. 122.

<sup>&</sup>lt;sup>170</sup> Pernica, Cat. No. 98.

<sup>&</sup>lt;sup>171</sup> Šmartno na Pohorju, Cat. No. 127.

Pernica, Cat. No. 98.

<sup>&</sup>lt;sup>173</sup> Slovenska Bistrica, Cat. No. 122.

<sup>&</sup>lt;sup>174</sup> Cat. Nos. 44; 93. For the motif, see Gabričević 1959; Arrigoni Bertini 2006; Ibba 2016.

<sup>&</sup>lt;sup>175</sup> Cat. No. 43. For the motif, see e.g. Buonopane 2013; Starac 2021.

## Portraits or images of the deceased

The sarcophagi of Poetovio only exceptionally hold portraits or images<sup>176</sup> of the deceased, whereas they are almost obligatory on the ash chests, occurring both on the chests proper and even more frequently on the lids. These depictions cannot be understood as portraits as defined by Bernhard Schweitzer,<sup>177</sup> but merely according to the definition by Wulf Raeck,<sup>178</sup> later elaborated by Eugenio La Rocca.<sup>179</sup> Such portraits correspond with the social role of the individuals portrayed, on the one hand, while on the other display varying degrees of assimilation<sup>180</sup> to the imperial models or the specific typological elements derived from them, such as the basic shape of the face, hairstyle and beard. As a result, many of the portraits are formally quite homogeneous and almost identical in their dress that serves as an expression of their social status.




Figure 35. Examples of full- and half-length portraits of men: a- sarcophagus Cat. No. 10; ash chests b- Cat. No. 43, c- Cat. No. 47, d- Cat. No. 49, e- Cat. No. 46, f- Cat. No. 58, g- Cat. No. 98, h- Cat. No. 100, i- Cat. No. 94, j- Cat. No. 102

For the use of the terms *Porträt / Bildnis*, see Ziegler 2000, 11–13.

<sup>&</sup>lt;sup>177</sup> Schweitzer 1963, 169.

<sup>178</sup> Raeck 2003, 29.

<sup>&</sup>lt;sup>179</sup> La Rocca 2011, 28:

<sup>-</sup> the portrait is not necessarily a faithful reproduction of reality,

<sup>-</sup> we should not confuse individuality with resemblance,

<sup>-</sup> all portraits, even those of an individual nature, must primarily represent the subject's positive social role within the community; in this sense, it is not sufficient to simply reproduce the individual's features; their body must also be portrayed with the clothes and attributes that correspond with their status.

For the concept of assimilation in Roman portraiture, see Fittschen 2011.

On the sarcophagi and ash chests of Poetovio, the deceased are depicted either in full-length form on the chests or in bust form on the lids. They all show considerable surface damage, hindering the identification of details, while some are even completely destroyed. The eight<sup>181</sup> surviving fulllength portraits of men (Figure 35) show them wearing the same garments: a knee-length tunic with long sleeves (tunica manicata)<sup>182</sup> and a military cloak (sagum)<sup>183</sup> fastened on the right shoulder with a disc brooch. The cloak drapes in an arc across the chest and left shoulder, falling in folds over the bent left arm. 184 The tunics are belted at varying heights at the waist, with only one portrait (Cat. No. 49) clearly displaying a ring buckle, without a pin, <sup>185</sup> that undoubtedly belongs to a military belt (cingulum militare), 186 worn by a soldier of legio XIIII Gemina. 187 In other full-length male figures, the belts are indistinct and cannot be positively identified as military. The figures on the ash chest from Savci even have the belts hidden beneath their tunics, which, according to Hansjörg Ubl, 188 could indicate a civilian rather than a military status. The depicted dress is generally characteristic of military personnel and sometimes referred to as 'camp dress', 189 but this is not the case with the above-mentioned active soldier of legio XIII Gemina, Fannius Florentinus, portrayed on an ash chest from Velika Nedelja. 190 The male half-length portraits on the lids of ash chests are shown wearing the same garments, but in a slightly different manner. The sagum, again fastened with a brooch on the right shoulder, is pleated and thrown over the left shoulder, similarly as on numerous Imperial portrait busts.<sup>191</sup> All the men depicted on ash chests, including those on the lids, hold a scroll in their left hand, pointing to it with the fingers of their right hand. 192 The only man portraved on a sarcophagus that is dressed in the same manner as the men on the ash chests holds not a scroll, but a staff (vitis) in his right hand, which identifies him as a centurion. 193 Whereas the men on the ash chests are primarily retired soldiers who display their civilian social status with a scroll/document, the man on the sarcophagus signals his high social rank with an attribute characteristic of active mid-ranking officers, as well as certain administrative positions within the Roman society. 194

The severely damaged heads of the portrayed men hinder an accurate identification in the sense of their assimilation to specific emperors. We can only establish that they are related to the forms

One on the sarcophagus with Cat. No. 10 and seven on ash chests: Cat. Nos. 43, 46, 47 (two portraits), 48, 49, 54 and 58

<sup>&</sup>lt;sup>182</sup> For the tunic, see Pausch 2003 and Rothe 2012, 145–150.

<sup>&</sup>lt;sup>183</sup> For the history of research and the main literature, see Pochmarski 2004, Rothe 2012.

The exception is the portrait on an ash chest held in Varaždin (Cat. No. 46), in which the individual is shown with the left arm extended along the body and consequently a freely falling cloak.

The literature on ring buckles is vast and given in von Schnurbein 1995, while Coulston (2007) published an exhaustive list of literature regarding the depictions of such buckles.

For the military belts, see Hoss 2014.

Fannius Florentinus, miles legionis XIIII Geminae; Ragolič 2023, 328.

<sup>&</sup>lt;sup>188</sup> Ubl 1969, 529.

<sup>&</sup>lt;sup>189</sup> Speidel 1976.

<sup>&</sup>lt;sup>190</sup> Erna Diez (1948, 158), who was the first to describe the soldier in greater detail, saw a sword in his left hand, with the right hand resting on the hilt. In addition to the sword, Ortolf and Friederike Harl (Lupa 3781) also see a shield and a helmet on his head, all of which Anja Ragolič (2023, 327) also accepted. The relief, however, is severely damaged and only the sword can be identified.

E.g. on Hadrian's bust from his villa at Tivoli, which is kept in the British Museum (Inv. No. 1805, 0703.95).

The man portrayed on an ash chest from Varaždin (Cat. No. 46) may hold the scroll in his right hand, while his left hand is lowered beside the body. For the scroll and the pointing gesture, see Grüll *et al.* 2023; Grabher 1991; Hainzmann 1991; Walde 2005, 66–71.

<sup>&</sup>lt;sup>193</sup> Ubl 1969, 416-420; Ward 2017.

<sup>&</sup>lt;sup>194</sup> Ward 2012, 30.

of Imperial portraits of the 3<sup>rd</sup> century beginning with the Emperor Caracalla. Roughly resembling this emperor is the portrait on the lid of the ash chest from Ptuj-Bolnišnica<sup>195</sup> (Figure 35j), with his slightly curled hair and a short beard. Other portraits feature short hairstyles and mostly clean-shaven faces, echoing the portraits of the barracks emperors of the 3<sup>rd</sup> century.

The male child figures wear the same garments as their fathers, though the cloaks are longer and reach to the mid-calf. Some hold attributes in their right hand that are damaged beyond identification.

The rare servants-slaves (delicati)<sup>197</sup> are dressed in either belted or unbelted tunics with long sleeves.

The female portraits (Figure 36) include some full-length depictions, though most are half-length portraits on the lids of ash chests and one in the acroterium of a sarcophagus lid. 198 All the women wear tunics, while the poor condition of the portraits prevents us from identifying the undergar-




Figure 36. Examples of full- and half-length portraits of women: ash chests a- Cat. No. 43; b- Cat. No. 49, c- Cat. No. 95, d- Cat. No. 100, e- Cat. No. 103, f- sarcophagi Cat. No. 28, g- Cat. No. 103, h- Cat. No. 95, i- Cat. No. 103

<sup>&</sup>lt;sup>195</sup> Cat. No. 102.

See the depiction on the right short side of the ash chest from Velika Nedelja (Cat. No. 49).

On the left short side of the ash chest from Velika Nedelja (Cat. No. 49) and the right acroterium of the ash chest lid from Pernica (Cat. No. 98).

<sup>198</sup> Cat. No. 28.

ments. The tunic reaches to the ankles and its long sleeves (tunica manicata) are sometimes covered by a cloak and other times exposed. Of the cloaks, we can identify the Roman palla<sup>199</sup> in at least three portraits,<sup>200</sup> which is shorter than the tunic and worn asymmetrically with long vertical folds on the left side. Most women, however, are portrayed in long, symmetrically worn and likely locally made rectangular cloaks with a thick border that frames and emphasises the uncovered chest and head. A particularly rich and heavy version of such a cloak appears in the bust portrait in the lid acroterion of the sarcophagus for Publius Aelius Vitalis (Cat. No. 28). Girls are portrayed in the same clothes and sometimes also wear short necklaces of large beads, similarly as adult women.

The women's hairstyles are better preserved that those of men and can be sufficiently accurately identified at least in silhouette. The most clearly identifiable are those that imitate the imperial hairstyles from the second quarter of the 3<sup>rd</sup> century, from Sallustia Orbiana to Herennia Etruscilla. These show the *Scheitelfrisur*, with long hair parted and combed back to leave the ears exposed, gathered at the nape into a wide, flat mass (sometimes braided, other times placed in a net), then secured at the crown to create what appears from the front as a low, flat bulge.<sup>201</sup> A few examples are modelled on the *Helmfrisur* of Iulia Domna,<sup>202</sup> while one<sup>203</sup> shows a melon coiffure with loose hair gathered at the nape, resembling that of Iulia Avita Mamaea.<sup>204</sup>

Four women are portrayed with headwear. The ash chest with Cat. No. 43 and the ash chest lid with Cat. No. 94 show a woman in a bonnet of Type H 7 according to Rothe,<sup>205</sup> the woman on the ash chest lid with Cat. No. 95 wears a bonnet of Type H 3, while the woman on the lid of an ash chest built into the south wall of the church in Črešnjevec<sup>206</sup> has turban-like headdress (possibly H 6 according to Rothe).

A particular feature of the family portraits on the lids of Poetovio ash chests is the generational and status differences among the portrayed female family members, which are reflected partly in their dress but primarily in their hairstyles. The hairstyles of three generations of women (grand-mother, mother, daughter) correspond to the styles characteristic of specific periods and are tied to their age and social status. Their chronological range extends from the *Helmfrisur* of the early 3<sup>rd</sup> century, to the *Scheitelfrisur* of the second quarter of the 3<sup>rd</sup> century and the hairstyles from the second half of the 3<sup>rd</sup> century.<sup>207</sup>

There are also three depictions of women as servants-slaves (Figure 37), which are very similar to one another. The best-preserved is the servant in the lateral front panel of the sarcophagus chest

<sup>&</sup>lt;sup>199</sup> For its use in Pannonia and the differentiation between *palla* and a local rectangular cloak, see Rothe 2011, 191–193.

Depiction in the left short side of the ash chest from Velika Nedelja (Cat. No. 49) and the lids of the ash chest from Pernica (Cat. No. 98) and that from Ptuj/PMPO RL 748 (Cat. No. 95).

Such hairstyles can be seen on the woman portrayed on the ash chest lids from Slivnica pri Mariboru (Cat. No. 99), Črešnjevec (Cat. No. 103), on the ash chest with Cat. No. 43, on the lids with Cat. Nos. 95 and 96, as well as the sarcophagus acroterium with Cat. No. 28. A similar hairstyle on the roughly carved figure on the sarcophagus fragment with Cat. No. 20 is later and dates to the second half of the 3<sup>rd</sup> century.

Ash chests with Cat. Nos. 61, 98 and 100.

<sup>&</sup>lt;sup>203</sup> On the ash chest with Cat. No. 49.

The damaged condition of the portraits prevents us from identifying possible depictions of wigs that were popular in that period (Ackers 2019).

<sup>&</sup>lt;sup>205</sup> Rothe 2012.

<sup>&</sup>lt;sup>206</sup> Cat. No. 103.

Examples of such female portraits of three generation are known, for example, on the sepulchral relief held in the Museo Nazionale Romano (Buccino 2011, 376, Fig. 10). On the ash chests of Poetovio, they are shown on the lids with Cat. Nos. 94, 98 and 102, all from the 3<sup>rd</sup> century.




Figure 37. Depictions of female servants: a - Cat. No. 19, b - Cat. No. 48, c - Cat. No. 98

from Veliko Tinje.<sup>208</sup> She is dressed in an ankle-length tunic with short sleeves and over it a *stola*, which is slightly shorter and girt below the breast, and has a melon coiffure. The servant on the left short side of an ash chest from Velika Nedelja<sup>209</sup> has a similar dress and hairstyle. The relief of the third servant, depicted in the left *acroterium* of an ash chest lid from Pernica,<sup>210</sup> is severely damaged, but shows the same features as the first two.

### The Seasons – Tempora Anni

The Seasons are depicted as personifications on the chests and even more frequently on the lids of both sarcophagi and ash chests (Figure 37). Some of them are severely damaged, but all appear to be shown as boys or young male (*erotes* and *genii*) *Tempora Anni* – *Kairoi* figures<sup>211</sup> rather than female Horae.<sup>212</sup>

There is a single relief with a nude winged and youthful *genius* of a Season,<sup>213</sup> depicted in the left front panel of a sarcophagus chest from Ptuj, with a floral garland held diagonally across his upper body. This figure may be interpreted as the genius of Spring, though it could also be an *eros* holding a garland, such as are known on the Metropolitan sarcophagi.<sup>214</sup> The motif of a garland held across

<sup>&</sup>lt;sup>208</sup> Cat. No. 19.

<sup>&</sup>lt;sup>209</sup> Cat. No. 48.

<sup>&</sup>lt;sup>210</sup> Cat. No. 98.

<sup>&</sup>lt;sup>211</sup> Boschung 2013; Abad Casal 1990.

<sup>&</sup>lt;sup>212</sup> Machaira 1990; 2009; a Hora is only depicted in the acroterium from Spodnja Polskava (Cat. No. 32).

<sup>&</sup>lt;sup>213</sup> Cat. No. 11; Katarina Šmid (2020) identifies the figure as an eros.

A sarcophagus held in the Louvre, Paris, MA 1033 (Robert 1897, 48–51, Fig. 35; Koch – Sichtermann 1982, 143) has two corner erotes with garlands who are not the personifications of Spring, similarly as on the sarcophagus from Naples, Sta Restituta (Kranz 1984, 195, No. 39). The genius with a garland on a sarcophagus held in the Palazzo Giustiniani (Kranz 1984, 221, No. 134) is undoubtedly the personification of Spring. A garland shown diagonally across the chest is also depicted with the associated Victoriae, for examples on a sarcophagus held in the Vatican, Museo




Figure 38. Representations of the Seasons: a - sarcophagi Cat. No. 11, b, c - Cat. No. 30; ash chests d - Cat. No. 59, e - Cat. No. 33, f, g - Cat. No. 96, h - Cat. No. 102

the chest is not very common, but does appear on Metropolitan sarcophagi that undoubtedly served as the model for this relief. The motif is also exceptional on Norican tombs, known in a single relief from Enns.<sup>215</sup> Most Metropolitan sarcophagi with such motifs are dated to the late or post-Gallienic period, which would also be the likely time frame for the sarcophagus from Ptuj. We should add that the stride of the genius of Spring from Ptuj with crossed legs is characteristic of many figures depicted on the sepulchral monuments of Noricum and is generally dated to a time after the first quarter of the 3<sup>rd</sup> century.<sup>216</sup>

Two youths holding a thyrsus<sup>217</sup> in the right or the left hand are found in the right and the left front panels, respectively, of two ash chests.<sup>218</sup> *Thyrsi* are also held by the half-length figures in the *acroteria* of the lid of another ash chest,<sup>219</sup> which are heavily damaged. These thyrsi have different tips; the one in the left *acroterium* is made up of flowers, the one in the right *acroterium* has wheat ears, while those on the chests are not clearly identifiable. It seems evident that these attributes identify the half-length figures on the lid as Season personifications, more precisely Spring and Summer. It is also clear that the rods with vegetal terminals can be seen as not true *thyrsi*. This is particularly ap-

Gregoriano Profano, Inv. No. 10411 (Kranz 1984, 202, No. 62).

Eckhart (1976, No. 67 Pl. 19) sees the relief as a personification of Spring, while Pochmarski (1983–84) interprets it as an eros with a garland.

<sup>&</sup>lt;sup>216</sup> Pochmarski-Nagele 1992; Šmid 2020.

For the thyrsus, see Reinach 1904; Olszewski 2019.

<sup>&</sup>lt;sup>218</sup> Cat. Nos. 66, 59.

<sup>&</sup>lt;sup>219</sup> Cat. No. 96.

parent in the depiction of the youth on the ash chest, though the lower part of this relief is broken off and other attributes (panther, *kantharos*) that would identify the figure as Dionysus/Bacchus/Liber Pater are missing. With rare exceptions on sarcophagi,<sup>220</sup> gods are not depicted on the known sepulchral monuments. It would seem that shaping the *thyrsus* tips as the attributes of the Seasons is a distinctive feature of the Poetovio workshops, and the use of the attributes of the Seasons in thyrsus form underlines the connection between the Seasons and the Dionysian ideology.

The half-length depictions of youths in the *acroteria* are often accompanied by Season attributes in baskets, namely flowers, wheat ears, grapes and other fruit. Examples include Spring and Summer in the *acroteria* of a sarcophagus lid from Ptuj, <sup>221</sup> Spring in an *acroterium* from Miklavž na Dravskem polju<sup>222</sup> and another Spring on an acroterium fragment held in Universalmuseum Joanneum. <sup>223</sup> The genius of Spring from Ptuj wears a cloak fastened on the right shoulder, leaving his left shoulder bare, whereas Spring from Miklavž is in a tunic. <sup>224</sup> The depictions of all four genii without attributes are in the *acroteria* of three ash chest lids in the Pokrajinski muzej Ptuj – Ormož, <sup>225</sup> which also houses an acroterium fragment with such a depiction. <sup>226</sup> Two ash chest lids from Ptuj only bear the attributes as *pars pro toto* representations of the Seasons. <sup>227</sup> The female bust<sup>228</sup> with a high bun on the crown of her head, wearing a *peplos* fastened at the left shoulder and draped across her left breast so as to leave the right breast exposed (Figure 39), is similar to the personification of Winter in the relief of the Artemis cycle in the theatre of Hierapolis. <sup>229</sup> This figure represents a H*ora*, who cannot be more precisely identified given the absence of attributes. Three depictions of Horae are known in the *acroteria* of ash chest. <sup>230</sup>




Figure 39. Hora, Spodnja Polskava Cat. No. 32

<sup>&</sup>lt;sup>220</sup> E.g. the sarcophagus fragment held at Vid near Metković; Cambi 2010, 134, No. 185.

<sup>&</sup>lt;sup>221</sup> Cat. No. 30.

<sup>&</sup>lt;sup>222</sup> Cat. No. 33; Pahič 1977a, 51.

<sup>&</sup>lt;sup>223</sup> Without inv. no.; Cat. No. 40; Lupa 16580.

Dressed in both tunic and cloak are the genii on the sarcophagus lid from Szekszárd; Koch – Sichtermann 1982, 327.

<sup>&</sup>lt;sup>225</sup> Cat. Nos. 100, 119, 126.

<sup>&</sup>lt;sup>226</sup> Cat. No. 34.

<sup>&</sup>lt;sup>227</sup> Cat. No. 95 and on one of the lids unearthed at Bolnišnica Ptuj (Cat. No. 102). The rear acroteria of the sarcophagus from Szekszárd only depict baskets.

The piece built into the church in Spodnja Polskava (Cat. No. 32) is most likely the acroterium of a sarcophagus lid.

<sup>&</sup>lt;sup>229</sup> Benson 2014, 16–17, Fig. 23.

<sup>&</sup>lt;sup>230</sup> Cat. No. 119.

There is a single example showing a winged boyish eros holding a basket in his hand, which can be found in the right *acroterium* of an ash chest lid<sup>231</sup> that differs in decoration from the characteristic lids of Poetovio. The surface damage prevents us from discerning further details. A formally similar eros is on the left short side of an ash chest from Savci.<sup>232</sup> Here, the eros is shown with a basket in a composition together with a peacock pecking at the contents of the basket full of wheat ears (?). This scene can be understood as the personification of Summer, which on Metropolitan sarcophagi may be accompanied by a peacock as its attribute.<sup>233</sup>

All the depictions that survive in a sufficiently good condition to allow us to identify the attributes show Spring in the left and Summer in the right front acroteria of sarcophagi or ash chests.

# Eros (and Psyche)

There is a single relief that very likely holds the depiction of Eros and Psyche, on the left short side of a sarcophagus from Ptuj.<sup>234</sup> The surviving composition suggests it is probably not the standard composition known, for example, on the Pannonian marble sarcophagi from Sremska Mitrovica<sup>235</sup> and Szekszárd.<sup>236</sup> However, the gesture of the right hand of the almost entirely missing central figure, which is placed under the chin of Psyche and is identical to the standard gesture of Eros when paired with Psyche, allows the hypothesis that the relief shows this precise pair.

Eros is also portrayed in two acroteria of ash chest lids, one from Pernica<sup>237</sup> and the other from





Figure 40. Eros the archer: a - Pernica (Cat. No. 98; from Muchar 1844, Pl. VII 2), b - Cat. No. 105

an unknown site in Slovenia (Figure 40).<sup>238</sup> He is depicted stringing his bow, aimed at the sleeping Psyche who is absent in the relief, intending to awaken her into life,<sup>239</sup> a motif that is known, for instance, on the lid of a sarcophagus from Tarsus.<sup>240</sup> Another possibility could be that Eros is shooting at a butterfly (the soul), as shown on the right short side of a sarcophagus from Bieda (Blera).<sup>241</sup>

<sup>&</sup>lt;sup>231</sup> Lid in Slovenska Bistrica, Cat. No. 122.

<sup>&</sup>lt;sup>232</sup> Cat. No. 47.

For the motif of a peacock on the Seasons sarcophagi, see Kranz 1984, Note 559, and p. 196, No. 41, Pl. 26.2 (sarcophagus in Museo di Ostia Antica, Inv. No. 126).

<sup>&</sup>lt;sup>234</sup> Cat. No. 11.

<sup>&</sup>lt;sup>235</sup> Vienna, KHM Inv. No. I 162; Koch – Sichtermann 1982, 330.

<sup>&</sup>lt;sup>236</sup> Budapest, MNM Inv. No. 23.1849.1; Koch – Sichtermann 1982, 327.

<sup>&</sup>lt;sup>237</sup> Pernica, church of St Margaret of Antioch, Cat. No. 98; Pochmarski 2015, 217, Fig. 6.

<sup>&</sup>lt;sup>238</sup> Joanneum, storage; Cat. No. 105.

<sup>&</sup>lt;sup>239</sup> Apul. Met. 6.21.

New York, Metropolitan Museum of Art, Inv. No. 70.1; McCann 1978, 30–33, Fig. 26 (https://www.google.com/books/edition/Roman\_Sarcophagi\_in\_the\_Metropolitan\_Mus/PBstaVWigg0C?hl=en&gbpv=1).

<sup>&</sup>lt;sup>241</sup> Robert 1897, 16, Fig. 14a.

The unusual half-palmette in the opposite acroterium of the lid from Pernica, which is atypical for the Poetovio production, has a parallel on the above-mentioned sarcophagus from Tarsus.

Yet a third motif with Eros is to be found on a fragment of the left short side of a sarcophagus,<sup>242</sup> positioned centrally and *en face*. The background and context are unidentifiable due to the limited size of the fragment. This motif is unusual and previously unknown in the Norico-Pannonian production.

### Pair of erotes

The right short side of a sarcophagus fragment from Ptuj<sup>243</sup> shows the stretched leg up to the hip of a naked, winged and striding youth. It can be identified as one of a pair of youthful erotes in a heraldic pose holding an object between them.

Pairs of erotes holding a shell or a medallion with portraits sporadically occur as early as the 1<sup>st</sup> century CE on Metropolitan marble urns.<sup>244</sup> In the 2<sup>nd</sup> century, they are found holding inscription plates on both urns and front sides of sarcophagi;<sup>245</sup> there are no examples known on Pannonian marble sarcophagi. The motif is very rare in Noricum and Pannonia, only present on the short side of an ash chest made of local limestone from Sisak (Figure 41).<sup>246</sup> The fragment from Ptuj can be dated to the Severan or post-Severan period.<sup>247</sup>




Figure 41. Part of the composition with a pair of erotes (Cat. No. 11) and the complete motif on an ash chest from Sisak (Lupa 3801)

<sup>&</sup>lt;sup>242</sup> Cat. No. 18.

<sup>&</sup>lt;sup>243</sup> Cat. No. 10.

<sup>&</sup>lt;sup>244</sup> Sinn 1987, 77–78.

<sup>&</sup>lt;sup>245</sup> E.g. the sarcophagus for Titus Canius Restitutus from Aquileia (today in Grado, in front of the baptistery); Gabelmann 1973, 207, No. 13.

<sup>&</sup>lt;sup>246</sup> Migotti – Šašel Kos – Radman-Livaja 2018, 32, No. 2.

<sup>&</sup>lt;sup>247</sup> Pochmarski 2015, 219.

### Mourning erotes

Undoubtedly one of the most common motifs on Roman sepulchral monuments, especially sar-cophagi and ash chests, in Noricum also on tombs, is the mourning eros (*Graberos*, *Trauergenius*, *Éros funéraire* or *erote funerario*). He is usually shown accompanying a motif in the central panel, flanking it on both sides as a pendant of mirror images. The most widespread representation, repeated nearly to becoming trite, is that of a nude winged boy or youth with crossed legs and drooping wings, supporting himself on a lighted inverted torch, <sup>248</sup> such as is used for lighting funeral pyres. <sup>249</sup> The arm beside the torch is mostly extended along the torch and holds a hand garland, the head is tilted onto the shoulder, while the other arm is usually placed across the chest and onto the opposite shoulder, a gesture interpreted as one of mourning.

The mourning eros is depicted on two of the sarcophagi from Ptuj. <sup>250</sup> On both, only the lower parts of the legs and the lighted torch survive, while one also shows part of the hand garland, suggesting that we are dealing in both cases with the standard representation of a mourning eros. The depictions on ash chests present a very different picture. None shows the most common representation as described above. The closest is the depiction of erotes with uncrossed legs and a raised head, holding a garland in the hand extended along the torch. <sup>251</sup> Uncrossed legs can also be found on the erotes on another ash chest that is missing its upper part, <sup>252</sup> whereas crossed legs are visible on two other ash chests. <sup>253</sup> The greatest diversity is in the positioning of the arms, which is never repeated: one relief shows one arm bent at the elbow and supporting the head, while the elbow




Figure 42. Depiction of mourning erotes on ash chests: a - Cat. No. 44, b - Cat. No. 50, c - Cat. No. 60, d - Cat. No. 45, e - Cat. No. 105

<sup>&</sup>lt;sup>248</sup> For a description, see e.g. Birkedal Hartmann 1969, 17–18; Drack 2008, 84; Pochmarski 2020, 335.

<sup>&</sup>lt;sup>249</sup> Virgil, Aen. VI 223–225: 'Pars ingenti subiere feretro, triste ministerium, et subiectam more parentum aversi tenuere facem'.

<sup>&</sup>lt;sup>250</sup> Cat. Nos. 6, 8.

<sup>&</sup>lt;sup>251</sup> Cat. No. 50.

<sup>&</sup>lt;sup>252</sup> Cat. No. 51.

<sup>&</sup>lt;sup>253</sup> Cat. Nos. 43, 44.

is resting on the opposite hand that is placed on the torch;<sup>254</sup> one relief shows both arms leaning onto the inverted torch, with the head resting on the hands;<sup>255</sup> another relief shows an eros with a raised head and spread wings supporting himself on the torch, while the other hand with a pruning knife (*falx*) at his side.<sup>256</sup> This variety of depictions indicates several different models used in the Poetovio workshops (Figure 42).

There is a single instance of an eros holding a raised torch,<sup>257</sup> which is positioned diagonally across his chest; it is depicted in the left acroterium of an ash chest lid fragment from Črešnjevec.<sup>258</sup> In Slovenia, such motifs are also known on a sarcophagus from Nova cerkev near Celje<sup>259</sup> and on Norican tombs.<sup>260</sup>

All the erotes discussed here have a childlike or early youthful appearance, which Pochmarski<sup>261</sup> attributes to the Antonine period. Only the eros from Črešnjevec is later and was likely created in the Severan period at the earliest.

### Attis or the mourning shepherd

The reliefs include one example, surviving on a poorly preserved right front panel of an ash chest,<sup>262</sup> of a clothed youthful figure leaning on a *lagobolon-pedum* (Figure 43), such as is commonly identified as Attis (*Attis tristis*).<sup>263</sup> Doubts regarding the correct identification of such figures as Attis were raised primarily by Nenad Cambi,<sup>264</sup> who instead termed it a 'sad Easterner', a defeated barbarian standing next to a trophy (without a *pedum*) or an Oriental shepherd (with a *pedum*). It is therefore more appropriate to change the conventional identification as Attis to that of the mourning *shepherd*.



Figure 43. The depiction of 'Attis' on an ash chest from Dravinjski vrh (Cat. No. 56)

<sup>&</sup>lt;sup>254</sup> Cat. No. 44.

<sup>&</sup>lt;sup>255</sup> Ptuj, Dominican Monastery, Cat. No. 60.

<sup>&</sup>lt;sup>256</sup> Cat. No. 44.

<sup>&</sup>lt;sup>257</sup> The raised torch is perceived in the context of a wedding or celebration.

<sup>&</sup>lt;sup>258</sup> Pahič 1977a, 46.

<sup>&</sup>lt;sup>259</sup> Visočnik 2014, 359–360, with an erroneous interpretation of the figural depictions.

Examples gathered in Drack 2008, 100–104.

<sup>&</sup>lt;sup>261</sup> Pochmarski 1987; 1998.

<sup>&</sup>lt;sup>262</sup> Dravinjski vrh, church of St John the Baptist, Cat. No. 57.

<sup>&</sup>lt;sup>263</sup> Vermaseren 1966.

<sup>&</sup>lt;sup>264</sup> Cambi 2003; 2021.

### Mythological motifs

Mythological motifs, which are so characteristic of the Norican tombs and aedicular stelae, <sup>265</sup> are extremely rare on the surviving sarcophagi and ash chests of Poetovio. They are considerably more numerous on the Pannonian marble sarcophagi that were made in the same workshops as those from Ptuj, bearing the motifs such as Apollo and Marsyas, <sup>266</sup> Ganymede and the eagle, Leda and the swan, Perseus and Medusa, Iphigenia in Tauris, <sup>267</sup> Apollo and Daphne, as well as Heracles and Hesione. <sup>268</sup>

Built into the southwest corner of the church of St Margaret of Antioch in Kebelj, near Oplotnica, is a fragment of the lower part of an ash chest<sup>269</sup> that holds a figural relief on the right short side (Figure 44). It depicts a female figure reclining against a rock, lying on her side and back with her head on the right, supporting her upper body on her left elbow, her bent right leg placed in front of the extended left leg. The body is preserved to the level of the left shoulder. She is wearing a cloak that covers her left shoulder, envelops her left arm and continues down her body so as to cover the legs with the exception of the right foot. The left third of the relief shows a pair of bare male legs surviving to knee height and striding toward the right. Behind his left leg is a narrow flat object, positioned diagonally to the leg, which can be identified as a ship gangway. The bottom part of the relief is occupied by an element resembling a horizontal palm frond. The remains of the relief can be identified as part of the motif of Theseus abandoning the sleeping Ariadne on the island of Naxos (Dia), with the 'palm frond' actually representing a stylized depiction of her bed, while the rocky background behind Ariadne represents the desolate island. This is a very rare motif in sepulchral art, known on only three Metropolitan<sup>270</sup> and one Attic sarcophagus,<sup>271</sup> while it has not



Figure 44. Theseus abandoning Ariadne on Naxos, Kebelj (Cat. No. 66)

<sup>&</sup>lt;sup>265</sup> For the motifs, see e.g. Walde 2005.

<sup>&</sup>lt;sup>266</sup> Szekszárd, Koch – Sichtermann 1982, 327; Lupa 824.

<sup>&</sup>lt;sup>267</sup> Pécs, Koch – Sichtermann 1982, 327; Lupa 827.

<sup>&</sup>lt;sup>268</sup> Migotti 2017.

<sup>&</sup>lt;sup>269</sup> Cat. No. 66; Djurić 2025.

<sup>&</sup>lt;sup>270</sup> Relief from Hadrian's villa, Musei Vaticani, Inv. No. 540; Bernhard, Daszewski 1986, 1058, No. 68, with references; garland sarcophagus (CE 140–150), New York, Metropolitan Museum of Art, 90.12; Bernhard, Daszewski 1986, 1058, No. 69, with references; Theseus sarcophagus (CE 240–250), Cliveden Estate, Buckinghamshire, NT 766179; Bernhard, Daszewski 1986, 1060, No. 92, with references.

<sup>&</sup>lt;sup>271</sup> Archaeology Museum Istanbul, Inv. No. 125; Bernhard – Daszewski 1986, 1058, No. 70 with references.

been previously recorded within the Norico-Pannonian mythological repertoire.

The same church holds another ash chest fragment,<sup>272</sup> built into the northwest corner of the bell tower (Figure 45). This lower part fragment bears a relief from the left short side of an ash chest that likely shows the triumph of Dionysus and Ariadne. Visible on the surviving relief is their two-wheel chariot drawn by two panthers.

The two fragments probably belong to the same ash chest that featured two motifs of the myth of Ariadne on its short sides. The one with Theseus represents separation, while the other, with Dionysus, symbolises the promise of a new life.



Figure 45. Chariot drawn by a female panther as part of the Triumph of Dionysus, Kebelj (Cat. No. 67)

# Dionysian motifs

These motifs, which comprise the primary attributes of Dionysus (Bacchus, Liber Pater), namely the panther, kantharos and grapevine, are quite common on the sepulchral monuments in Noricum and Pannonia of the 2<sup>nd</sup> and 3<sup>rd</sup> centuries. On the sarcophagi and ash chests of Poetovio, only one (Figure 46a) depicts the complete Dionysian motif of a kantharos with two grape vines flanked by a seated panther on either side with one paw resting on a goat drinking horn.<sup>273</sup> This motif is carved on the short side of a sarcophagus,<sup>274</sup> of which only the said short side survives that nevertheless allows for a credible reconstruction. The motif was fairly frequent in the second half of the 2<sup>nd</sup> and in the 3<sup>rd</sup> century, appearing on all forms of sepulchral monuments. On sarcophagi, it adorns the examples from Sremska Mitrovica,<sup>275</sup> Šid-Bjelnjača<sup>276</sup> and Szombathely,<sup>277</sup> though without the drinking horns. The small fragment of a seated panther, built into the wall of a passageway at Prešernova ulica 16 in Ptuj,<sup>278</sup> can probably also be attributed to such a motif, belonging to a short side of a sarcophagus. Another complete motif (without the drinking horns) is depicted

<sup>&</sup>lt;sup>272</sup> Cat. No. 67.

<sup>&</sup>lt;sup>273</sup> For the motif, see Djurić 2020.

<sup>&</sup>lt;sup>274</sup> Cat. No. 17.

Vienna, KHM Inv. No. AS I 162. Koch – Sichtermann 1982, 330; Dautova Ruševljan 1983, No. 40; Djurić 2001,
 48, Fig. 9; Lupa 4353.

<sup>&</sup>lt;sup>276</sup> Gallery of Sava Šumanović, Šid. Pop-Lazić 2008; Lupa 26164.

<sup>&</sup>lt;sup>277</sup> Szombathely, Savaria Múzeum Inv. No. 67.10.128. Erdélyi 1974, No. 74; Buócz 2003, 112, No. 107; Lupa 3387.

<sup>&</sup>lt;sup>278</sup> Unpublished; Cat. No. 71; Lupa 33313.

on the short side of an ash chest made of Neogene limestone, unearthed at Vranje near Sevnica (Figure 46b).<sup>279</sup>

Dionysian motifs can also appear in a reduced form, consisting of only some elements. A kantharos with a double grape vine is common on the short sides of ash chests (Figure 47),<sup>280</sup> in one example<sup>281</sup> combined with the motif of a standing panther holding a drinking horn on the opposite short side. The surviving lower parts of both short sides of a large marble ash chest from Zgornji Breg in Ptuj<sup>282</sup> bear the same motif of a kantharos with a double grape vine, while a kantharos with





Figure 46. Dionysian motifs: a - Ptuj (Cat. No. 17), b - Vranje (Lupa 1653)




Figure 47. Dionysian motif of vines growing from a kantharos: a - Savci (Cat. No. 47), b - Ptuj (Cat. No. 48)

<sup>&</sup>lt;sup>279</sup> Graz, Joanneum Inv. No. 28. Hoffiller – Saria 1938, No. 31; Modrijan – Weber 1979–81, 48, No. 28; Koch – Sichtermann 1982, 306; Hudeczek 2004, No. 7; Pochmarski 2014b, 362; Visočnik 2017, 442, No. 449; Lupa 1653.

Ash chest reworked into a wash basin, in the Minorite Monastery in Ptuj, Cat. No. 48; Djurić 2023; ash chest from Savci, Cat. No. 47; Modrijan – Weber 1979–81, 94; Hudeczek 2004, No. 8; Lamut 2013; Lamut 2015; Lupa 1696.

<sup>&</sup>lt;sup>281</sup> Ash chest reworked into a wash basin, Cat. No. 46.

<sup>&</sup>lt;sup>282</sup> PMPO RL 1023, Cat. No. 52; unearthed during golf course works; Lubšina Tušek 2001, 95; Pochmarski 2014, 354,

a single grape vine occurs on the lateral front panel of an ash chest from Varaždin.<sup>283</sup>

Three front fragments of ash chest lids form a special group of motifs featuring a kantharos with a double grape vine, <sup>284</sup> on which the grape vines do not cross each other at the bottom, but grow separately and in opposite directions (Figure 48). There is also an example <sup>285</sup> that includes the golden apple of the Hesperides shown above the kantharos and grape vines. <sup>286</sup>




Figure 48. Fragments of ash chest lids with the motif of vines growing from a kantharos: a - Ptuj, Dominican Monastery (Cat. No. 125), b - Videm pri Ptuju (Cat. No. 124), c - Laporje (Cat. No. 123)

Fig. 1; Pochmarski 2015, 219; Ragolič 2023, 90-91, No. 49; Lupa 9437.

<sup>&</sup>lt;sup>283</sup> Cat. No. 46; Diez 1948, 156, No. 9; Ragolič 2023, 112–113, No. 71; Lupa 4262.

<sup>&</sup>lt;sup>284</sup> Laporje near Slovenska Bistrica (Cat. No. 123), Videm pri Ptuju (Cat. No. 124), Dominican Monastery in Ptuj (Cat. No. 125).

<sup>&</sup>lt;sup>285</sup> Cat. No. 125.

Such apples are depicted on the lid front of a marble sarcophagus from Sremska Mitrovica; Vienna, KHM Inv. No. I162; Koch – Sichtermann 1982, 330; Dautova Ruševljan 1983, No. 40; Lupa 4353.

# **CONCLUSION**

The marble sarcophagi of Poetovio are part of a large group of Pannonian marble Kastensarkophagen<sup>287</sup> produced in the quarries in the Pohorje (Smartno-Frajhajm, Hudinja above Vitanje, Crešnova above Zreče, in Slovenia) and at Gummern (Puch near Gummern, in Austria), and shipped to the Roman towns across Pannonia using the trade routes along the waterways (the Rivers Drau/ Drava and Danube). In addition to the 42 mostly fragmented sarcophagi from Poetovio, examples of these Kastensarkophagen, mostly complete, also came to light at Savaria<sup>288</sup> (Szombathely 1), Siscia<sup>289</sup> (Sisak 2), Aquae Balissae<sup>290</sup> (Daruvar 1), Mursa<sup>291</sup> (Osijek 2), Sopianae<sup>292</sup> (Pécs 4), Alisca<sup>293</sup> (Szekszárd 1), Sirmium<sup>294</sup> (Sremska Mitrovica 5), Šid<sup>295</sup> (2) and, furthest east, at Viminacium<sup>296</sup> (Kostolac 4). All these sarcophagi are closely linked to the production of other forms of marble funerary monuments, as indicated by the tripartite structure of their front sides, the specific use of the Norico-Pannonian volute (which differs from those on the Pannonian travertine sarcophagi) and the choice of the mythological and symbolic motifs. They form a homogeneous group together with the characteristically Norican marble aedicula tombs and funerary stelae, with the main production centre associated with the Gummern quarry. However, there are also several exceptions that significantly deviate from this homogeneous group and demonstrate the diversity in the production of marble sarcophagi, which is possibly related to the customers and/or the origin of the craftsmen. One such example is the frieze sarcophagus from Ptuj, 297 whose lower section is broken off and the exact type thus unclear. Other examples include the architectural-columnar sarcophagi from Sremska Mitrovica, namely the Seasons sarcophagus<sup>298</sup> and the sarcophagus with Apollo and Marsyas.<sup>299</sup> Another example is the fragment of a garland sarcophagus(?)<sup>300</sup> from Ptuj that has a high base characteristic of architectural sarcophagi. All of these sarcophagi were richly painted, as can most clearly be observed on the sarcophagus from Sremska Mitrovica now held in Vienna<sup>301</sup> and the sarcophagi from Szekszárd<sup>302</sup> and Pécs,<sup>303</sup> both held in Budapest. Forming a specific group are the limestone sarcophagi with simple, undecorated chests and gabled lids with corner acroteria; these were buried in the ground so as to leave only the lid visible above ground.

Whereas the marble sarcophagi modelled the sarcophagi from Italy in their basic form and mainly

<sup>&</sup>lt;sup>287</sup> In Italian sarcofago a cassapanca.

<sup>&</sup>lt;sup>288</sup> Buócz 2003, 112–113, No. 107.

<sup>&</sup>lt;sup>289</sup> Migotti – Šašel Kos – Radman-Livaja 2018, 20–23, Nos. 9–10.

<sup>&</sup>lt;sup>290</sup> Migotti – Šašel Kos – Radman-Livaja 2018, 117–119, No. 1.

<sup>&</sup>lt;sup>291</sup> Djurić – Filipović – Müller 2009, 12, 14.

<sup>&</sup>lt;sup>292</sup> Burger 1991, No. 101.

<sup>&</sup>lt;sup>293</sup> Burger 1991, No. 97.

<sup>&</sup>lt;sup>294</sup> Dautova Ruševljan 1983.

<sup>&</sup>lt;sup>295</sup> Dautova Ruševljan 1983, No. 41; Pop Lazić 2008.

<sup>&</sup>lt;sup>296</sup> Three unpublished sarcophagi held at the site, one sarcophagus held in the Narodni muzej in Požarevac, Koch – Sichtermann 1982, 334.

<sup>&</sup>lt;sup>297</sup> PMPO RL 447, Cat. No. 1.

<sup>&</sup>lt;sup>298</sup> Zagreb, AMZg Inv. No. 153.

<sup>&</sup>lt;sup>299</sup> Sremska Mitrovica, MS Inv. No. A12.

<sup>&</sup>lt;sup>300</sup> PMPO G 2060 PL, Cat. No. 22.

<sup>&</sup>lt;sup>301</sup> Vienna, KHM Inv. No. AS I 162.

<sup>&</sup>lt;sup>302</sup> Budapest, MNM Inv. No. 23.1849.1.

<sup>&</sup>lt;sup>303</sup> Budapest, MNM Inv. Nos. 62.84.1-2, 62.85.1-2.

differed from them in the flat ridge of the gabled lid, the ash chests are a creation of the workshops of Poetovio. Formally, this is evident in their lids that have the ridge oriented perpendicularly to the length of the chest, forming a pediment on the front side. Spatially, this is clear from their distribution that is limited to Poetovio and its territory. Their structure shows a reduced version of an aedicula tomb and consists of a tripartite base and a gabled roof, with the portraits shifted from the absent niche to the tympanum. In addition to this numerically dominant group, there are several smaller and simple chests with the inscription panel on the front and several smaller lids with the ridge oriented lengthwise. The small undecorated marble chests without inscriptions, usually covered with a plain slab and some also with a gabled lid with corner acroteria, <sup>304</sup> are common forms of graves unearthed primarily under burial mounds, but are not closely related to the Poetovio ash chests. They should rather be viewed similarly as the undecorated chests of the limestone sarcophagi sunken into the ground.

The main and predominant groups of marble sarcophagi and ash chests are similar in structure, whereas in terms of execution, the sarcophagi excel in the quality of decorative elements (moulding, volutes), reliefs and portraits of the deceased. The iconographic programme and motifs are similar or at least closely related in both groups, but possibly more varied on sarcophagi, though there are also some ash chests that hold exceptional depictions, such as the sleeping Ariadne on Naxos. Considering their dating, predominantly from the Severan period onward, it is understandable that most motifs are tied to the Dionysian ideology, with the canonical depictions of the Seasons representing the cycle of life, the symbolic motifs featuring Dionysian attributes and the mythological motifs that metaphorically promise a new life, such as Ariadne's union with Dionysus.

The rare inscriptions mentioning the customers of the Poetovio sarcophagi and ash chests, as well as some of their portraits provide only limited information on this subject and we can only observe that the sarcophagi were mostly commissioned by members of the higher, the ash chests by those of the lower provincial elite. Inscriptions on sarcophagi, for example, name members of the Roman equestrian Aelii family: Publius Aelius Marinus, Publius Aelius Marcianus, decurio of the Poetovio colony, and Publius Aelius Vitalis. Other examples are the sarcophagus depicting a centurion and possibly the ash chest with a Greek inscription for Demetrios of Bithynia, centurion and member of the Roman equestrian order. The few functions mentioned in the surviving inscriptions on ash chests only include two soldiers of *legio XIIII Gemina*.

The suggestion that some customers were crypto-Christians, as put forward by some authors in connection with the frieze sarcophagus and its depiction of a banquet under grape vine, is entirely speculative and unsupported by any concrete evidence, hence purely a matter of belief.<sup>312</sup>

An example of the highest quality is the limestone ash chest (Cat. No. 130) found at Obrež near Središče ob Dravi and is kept in the PMPO RL 686; Bratanič 1954.

<sup>&</sup>lt;sup>305</sup> Šašel Kos 1993.

<sup>306</sup> Cat. No. 8.

<sup>307</sup> Cat. No. 28.

<sup>&</sup>lt;sup>308</sup> PMPO RL 883, Cat. No. 10.

<sup>309</sup> Cat. No. 63.

<sup>&</sup>lt;sup>310</sup> Jordan – Šašel Kos – Wallace 1985.

<sup>&</sup>lt;sup>311</sup> PMPO RL 36, Cat. No. 77 and RL 104, Cat. No. 49.

For such a hypothesis, see recently Šmid 2020. The only Pannonian marble sarcophagus with a very likely crypto-Christian motif appears to be that from Veliki Bastaji near Daruvar (*Aquae Balissae*) (Migotti 1996).

### REFERENCES

AV – Arheološki vestnik

CLEPann – Carmina latina epigraphica Pannonica

ČZN – Časopis za zgodovino in narodopisje

JÖh – Jahreshefte des Österreichischen archäologischen Institutes in Wien

VS – Varstvo spomenikov

#### ABAD CASAL 1990

Lorenzo Abad Casal, Kairoi/Tempora Anni, in: Lexicon Iconographicum Mythologiae Classicae 5.1, Zürich-München 1990, 891–920

ABRAMIĆ 1914

Mihovil Abramić, Archäologische Funde aus Pettau, JÖb 17, 1914, 87-150

ABRAMIĆ 1925

Mihovil Abramić, Poetovio. Fürher durch die Denkmäler der römischen Stadt, Wien 1925

ABRAMIĆ 1933

Mihovil Abramić, Opaske o nekim spomenicima staroga Poetovija, ČZN 28, 1933, 129-144

ACKERS 2019

Helen I. Ackers, The representation of wigs in Roman female portraiture of the late 2<sup>nd</sup> to 3<sup>rd</sup> century AD, BABESCH - Annual Papers on Mediterranean Archaeology 94, 2019, 211-234

ALTMAN 1905

Walter Altman, Römischen Grabaltäre der Kaiserzeit, Berlin 1905

### ARRIGONI BERTINI 2006

Maria Giovanna Arrigoni Bertini, Il simbolo dell'ascia nella Cisalpina romana, Faenza 2006

### BENSON 2014

Bailey Benson, *The creation of shared memory: the theater reliefs from Hierapolis*, Chapel Hill 2014 (Diss. University of North Carolina)

#### BERNHARD, DASZEWSKI 1986

Maria Luisa Bernhard – Wiktor A. Daszewski 1986, s. v. Ariadne. – *LIMC* III 1, Zürich - München, 1050-1070

### BEUTLER 2019

Franziska Beutler, Grabsteine recycelt – Darf man das?, in: A. Konecny, F. Humer, K. Decker (eds.), Das Carnuntiner Erdbeben im Kontext. Archäologischer Park Carnuntum. Neue Forschungen Band 14. Akten des III. Internationalen Kolloquiums veranstaltet vom Land Niederösterreich, der Archäologischen Kulturpark NÖ Betriebsges.m.b.H., dem Institut für Geodynamik und Sedimentologie der Universität Wien und der Gesellschaft der Freunde Carnuntums, Kulturfabrik Hainburg 17.–18. Oktober 2013, St. Pölten 2019, 108-111

#### BIRKEDAL HARTMANN 1969

Jörgen Birkedal Hartmann, Die Genien des Lebens und des Todes, Römisches Jahrbuch für Kunstgeschichte 12, 1969, 9-38

### **BOSCHUNG 2013**

Dietrich Boschung, Tempora anni. Personifikationen der Jahreszeiten in der römischen Antike, in: Th. Greub (ed.), Das Bild der Jahreszeiten im Wandel der Kulturen und Zeiten, München 2013, 179–200

### BRATANIČ 1952

Rudolf Bratanič, Rimske najdbe iz Poetovione, AV 3, 1952, 300-307

### BRATANIČ 1954

Rudolf Bratanič, Nove najdbe iz Ptuja, AV 5, 1954, 361-377

### **BUONOPANE 2013**

Alfredo Buonopane, Le raffigurazioni di utensili nelle iscrizioni funerarie: da immagini parlanti a simbolo, Sylloge Epigraphica Barcinonensis 11, 2013, 73-82

## BUÓCZ 2003

Terézia Buócz, Lapidarium. Savaria Múzeum, Szombathely 2003

#### **CAMBI 2003**

Nenad Cambi, Attis or someone else on funerary monuments from Dalmatia?, in: Akten des VII. Internationalen Colloquium über Probleme des provinzialrömischen Kunstschaffens, Mainz 2003, 511–520

#### **CAMBI 2010**

Nenad Cambi, Sarkofazi lokalne produkcije u rimskoj Dalmaciji (od II. do IV. stoljeća). Die Sarkophage der lokalen Werkstätten im Römischen Dalmatien, Split 2010

### **CAMBI 2021**

Nenad Cambi, Atis ili netko drugi na nadgrobnim spomenicima u Dalmaciji?, *Arheološki radovi i rasprave* 20, 2021, 173-200

### CERMANOVIĆ 1965

Aleksandrina Cermanović, Die dekorierten Sarkophage in den römischen Prowinzen von Jugoslawien, Archaeologia Iugoslavica 6, 1965, 89-103, Tab. I-XI

# CIGLER – PUKŠIČ 2022

Iva Cigler – Luka Pukšič, *Poročilo o predhodni arheološki raziskavi ... zahodnega dvorišča Dominikanskega samostana*, Ptuj 2022 (unpublished report)

### **CONZE 1875**

Alexander Conze, Römische Bildwerke einheimischen Fundorts in Österreich II, Wien 1875

### COULSTON 2007

Jon Coulston, Art, culture and service: The depiction of soldiers on funerary monuments of the 3rd century ad, in: The impact of the Roman army (200 BC- AD 476): economic, social, political, religious, and cultural aspects: proceedings of the Sixth Workshop of the International Network Impact of Empire (Roman Empire, 200 B.C.-A.D. 476), Capri, March 29-April 2, 2005, Boston 2007, 529-561

### DAUTOVA RUŠEVLJAN 1983

Velika Dautova Ruševljan, Rimska kamena plastika u jugoslovenskom delu provincije Donje Panonije, Novi Sad 1983

#### **DIEZ 1948**

Erna Diez, Die Aschenkisten von Poetovio, JÖh 37, 1948, 151-174

# DJURIĆ 2001a

Bojan Djurić, Ossuaria Poetovionensia: Iconography and structure, in: T.A.S.M. Panhuysen (ed.),

Die Maastrichter Akten des 5. Interntionalen Kolloquiums über das provinzialrömische Kunstschaffen, Maastricht 2001, 117-129

# DJURIĆ 2001b

Bojan Djurić, Production of marble sarcophagi in Poetovio, Budapest régiségei 24, 2001, 47-62

# DIURIĆ 2005

Bojan Djurić, Poetovio and the Danube marble trade, in: M. Mirković (ed.), Römische Städte und Festungen an der Donau: Akten der regionalen Konferenz, Beograd 16.-19. Oktober 2003, Beograd 2005, 75-82

# DIURIĆ 2015

Bojan Djurić, A Late Roman convivium sarcophagus from Ptuj, in: B. Porod – G. Koiner (eds.), Römische Sarkophage. Akten des internationalen Werkstattgesprächs 11. – 13. Oktober 2012, Graz (Schild von Steier, Beiheft 5), Graz 2015, 92-101

# DJURIĆ 2019a

Bojan Djurić, The Logistics behind Ancient Art. The Case of Noricum and Pannoniae, in: B. Porod – P. Scherrer (eds.), Akten des 15. Internationalen Kolloquiums zum Provinzialrömischen Kunstschaffen. Der Stifter und sein Monument, Gesellschaft – Ikonographie – Chronologie, 14. bis 20. Juni 2017, Graz / Austria, Graz 2019, 8-38

# DJURIĆ 2019b

Bojan Djurić, Kamniti nagrobni spomeniki z izkopavanj v Ljudskem vrtu na Ptuju, *Zbornik Pokra-* jinskega muzeja Ptuj – Ormož 6, Ptuj 2019, 45-58

# DJURIĆ 2020

Bojan Djurić, Bakhični motiv na sarkofagu s Ptuja, in: M. Šteiner – T. Osterman Renault (eds.), *Umetnost Ptuja in ptujski umetniki*, Ptuj 2020, 11-28

# DJURIĆ 2023

Bojan Djurić, Dionysos in the province. Dionysian motifs on Poetovian monument, in: B. Govedarica – I. Vranić – A. Kapuran (eds.), A step into the past. Approaches to Identity, Communications and Material Culture in South-Eastern European Archaeology. Papers dedicated to Petar Popović for his 78th birthday, Beograd, 315-324

# DJURIĆ 2025

Bojan Djurić, Ariadne at St Margaret's (Kebelj, Slovenia) and the promise of a new life, in: *Omnia tempus revelat. Studies on Antiquity and the Early Middle Ages. In Memory of Jaroslav Šašel, Razprave SAZU* 44, Ljubljana 2025, 97–113

# DJURIĆ – FILIPOVIĆ – MÜLLER 2009

Bojan Djurić – Slavica Filipović – Harald W. Müller, Karakteriziranje mramornih spomenika Murse, *Osječki zbornik* 29, 2009, 9-17

### DJURIĆ – HEBERT et al. 2004

Bojan Djurić – Bernhard Hebert – Christian Hinkler – Erich Hudeczek – Stephan Karl – Harald W. Müller, Marmore römischer Steinbruche und Steindenkmäler in der Steiermark und in Štajerska, Fundberichte aus Österreich 43, 2004, 365–431

# DJURIĆ et al. 2006

Bojan Djurić – Jasmina Davidović – Andreja Maver – Harald W. Müller, Stone use in Roman towns. Resources, transport, products and clients. Case study Sirmium. First report, *Starinar* 56, 2006, 103-136

# DJURIĆ – RAGOLIČ 2022

Bojan Djurić – Anja Ragolič, Rimska pepelnica iz zahodnega stolpa na Ptujskem gradu, *Poetoviona in njen ager, Archaeologia Poetovionensis* 4, 2022, 25-28

#### DRACK 2008

Anja Drack, Erotendarstellungen in Noricum, Graz 2008 (Bachelor thesis, Universität Graz)

#### ECKHART 1976

Lothar Eckhart, Die Skulpturen des Stadtgebietes von Lauriacum, CSIR Österreich III 2, Wien 1976

### ERDÉLYI 1974

Gizella Erdélyi, A római kofaragás és koszobrászat magyarországon. Budapest 1974

### FARKAS - GABLER 1994

Zoltán Farkas - Dénes Gabler, Die Skulpturen des Stadtgebietes von Scarbantia und der Limesstrecke Ad Flexum - Arrabona, Budapest 1994

#### FITTSCHEN 2011

Klaus Fittschen, Il fenomeno dell'assimilazione delle immagini nella ritrattistica romana di età imu periale, in: E. La Rocca – C. Parisi Presicce – A. Lo Monaco (eds.), Ritratti. Le tante facce del potere, Roma 2011, 247-252

#### **FULIR 1969**

Miroslav Fulir, Topografska istraživanja rimskih cesta na varaždinskom i medjimurskom području: (1960-1967), Razprave, Razred za zgodovinske in družbene vede 6, 1969, 363-431

#### **FULIR 1970**

Miroslav Fulir, Osvrt na položaj današnjeg Varaždina u nizu nekadašnjih rimskih postaja, *Godišnjak Gradskog muzeja* 4, 1970, 5-19

#### GABELMANN 1973

Hans Gabelmann, Die Werkstattgruppen der oberitalischen Sarkophage, Bonn 1973

#### GABELMANN 1977

Hans Gabelmann, Zur Tektonik oberitalischer Sarkophage, Altäre und Stelen, Bonner Jahrbücher 77, 1977, 199-244

### GABRIČEVIĆ 1959

Branimir Gabričević, Značenje ascije na antičkim nadgrobnim spomenicima u svijetlu epigrafičke analize glagola "deasciare" ("exacisclare"), Arheološki radovi i rasprave 1, 1959, 299-310

#### GARBSCH 1965

Jochen Garbsch, Die norisch-pannonische Frauentracht im 1. und 2. Jahrhundert, München 1965

#### **GESZTELYI 1989-90**

Tamás Gesztelyi, Ein dreifiguriges Votiv-Relief aus Savaria, Mitteilungen der Archaeologischen Gesellschaft Steiermark 3-4, 1989-90, 144-152

### **GRABHER 1991**

Gerhard Grabher, Die Schriftrolle auf römischen Grabsteinen in Österreich. Burgerrechtsdekret und Schwurgestus?, in: Akten des 1. internationalen Kolloquiums über Probleme des provinzialrömschen Kunstschaffens, Graz, 27.- 30. April 1989, Wien 1993, 42-56

# GRASSL 1976

Herbert Grassl, Zur metrischen Grabinschrift CIL III 5695 = 11827, Römisches Österreich 4, 1976, 49-55

### GRÜLL et al. 1976

Tibor Grüll – Nándor Agócs – János Jusztinger – Ernő Szabó, Representations of writing tools and materials on Roman funerary monuments, in: T. Grüll (ed.), Representations of writing materials on Roman funerary monuments. Text, image, mesage, Oxford 2023, 1-32

### GULIČ 2006

Andrej Gulič, *Zgodovinska podoba slovenskobistriškega Pohorja od prazgodovine do 20. stoletja*, Maribor 2006 (Bachelor thesis, Univerza v Ljubljani)

### GULIČ 2007

Andrej Gulič, Nadzor in nova arheološka odkritja ob drenažnih delih ob cerkvi sv. Petra in Pavla. Poročilo, Veliko Tinje 2007 (unpublished report)

### **GURLITT 1895**

Wilhelm Gurlitt, Römische Inschrift aus Steiermark, Mittheilungen der k.k. Central-Commision 21, 1895, 64

### **GURLITT 1901**

Wilhelm Gurlitt, Römische Inschrift aus Steiermark, Mittheilungen der k.k. Zentral-Kommision 27, 1901, 221-222

### GUTSMIEDL-SCHÜMANN 2013

Doris Gutsmiedl-Schümann, Erna Diez (1913-2001). Biographische Skizzen zu einembeschwerlichen Weg in Forschung und Lehre, in: J. E. Fries – D. Gutsmiedl-Schümann (eds.), Ausgräberinnen, Forscherinnen, Pionierinnen: Ausgewählte Porträts früher Archäologinnen im Kontext ihrer Zeit, Frauen – Forschung – Archäologie 10, Münster 2013, 255-260

### HAINZMANN 1993

Manfred Hainzmann, Schriftrolle und Schwurgestus. Neue Beobachtungen zu einem alten Bildmotiv, in: Akten des 1. internationalen Kolloquiums über Probleme des provinzialrömschen Kunstschaffens, Graz, 27.- 30. April 1989, Wien 1993, 120-146

# HANDY - POCHMARSKI 2014

Markus Handy – Erwin Pochmarski, Grabaltäre im südlichen Noricum, JÖh 83, 2014, 57-99

### HANDY - POCHMARSKI 2020

Markus Handy – Erwin Pochmarski, Die Sagumtracht in der Provinz Pannonia Superior, in I. Radman Livaja – T. Bilić (eds.): *Monumenta marmore aereque perenniora. Zbornik radova u čast Anti Rendiću-Miočeviću*, Zagreb 2020, 278-301

#### HARL 2020

Ortolf Harl, Es begann in Pettau. Erna Diez und das Steindenkmälerprojekt des Archäologischen Instituts des Deutschen Reiches, in: E. Steigberger (ed.), Von den Alpen bis ans Meer. Festschrift für Bernhard Hebert zum 60. Geburtstag, Wien 2020, 63-85

#### **HEGER 2007**

Norbert Heger, Eine Randbemerkung zum pannonisch-norischen Rahmenornament, in: V. Höck – F. Lang – W. Wohlmayr (eds.), Akten zum 2. Österreichischen "Römerstein-Treffen" 2006 in Salzburg, Wien 2007, 185-188

#### HEKLER 1912

Antal Hekler, Forschungen in Intercisa, JÖb 15, 1912, 174-196

### HOFFILLER - SARIA 1938

Viktor Hoffiller – Balduin Saria, *Antike Inschriften aus Jugoslavien*, Zagreb 1938

#### HORVAT et al. 2003

Jana Horvat – Milan Lovenjak – Andreja Dolenc Vičič – Marija Lubšina Tušek – Marijana Tomanič Jevremov – Zorka Šubic, Poetovio, Development and Topography, in: M. Šašel Kos, P. Scherrer (eds.), *The autonomous towns of Noricum and Pannonia / Die autonomen Städte in Noricum und Pannonien. Pannonia* I (Situla 41), Ljubljana 2003, 153–189

# HORVAT – DOLENC VIČIČ 2010

Jana Horvat – Andreja Dolenc Vičič, Arheološka najdišča Ptuja – Rabelčja vas, Ljubljana 2010

#### HOSS 2011

Stefanie Hoss, The Roman military belt, in: M.-L. Nosch (ed.), Wearing the Cloak: Dressing the Soldier in Roman Times, Oxford 2011, 29-44

#### HOSS 2014

Stefanie Hoss, Cingulum Militare: Studien zum römischen Soldatengürtel des 1. bis 3. Jh. n. Chr., Leiden 2014 (Diss. Universiteit Leiden)

#### **HUDECZEK 2004**

Erich Hudeczek, Die Römersteinsammlung des Landesmuseums Joanneum: ein Führer durch das Lapidarium, Graz 2004

#### IBBA 2016

Antonio Ibba, SUB ASCIA. Il simbolo dell'ascia nell'epigrafia funeraria della Sardegna romana, Sylloge Epigraphica Barcinonensis 14, 2016, 119-147

#### ILIJANIĆ 1961

Mira Ilijanić, Sarkofag Julija Viktorija Quadrata, Bulletin Zavoda za likovne umjetnosti Jugoslavenske 9, 1961, 43-48

### JARC 2006

Simona Jarc, *Izvor marmorja iz nekaterih slovenskih arheoloških najdišč*, Ljubljana 2006 (Diss. Univerza v Ljubljani)

#### **JEVREMOV 1988**

Blagoj Jevremov, Vodnik po lapidariju, Ptuj 1988

#### JJ 74

Vierundsiebzigster Jahresbericht des steiermärkisch-landschaftlichen Joanneums zu Graz über das Jahr 1885, Graz 1886

# JORDAN – ŠAŠEL KOS – WALLACE 1985

David R. Jordan – Marjeta Šašel Kos – Malcolm B. Wallace, A Greek Metrical Epitaph from Poetovio for a Soldier from Bithynia, *Zeitschrift für Papyrologie und Epigraphik* 60, 1985, 85-89

### KAJZER – LOVENJAK 2012

Mihela Kajzer – Milan Lovenjak, Črešnjevec, VS 47, 2012, 28-30

#### KARL 2013

Stephan Karl, Turris antiqua in castro Leybentz. Zur frühesten Baugeschichte der Burgenanlage Leibnitz/ Seggau im Kontext der spätantiken Ostflanke der Provinz Noricum mediterraneum, Graz 2013 (Diss. Karl-Franzens-Universität Graz)

### KLEMENC - SARIA 1936

Josip Klemenc – Balduin Saria, Archaeologische Karte von Jugoslavien. Blatt Ptuj, Beograd – Zagreb 1936

#### KLEMENC - SARIA 1939

Josip Klemenc – Balduin Saria, Archaeologische Karte von Jugoslavien. Blatt Rogatec, Beograd – Zagreb 1939

#### KNABL 1851

Richard Knabl, Inschriftliche Funde aus neuerer und neuster Zeit in und an den Gränzen des Kronlandes Steiermark, Mittheilungen des Historischen Vereines für Steiermark 2, 1851, 43-73, Taf. III

### KNABL 1855

Richard Knabl, Epigraphische Excurse, Mittheilungen des Historischen Vereines für Steiermark 6, 1855, 125-172

#### **KNABL 1856**

Richard Knabl, Unedirte Römer-Inschriften aus Steiermark, Archiv für Kunde österreichischer Geschichts-Quellen, Beilage 6, 1856, 523-532

#### KNABL 1859

Richard Knabl, Epigraphische Excurse in Jahre 1858, Mittheilungen des Historischen Vereines für Steiermark 9, 1859, 85-138

### **KNABL 1869**

Richard Knabl, Epigraphische Excurse, Mittheilungen des Historischen Vereines für Steiermark 17, 1859, 56-69

#### **KOCH 2015**

Guntram Koch, Einige Überlegungen zum Verhältnis der erhaltenen kaiserzeitlichen Sarkophage zur ursprünglichen Produktion, in: B. Porod, G. Koiner (eds.), Römische Sarkophage. Akten des Internationalen Werkstattgesprächs, 11. – 13. Oktober 2012 (Graz), Graz 2015, 144-162

### KOCH – SICHTERMANN 1982

Guntram Koch – Hellmut Sichtermann, Römische Sarkophage, Handbuch der Archäologie, München 1982

### KOROŠEC 1998

Josip Korošec, Il Kairos dei lapidari di Ptuj, Prilozi povijesti umjetnosti u Dalmaciji 37, 1998, 37-54

#### KOVÁCS 2007

Péter Kovács, Corpus Inscriptionum Graecarum Pannonicarum, Hungarian Polis Studies 15, Debrecen – Budapest 1998

### KRANZ 1984

Peter Kranz, Jahreszeiten-Sarkophage. Entwicklung und Ikonographie des Motivs der vier Jahreszeiten auf kaiserzeitlichen Sarkophagen und Sarkophagdeckeln, Die antiken Sarkophagreliefs 5.4, Berlin 1984

#### **KRANZ 1986**

Peter Kranz, Die Grabmonumente von Šempeter, BJb 186, 1986, 193-239

#### KREMER 2001

Gabrielle Kremer, Antike Grabbauten in Noricum, Wien 2001

### KRÜGER 1974

Marie-Louise Krüger, Die Reliefs der Stadtgebiete von Scarbantia und Savaria, CSIR Österreich I 5, Wien 1974

### LA ROCCA 2011

Eugenio La Rocca, Il ritratto e la somiglianza, in: E. La Rocca, C. Parisi Presicce, A. Lo Monaco (eds.), Ritratti. Le tante facce del potere, Roma 2011, 21-29

#### **LAMUT 2013**

Brane Lamut, Kopija rimske pepelnice iz Savcev v arheološki zbirki ormoškega gradu, Jubilejni zbornik ob 120-letnici Pokrajinskega muzeja Ptuj-Ormož, Ptuj 2013, 154-163

#### **LAMUT 2015**

Brane Lamut, Arheološke ostaline z območja Občine Sveti Tomaž, Zbornik Pokrajinskega muzeja Ptuj – Ormož 4, 2015, 303-327

### LAZAR 2003

Irena Lazar, Rimsko steklo Slovenije. The Roman glass of Slovenia, Ljubljana 2003

### LOŽAR 1927

Rajko Ložar, Studien zu den römischen Sarkophagen von Noricum und Pannonien (Diss. Universität Wien 1927)

### LOŽAR 1934

Rajko Ložar, Ornamenti noriškopanonske kamnoseške industrije, ČZN 29, 1934, 99-147

### LUBŠINA TUŠEK 2001

Marija Lubšina Tušek, Ptuj, arheološko območje Hajdina, golf igrišče, VS Poročila 38, 2001, 95-97

## MACHAIRA 1990

Vasiliki Machaira, Horai, in: Lexicon Iconographicum Mythologiae Classicae 5.1, Zürich-München 1990, 502–510

### MACHAIRA 2009

Vasiliki Machaira, Horai, in: Lexicon Iconographicum Mythologiae Classicae, Supplement 1, Zürich-München 2009, 286–287

#### MANDER 2012

Jason Mander, Portraits of children on Roman funerary monuments, Cambridge 2012

#### McCANN 1978

Anna Marguerite McCann, Roman sarcophagi in The Metropolitan Museum of Art, New York 1978

### **MEINECKE 2012**

Katharina Meinecke, Invisible Sarcophagi: Coffin and Viewer in the Late Imperial Age, in: S. Birk – B. Poulsen (eds.), *Patrons and Viewers in Late Antiquity*, Aarhus 2012, 83-105

### MIGOTTI 2017

Branka Migotti, Roman Sarcophagi of Northern Croatia Featuring Peculiar Iconographies, in: *Illyrica antiqua in honorem Duje Rendić-Miočević. Proceedings of the International Conference, Šibenik 12<sup>th</sup>-15<sup>th</sup> September 2013, Zagreb 2017, 499-513* 

# MIGOTTI – ŠAŠEL KOS – RADMAN-LIVAJA 2018

Branka Migotti – Marjeta Šašel Kos – Ivan Radman-Livaja, Roman funerary monuments of south-western Pannonia in their material, social and religious context, Oxford 2018

#### MIKL 1960-61a

Iva Mikl, Rimske najdbe iz Ptuja po letu 1954, AV 11-12, 1960-61, 153-186

#### MIKL CURK 1960-61b

Iva Mikl Curk, Żetale, VS 17-19/1, 1974, 163,

### MILETIĆ 2023

Karakterizacija in določanje izvora kamnin uporabljenih v grajenih strukturah mesta Municipium Claudium Celeia, Ljubljana 2023 (Diss. Univerza v Ljubljani)

#### MLINAR 2019

Janez Mlinar, Balduin Saria (1893–1974): "Ein deutschsprachiger Sohn der Untersteiermark", in: K. Hruza (ed.), Österreichische Historiker, Band 3, Wien 2019, 379-403

### MODRIJAN – WEBER 1979-81

Walter Modrijan – Eckehardt Weber, Die Römersteinsammlung des Joanneums in Eggenberger Schlosspark, *Schild von Steier* 14, 1979-81, 7-111

#### MUCHAR 1844

Albert von Muchar, Geschichte des Herzogthums Steiermark Ia, Graetz 1844

#### MUCHAR 1845

Albert von Muchar, Geschichte des Herzogthums Steiermark II, Graetz 1845

### **MURER 2018**

Cristina Murer, From the tombs into the city: grave robbing and the reuse of funerary spolia in Late Antique Italy, *Acta ad archaeologiam et artium historiam pertinentia* XXX (N.S. 16), 2018, 115-137

#### **MURER 2022**

Cristina Murer, Recycling Roman funerary sculpture in Italy and the Late Roman West, in: C. Parigi (ed.), Recycling and Reuse of Sculpture in Roman and Late Antique Times, Panel 6.8, Archaeology and Economy in the Ancient World 37, Heidelberg 2022, 49–57

#### MÜLLER 2004

Harald W. Müller, Naturwissenschaftliche Grundlagen (368-369), Die Marmorsteinbrüche (369-372), Analysenergebnisse (373-383), in: B. Djurić – B. Hebert et al., Marmore römischer Brüche und Steindenkmäler in der Steiermark und in Štajerska. Ergebnisse eines Forschungprojektes, Fundberichte aus Österreich 43, 2004, DOI: https://doi.org/10.11588/propylaeum.928.c12254

### MÜLLER 2007

Harald W. Müller, Der Marmor von Gummern und seine Bedeutung für die römischen Provinzen Pannonien, Norikum und Rätien, in: V. Höck – F. Lang – W. Wohlmayer (eds.), Akten zum Österreichischen »Römerstein-Treffen« in Salzburg, Wien 2007, 33-36

### OLSZEWSKI 2019

Edward Olszewski, Dionysus's Enigmatic Thyrsus, Proceedings of the American philosophical society 163.2, 2019

### OROŽEN 1889

Ignaz Orožen, Neu aufgefundene Römersteine, Mittheilungen des Historischen Vereines für Steiermark 37, 1889, 218-220

### PAHIČ 1960-61

Stanko Pahič, Malečnik, VS 8, 1960-61, 246

### PAHIČ 1968-69a

Stanko Pahič, Slovenska Bistrica, VS 13-14, 167-168

#### PAHIĊ 1968-69

Stanko Pahič, Tinje na Pohorju, VS 13-14, 171

PAHIČ 1969

Stanko Pahič, Antična gomila z grobnico v Miklavžu pri Mariboru, AV 20, 1969, 35-103

**PAHIČ 1970** 

Stanko Pahič, Maribor v rimski dobi, ČZN 6.2, 1970, 159-243

PAHIČ 1974a

Stanko Pahič, Miklavž na Dravskem polju, VS 17-19/1, 1974, 134

PAHIČ 1974b

Stanko Pahič, Morje pri Framu, VS 17-19/1, 1974, 135

PAHIČ 1977a

Stanko Pahič, Seznam rimskih kamnov v Podravju in Pomurju, AV 28, 1977, 13-73

PAHIČ 1977b

Stanko Pahič, Novi rimski napisi v Podravju, AV 28, 1977, 74-91

PAHIČ 1977c

Stanko Pahič, Spodnja Polskava, VS 21, 1977, 267-268

PAHIČ 1977d

Stanko Pahič, Črešnjevec, VS 21, 1977, 204-206

PAHIČ 1977e

Stanko Pahič, Šmartno na Pohorju, VS 21, 1977, 273-274

PAHIČ 1983

Stanko Pahič, Arheološka preteklost Maribora, Kronika 31, 1983, 114-126

PAHIČ 1984

Stanko Pahič, Črešnjevec, VS 26, 1984, 221-226

PAHIČ 1984a

Stanko Pahič, Šmartno na Pohorju, VS 26, 1984, 257-259

PAHIČ 1990

Stanko Pahič, Črešnjevec, VS 32, 172-173

PICHLER 1871

Friedrich Pichler, Die römischen Grabschriften des norisch-pannonischen Gebietes, Mittheilungen des Historishen Vereines für Steiermark 19, 1871, 77-128

### POCHMARSKI 1983-84

Erwin Pochmarski, Girlandenhaltende Eroten in Noricum und Pannonien, Römisches Österreich 11-12, 1983-84, 226-277

### POCHMARSKI 1987

Erwin Pochmarski, Motivgeschichte und Chronologie: girlandenhaltende Eroten in Noricum und Pannonien, in: Berichte des 2. österreichischen Archäologentages, MAGesStei, Beih.1, Graz 1987, 90–94

### POCHMARSKI 1998

Erwin Pochmarski, Überlegungen zur Chronologie der pannonischen Sarkophage, in G. Koch (ed.): Akten des Symposions »125 Jahre Sarkophag-Corpus«, Marburg 4.-7. 10. 1995, Sarkophag-Studien 1, Mainz 1998, 182-200

### POCHMARSKI 2004

Erwin Pochmarski, Das sagum – urtrachtlicher keltischer Umhang und/oder römischer Uniformmantel, in: H. Heftner – K. Tomaschitz (eds.), *Ad fontes! Festschrift Gerhard Dobesch*, Wien 2004, 571–578

#### POCHMARSKI 2014a

Erwin Pochmarski, Die Sarkophagwerkstätten von Aquincum und Brigetio, *Acta Archaeologica Academiae Scientiarum Hungaricae* 65, 2014, 405-426

### POCHMARSKI 2014b

Erwin Pochmarski, Die Aschenkisten von Poetovio und Celeia, AV 65, 2014, 353-366

#### POCHMARSKI 2015

Erwin Pochmarski, Aschenkisten und Sarkophage von Poetovio, in: B. Porod – G. Koiner (eds.), Römische Sarkophage. Akten des internationalen Werkstattgesprächs 11. – 13. Oktober 2012, Graz (Schild von Steier, Beiheft 5), Graz 2015, 212-225

### POCHMARSKI 2016

Erwin Pochmarski, Ein Sarkophagfragment mit Nymphendarstellung aus Poetovio, in: G. Koiner – U. Lohner-Urban (eds.), "Ich bin dann mal weg". Festschrift für einen Reisenden Thuri Lorenz zum 85. Geburtstag, Wien 2016, 163-168

#### POCHMARSKI 2018

Erwin Pochmarski, Aschenkisten aus dem Territorium von Iuvavum, in: R. Kastler – F. Lang – H. Wendling (eds.), Faber Salisburgi. Festschrift für Wilfried K. Kovacsovics zum 65. Geburtstag, Salzburg 2018, 223-228

### POCHMARSKI 2019

Erwin Pochmarski, Beobachtungen zu den Sarkofagen aus Mursa und Cibalae, *Prilozi povijesti umjetnosti u Dalmaciji* 44, 2019, 247-260

#### POCHMARSKI 2020

Erwin Pochmarski, Trauernde Eroten auf Grabmonumenten der Provinz Noricum, in: L. Berger – F. Lang – C. Reinholdt – B. Tober – J. Weilhartner (eds.), *Gedenkschrift für Wolfgang Wohlmayr*, Salzburg 2020, 335-342

### POCHMARSKI – HANDY 2020

Zur Nymphenverehrung in Noricum und Pannonien, in: S. Petković – N. Gavrilović Vitas (eds.), *Ancient cult in Balkans through archaeological findings and iconography*, Beograd 2020, 39-62

### POCHMARSKI-NAGELE 1992

Margaretha Pochmarski Nagele, Die dyonisischen Reliefs in Noricum und ihre Vorbilder, Wien 1992

### POCOCKE – MILLES 1752

Richard Pococke – Jeremias Milles, Inscriptionum antiquarum liber alter, London 1752

# POP LAZIĆ 2008

Stefan Pop Lazić, Late Roman necropolis Beljnjača in Šid, Starinar 58, 2008, 163-173

#### POVODEN 1818

Simon Povoden, Archäologische Blütenlese, Archiv für Geographie, Historie, Staats- und Kriegeskunst 9, 1818, 209-212

### POVODEN 1830

Simon Povoden, Antiquitaeten Poetoviens. Ahhildungen der römischen Votiv- und Begrabungssteine sammt einer Erklärung (manuscript)

#### PREDAN et al. 2013

Primož Predan – Grega Čakš – Jasna Vinder – Barbara Čeh, *Arheološko najdišče Ptuj Rabelčja vas – meteorna kanalizacija OŠ Ljudski vrt*, Slovenska Bistrica 2013 (unpublished report)

#### RAECK 2003

Wulf Raeck, Rolle und Individuum im frühen griechischen Porträt, in: M. Büchsel, P. Schmidt (eds.), Das Porträt vor der Erfindung des Porträts, Mainz 2003, 29–42

### RAGOLIČ 2014

Anja Ragolič, The territory of Poetovio and the boundary between Noricum and Pannonia, AV 65, 2014, 323–351

### RAGOLIČ 2020

Anja Ragolič, Katalog kamnitih spomenikov, in: *Arheološka najdišča Ptuja. Panorama*, Ljubljana 2020, 71-139

### RAGOLIČ 2023

Anja Ragolič, Poetovio. Römische Grabdenkmäler, Inscriptiones latinae Sloveniae 2/1, Ljubljana 2023

### REINACH 1904

Adolphe Joseph Reinach, Thyrsos, in: Ch. Daremberg – E. Saglio, Dictionnaire des antiquités grecques et romaines: d'après les textes et les monuments, tome 5, Paris 1904, 287-296

### RENDIĆ-MIOČEVIĆ 2013

Ante Rendić-Miočević, The marble funerary stele of a cohors II Varcianorum equitata's veteran, Titus Flavius Ateboduus from the Odra village near Zagreb, in: N. Cambi – G. Koch (eds.), Funerary Sculpture of the Western Illyricum and the Neighbouring Regions of the Roman Empire, Split 2013 343-382

### RINDLER 2004

Susanne Rindler, Zur Aufnahme römischer Steindenkmäler der »Ostalpenländer« 1943/44, Zeitschrift des Historischen Vereines für Steiermark 95, 2004, 337-349

#### ROBERT 1897

Carl Robert, Die antiken Sarkophag-Reliefs III.1, Berlin 1897

#### ROTHE 2012

Clothing in the Middle Danube provinces. The garments, their origins and their distribution,  $J\ddot{O}h$  81, 1912, 137-231

### SARIA 1933-34

B. Saria, Jedan nadgrobni spomenik iz Viminacija, Starinar 8-9, 1933-34, 73-82

### **SARIA 1939**

Balduin Saria, Rimski napisi v Mariboru, Kronika slovenskih mest 6.2, 1939, 73-79

#### **SARIA 1943**

Balduin Saria, Pettau. Ein Führer durch die Stadt und deren Geschichte, Pettau 1943

#### **SARIA 1946**

Balduin Saria, Neue Inschriften aus dem norisch-pannonischen Grenzgebiet, JÖh 36, 1946, 41-66

### **SCHNURBEIN VON 1995**

Siegmar von Schnurbein, Merkur als Soldat? Zur Gürtelmode des 3. Jahrhunderts n. Chr, in: W. Czysz (ed.), Provinzialrömische Forschungen. Festschrift für Günter Ulbert zum 65. Geburtstag, München 1995, 139-148

#### SCHOBER 1923

Arnold Schober, Die römischen Grabsteine von Noricum und Pannonien, Wien 1923

#### SCHWEITZER 1963

Bernhard Schweitzer, Zur Kunst der Antike: ausgewählte Schriften, Tübingen 1963

SINN 1987

Friederike Sinn, Stadtrömische Marmorurnen I, Mainz am Rhein 1987

#### SKRABAR 1935

Viktor Skrabar, Römische Funde aus Pettau, Mitteilungen der k.k. Zentralkommision 4, 1905, 302-316

#### SKRABAR 1905

Viktor Skrabar, Stara ledinska karta v ormoškem gradu, ČZN 30, 1935, 30-44

SPEIDEL 1976

Michael P. Speidel, Eagle-Bearer and Trumpeter, Bonner Jahrbücher 176, 1976, 123-163

### STARAC 2021

Alka Starac, An Architect of His Own Life, Academia Letters, Article 3439, 2021

#### STEINBÜCHEL 1829

Anton Steinbüchel von Rheinwall, Alterthümer in der österreichischen Monarchie, *Jahrbücher der Literatur*. Anzeige Blatt 46, 1829, 35-75

#### STUVERAS 1969

Roger Stuveras, Le putto dans l'art romain, Bruxelles 1969

#### ŠAŠEL KOS 1993

Marjeta Šašel Kos, A new equestrian family from Poetovio, Zeitschrift für Papyrologie und Epigraphic 95, 1993, 236-240

# ŠMID 2015

Katarina Šmid, Rajko Ložar (1904–1985) und seine WienerDissertation. Ein wenig bekannter früher Beitrag zur Sarkophagforschung in Noricum und Pannonien, in: B. Porod – G. Koiner (eds.), Römische Sarkophage. Akten des internationalen Werkstattgesprächs 11. – 13. Oktober 2012, Graz (Schild von Steier, Beiheft 5), Graz 2015, 250-255

### **ŠMID 2020**

Katarina Śmid, Med »pogansko« antiko in zgodnjim krščanstvom sarkofag z upodobitvijo gostije (convivium), in: *Umetnost Ptuja in ptujski umetniki*, Ptuj 2020, 31-44

#### **ŠMID 2023**

Katarina Šmid, Lysippean models on two Roman reliefs from Poetovio, AV 74, 2023, 315-329

#### **ŠUBIC 1965**

Zorka Šubic, Ptuj, VS 10, 1965, 202-204

### ŠUBIC 1966

Zorka Šubic, Videm pri Ptuju, VS 11, 1966, 130

ŠUBIC 1967a

Zorka Šubic, Ptuj, VS 12, 1967 (1969), 93-94

ŠUBIC 1967b

Zorka Šubic, Epigrafske najdbe v Ptuju in območju v letih 1965-1966, AV 18, 1967, 187-191

**ŠUBIC 1968-69** 

Zorka Šubic, Ptuj, VS 13-14, 1968-69 (1970), 164-165

ŠUBIC 1972

Zorka Šubic, La nécropole romaine a Poetovio, Inventaria Archaeologica: Jugoslavija 14, 1972

ŠUBIC 1974

Zorka Šubic, Sp. Hajdina, VS 17-19/1, 1974, 152-153

**ŠUBIC 1975** 

Zorka Šubic, Beg Ifigenije s Tavride na videmskem reliefu, Ptujski zbornik 4, 1975, 95-100

ŠUBIC 1977

Zorka Šubic, Novi rimski napisi iz Poetovione (1968-1972), AV 28, 1977, 92-99

TUŠEK 1984

Ivan Tušek, Rimska apnenica v Rabelčji vasi v Ptuju, AV 35, 1984, 225-231

TUŠEK 1986

Ivan Tušek, Novi rimski reliefni kamni in napisi iz Ptuja, AV 37, 1986, 343-370

TUŠEK 1992a

Ivan Tušek, Ptuj. Zaščitna izkopavanja ob novi porodnišnici, VS 34, 1992, 282-284

TUŠEK 1992b

Ivan Tušek, Ptuj. Prešernova 16, VS 34, 1992, 286-287

TUŠEK 1993a

Ivan Tušek, Ptuj. Prešernova 16, VS 35, 1993, 137

TUŠEK 1993b

Ivan Tušek, Novi oltarni in reliefni kamni iz Petovione, AV 44, 1993, 203-208

**UBL 1969** 

Hannsjörg Ubl, Waffen und Uniform des römischen Heeres der Prinzipatsepoche nach den Grabreliefs Noricums und Pannoniens (Diss. Universität Wien 1969) = Waffen und Uniform des römischen Heeres der Prinzipatsepoche nach den Grabreliefs Noricums und Pannoniens (Austria antiqua. Band 3), Graz 2013

**VERMASEREN 1966** 

Maarten Jozef Vermaseren, The legend of Attis in Greek and Roman art, Leiden 1966

VISOČNIK 2014

Julijana Visočnik, Rimski spomeniki na Dobrni in njeni okolici, Kronika 62, 2014, 355-364

VISOČNIK 2017

Julijana Visočnik, The Roman Inscriptions from Celeia and its Ager, Celje 2017

VOMER GOJKOVIČ 1993

Mojca Vomer Gojkovič, Lončarsko opekarska delavnica v rimski obrtniški četrti na Ptuju, *Ptujski arheološki zbornik*, Ptuj 1993, 449-463

# VOMER GOJKOVIČ 1996

Mojca Vomer Gojkovič, Grobišče pri Dijaškem domu v Rabelčji vasi na Ptuju, *Ptujski zbornik* 6.1, Ptuj 1996, 229-312

# VOMER GOJKOVIČ 1997

Mojca Vomer Gojkovič, Marmorfragment mit Vogeldarstellung, Akten des IV. Internationalen Kolloquiums über Probleme des provinzialrömischen Kunstschaffens: Celje 8.-12. Mai 1995, Ljubljana 1997, 131-134

# VOMER GOJKOVIČ 2015

Mojca Vomer Gojkovič, A sarcophagus from Orešje near Ptuj, in: B. Porod – G. Koiner (eds.), Römische Sarkophage. Akten des internationalen Werkstattgesprächs 11. – 13. Oktober 2012, Graz (Schild von Steier, Beiheft 5), Graz 2015, 256-268

### **WALDE 2005**

Elisabeth Walde, Im herrlichen Glanze Roms. Die Bilderwelt der Römersteine in Österreich, Innsbruck 2005

#### **WARD 2012**

Graeme Alexander Ward, Centurions: the practice of Roman officership, Chapel Hill 2012 (Diss. University of North Carolina)

#### WARD 2017

Graeme Alexander Ward, From Stick to Scepter: How the Centurion's Switch Became a Symbol of Roman Power, Paper presented to the 148th Annual Meeting of the Society for Classical Studies held January 5-8, 2017, Toronto, Canada (https://www.academia.edu/30840391/)

#### WILSON 2010

Mark Wilson, Biblical Turkey: A Guide to the Jewish and Christian Sites of Asia Minor, Istanbul 2010

### **WLACH 2014**


Gudrun Wlach, Arnold Schober – Leben und Werk, in: E. Trinkl (ed.), Akten des 14. Österreichischen Archäologentages am Institut für Archäologie der Universität Graz vom 19. bis 21. April 2012, Wien 2014, 457-470

#### ZIEGLER 2000

Daniela Ziegler, Frauenfrisuren der römischen Antike: Abbild und Realität, Berlin 2000

### ŽNIDARČIČ – MIOČ 1989

Miro Żnidarčič – Peter Mioč, Osnovna geološka karta SFRJ, list Maribor in Leibnitz, 1:100.000, Beograd 1989



#### List of abbreviations:

AMZg Arheološki muzej, Zagreb

CLEPann Carmina latina epigraphica Pannonica

EDCS Epigraphische-Datenbank Clauss-Slaby (http://www.manfredclauss.de/)
HD/EDH Epigraphische Datenbank Heidelberg (https://edh.ub.uni-heidelberg.de/)

ILJug Šašel A. – Šašel J., Inscriptiones Latinae quae in Iugoslavia inter annos MCMXL et

MCMLX repertae et editae sunt, 1963 (= Situla 5)

KHM Kunsthistorisches Museum, Vienna

Lupa Ubi Erat Lupa (http://lupa.at)

MNM Magyar Nemzeti Múzeum, Budapest

MS Muzej Srema, Sremska Mitrovica

PMMb Pokrajinski muzej, Maribor

PMPO Pokrajinski muzej Ptuj – Ormož, Ptuj

TM Trismegistos (http://www.trismegistos.org/)

#### Note:

The inscriptions on the monuments described in the catalogue are taken from the work of Anja Ragolič, 2023.

### **SARCOPHAGI**

#### 1. FRIEZE SARCOPHAGUS

PL. 1

Prov.: Zgornja Hajdina near Ptuj, church of St Martin, south wall of the presbytery.

Loc.: Ptuj, PMPO, Inv. No. RL 447.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 12; H. W. Müller).

Condition: Large part of the front side broken off above the bottom, missing the left and right corners at least for the thickness of the short sides, more so on the left than on the right. Upper left corner crushed and restored. Surface heavily weathered, with poorly visible details. The interior shows well-preserved tool marks in the form of slightly curved horizontal lines left by a double-pointed quarry pick used to carve out the chest interior.

Size:  $232 \times 62 \times 21$  cm; side th. 22 cm.

Structure: Chest with relief decoration on the front. The bedding surface has a raised semi-circular edge along the interior to keep the lid in place.

Iconography: The centrally placed couch (lectus, kline) with a high back and armrests (fulcra), such as are depicted on many Roman reliefs with banqueting scenes, holds two reclining figures, likely a man on the right and a woman on the left. The man has short hair, the woman perhaps a melon coiffure (Melonenfrisur). They are both dressed in tunics. The woman also wears an asymmetrical palla, the man possibly a cloak (sagum?) pleated on the left shoulder. Both figures are portrayed in a manner reminiscent of half-length funerary portraits on numerous Pannonian funerary stelae or Norican medallions and aedicula tombs, and only a detail on the left side of the left figure hints at a reclining pose. The figure on the right holds a drinking cup (modiolus?) in the left hand, with the arm bent at waist height, while the right hand is not visible. The figure on the left also has the left arm bent at waist height, with the hand loosely hanging down, while the right arm is bent at chest height and holds an unidentifiable object. Shown between them is a pair of nude boys, each oriented toward one of the reclining figures. The boy on the left is kneeling on the couch, placing a garland around the woman's neck. The boy on the right is sitting, with an extended right arm possibly holding a vessel towards the man, while the left arm is reaching towards the man's chest below the neck. Such nude child figures with garlands and kalathoi in hand are known from the Metropolitan sarcophagi and identified as deliciae. On the sepulchral monuments with banqueting scenes, they can be seen participating in the feasting as pleasant and amusing 'pets', with whom others engaged in play and to whom the Romans also referred as deliciae. Shown at either end and in front of the couch is a female figure seated on a chair with a backrest. Both women are dressed in a tunic and palla, the latter better visible on the right woman. The tunics are girt under the breasts. Between them stands a round, likely three-legged table (mensa tripes), which the woman on the left is touching with her left hand and the woman on the right with her right hand. The woman on the left has her right arm bent and raised before her at chest height, possibly with two extended fingers, while the woman on the right holds a vessel (modius, calathus?) in her lap, presumably filled with fruit. Placed in the centre of the table is a round platter with food, likely poultry based on its outline, which would typically follow fish as the most prized meat at banquets. To the left and right of the platter is a round loaf of bread with a hole in the middle. Another object

is depicted below the left loaf, but it is no longer identifiable.

Other figures are arranged to the left and right of the central scene, two on each side. On the far left is a partially preserved figure shown in profile, facing right and holding a platter with food (?) in the outstretched hands; part of the pallium is visible under the arms. On the far right, a similar figure is depicted in profile, but facing away from the central scene, dressed in a pallium and holding a platter in the hands outstretched at the level of the face. Both figures are servants-slaves attending to the banqueters. Shown in a similar posture is another figure on the left, dressed in a tunic (?) and pallium, holding a large cup (calathus?) in the outstretched left hand at chest height, while the missing right arm presumably held a wine jug - this individual may be a puer speciosus, as named by Petronius (Satyrica 41.6). The figure of a handwasher can be identified in the person standing behind the seated woman on the right. This figure is shown frontally, with the head slightly turned to the right, dressed in a tunica manicata girt below the breasts, touching the chair's backrest with the right hand while holding a mantele, napkin used for wiping hands during meals (lavatio), that is slung over the left shoulder. The gender of this figure cannot be identified due to damage; the high-girt tunic and the regional tradition of depicting female servant-slaves suggest it is more likely a woman, though there are also known similar depictions of youthful luxury slaves capillati or paedagogiani.

Shown on the far right are two cylindrical objects with a domed lid terminating in a knob and tied with a ribbon. They are pair of flasks for wine and water in wicker containers.

The scene unfolds beneath a vine that symmetrically arches towards the *kline* from the left and right. The vine has five-lobed leaves with incised central veins, simple single tendrils and full bunches of sub-round, only slightly elongated grapes. In the 3<sup>rd</sup> century, the vine motif is primarily associated with Dionysian ideolo-

gy, while a Christian interpretation is much less likely, but cannot be entirely excluded.

Dating: 3<sup>rd</sup> century.

Lit.: Conze 1875, 12; Abramić 1925, 171; Klemenc – Saria 1936, 59; Djurić 2001b, 47, No. 1; Djurić – Hebert *et al.* 2004, 400 (PET 12); Djurić 2015, 92–101; Šmid 2020; Ragolič 2023, 164, No. 156.

www: Lupa 5295.

### 2. SARCOPHAGUS WITH LID PL. 2

Prov.: Hajdina (?) near Ptuj.

Loc.: Graz, Universalmuseum Joanneum, Inv. No. 50.

Material: Eastern Alpine marble.

Condition: Complete chest and lid with chipped edges.

Size: chest  $206 \times 55 \times 98$  cm; lid  $173 \times 64 \times 18$  cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The central panel has a straight moulded frame on all four sides, it is finely finished and prepared for the inscription. The decoration panels have a straight moulded frame on all four sides and are left rough. The short sides have an outlined decoration panel in each. The bedding surface has a raised semicircular edge along the interior to keep the lid in place. The front side is six modules long. The lid is in the form of a slab.

Dating: 3<sup>rd</sup> century.

Lit.: Diez 1948, 152; Gabelmann 1977, 241; Modrijan – Weber 1979–81, 103; Djurić 2001b, 47–48, No. 2; Ragolič 2023, 159, No. 146.

www: Lupa 4577.

#### 3. SARCOPHAGUS WITH LID PL. 2

Prov.: Ptuj, Rogaška cesta 14 (today Zagrebš-ka cesta 28), Lot No. 318/3, Sp. Breg cadastral municipality, 1967.

Loc.: Ptuj, PMPO, Inv. No. RL 872.

Context: The excavations for a soakaway on Spodnji Breg brought to light a lidded sarcophagus. Its chest and lid were fixed together with an iron dowel on either side (Inv. No. R11307), secured with lead. The sarcophagus was buried 1.85 meters below the modern-day surface (see Fig. 6) and held the skeleton of a woman and grave goods: a small glass jug with a handle<sup>313</sup> (Inv. No. R11308), a small globular glass bottle314 (Inv. No. R11311), a fragment of a lead mirror frame with relief decoration (spruce branch above a circle) (Inv. No. R11310) and a bronze as of Claudius I<sup>315</sup> (Inv. No. RN 3834). Outside the sarcophagus, a small globular glass bottle with a long neck<sup>316</sup> (Inv. No. R11309), a round bronze fitting (Inv. No. R11312), an amber bracelet or spindle (Inv. No. R11313) and half of a disc-shaped amber bead (Inv. No. R11314) were found on the surface from which the pit for the sarcophagus was dug. Unearthed higher up, on another ancient ground above the sarcophagus were fragments of two incense burners (Inv. Nos. R11319, R11320), three plates (Inv. Nos. R11315-11317) and a damaged beaker decorated with incisions and barbotine (Inv. No. R11321).

Material: Eastern Alpine marble, Pohorje quarry (Samples PET 07, 08; H. W. Müller).

Condition: Complete chest and lid, containing the skeleton of a woman and grave goods (cf. Šubic 1972).

Size: chest  $208 \times 50 \times 100$  cm; lid  $224 \times 14 \times 106$  cm; bottom th. 10–13 cm; side th. 16–28 cm.

Structure: Low chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The central panel has a straight moulded frame on all four sides, it is finely finished and prepared for the inscription. The decoration panels also have a straight moulded frame on all four sides, but otherwise left rough. The short sides are plain and have a clamp hole at the upper edge. The bedding surface has a raised semicircular edge along the interior for keeping the lid in place. The front side is six modules long.

The lid is in the form of a slab and has a groove framing the underside or standing surface intended to fit onto the chest. The short sides of the lid have a clamp hole for fastening the lid to the chest with a pair of iron clamps secured with lead.

Dating: CE 150–300 (based on grave goods, cf. Lazar 2003, 130, 142).

Lit.: Šubic 1967, 94; Šubic 1972; Jevremov 1988, 115; Djurić 2001b, 47–48, No. 3; Djurić – Hebert *et al.* 2004, 400 (PET 7, PET 8); Ragolič 2023, 158, No. 145.

www: Lupa 9363.

#### 4. SARCOPHAGUS

PL. 2, 3

Prov.: Orešje near Ptuj, Orešje 76 (Grdiša family).

Loc.: Ptuj, PMPO, Inv. No. RL 1034.

Material: Eastern Alpine marble.

Condition: Complete chest with damaged upper and bottom edges on the back and a cracked right short side that holds a later hole for water drainage.

Size:  $200 \times 91 \times 94$  cm; bottom th. 51 cm; side th. 14 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The central panel has a straight moulded frame on all four sides, it is finely finished and prepared for the inscription. The decoration panels also have a moulded frame, formed as a Norico-Pannonian volute in the upper part, and are left rough. The short sides have an outlined decoration panel, which is coarsely dressed. The thick bottom allows for the possibility of the piece being an ash

<sup>313</sup> Lazar 2003, 130, Form 5.1.6.

<sup>314</sup> Lazar 2003, 142, Form 6.2.4.

<sup>315</sup> Identification: Efrem Pegan, Narodni muzej Slovenije.

<sup>316</sup> Lazar 2003, 142, Form 6.2.4.

chest. The front side is five modules long.

Dating: Second half of the  $2^{nd} - 3^{rd}$  century.

Lit.: Pahič 1977a, 52; Djurić 2001b, 48, No. 4; Djurić 2005, 82; Vomer Gojkovič 2015; Ragolič 2023, 301, No. 398.

# 5.SARCOPHAGUSFORQUINTINA PL.3

Prov.: Zgornja Hajdina near Ptuj, excavations of the Maribor museum association in 1905 or 1907.

Loc.: Maribor, PMMb, Inv. No. A 2330.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 44; H. W. Müller).

Condition: The two parts of the upper front side, once built into the wall of the PM Maribor, broke into several pieces that were then restored and reassembled. There were six fragments upon discovery that are today joined into two pieces; the right upper part is missing.

Size: 205 (reconstr.)  $\times$  32 (reconstr. 70)  $\times$  17.5 cm; surviving size 1. 135  $\times$  19  $\times$  16 cm; surviving size 2. 33  $\times$  12  $\times$  16 cm; left short side th. 19 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The central panel has a straight moulded frame and bears an inscription. The decoration panels also have a moulded frame, formed as a Norico-Pannonian volute in the upper part, and are left rough. The short sides have a simple frame and are left rough. The front side is five modules long.

Inscription: [D(is) M(anibus)] / [et perpe]tuae saecuritati (!) ne grave sit quicum/ [que leg]is cognoscere casus Quintinae est in / [---]ii tegitur fato rapta malo et iniquo numi/ [ne --] NISIDV CI[ // ann]or(um) LX semi/ [ssis --- req]uiem ex more vetusto perpet/ [uam ---]dec(?) ex provincia RITIIASV [---] / [--- coni]ugi inco[mparabili---

Dating: 3<sup>rd</sup> century.

Lit.: Hoffiller – Saria 1938, 180–182, No. 401; Diez 1948, 152–153; Cermanović 1965, 98, No. 7; Djurić 2001b, 53, No. 5; Djurić – Hebert *et al.* 2004, 402

(PET 44); Ragolič 2023, 120–121, No. 79; *CLE-Pann* 20.

www: Lupa 4271; EDCS-11301067; HD069061; TM 407241.

### 6. SARCOPHAGUS

PL. 3, 4

Prov.: Ptuj, Zgornji Breg, prior to 1948.

Loc.: Ptuj, PMPO Mithraeum III, Inv. No. RL 1020.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 40; H. W. Müller).

Condition: Bottom part with all four sides broken off.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The central panel has a moulded frame. The lateral panels also have a moulded frame. The short sides are plain and coarsely dressed. The front side is five modules long.

Size:  $206 \times 37 \times 102$  cm; bottom th. 18 cm; side th. 16 - 20 cm.

Iconography: The lateral front panels show a pedestal with concave sides. The right panel more precisely shows the lower part of crossed legs, while the left panel shows the lower part of an inverted torch. They are likely mirror depictions of mourning erotes leaning onto an inverted torch, with their legs crossed.

Dating: Second half of the  $2^{nd} - 3^{rd}$  century.

Lit.: Diez 1948, 153; Cermanović 1965, 99, No. 11; Djurić 2001b, 53, No. 6; Djurić – Hebert *et al.* 2004, 402 (PET 40); Ragolič 2023, 168–169, No. 165.

#### 7. SARCOPHAGUS

PL. 4

Prov.: Ptuj, garden of the Minorite Monastery, 1958.

Loc.: Ptuj, PMPO, Inv. No. RL736.

Material: Eastern Alpine marble.

Condition: Bottom part repurposed, turned upside down, as a rectangular basin with two

rounded corners and shortened on the short sides.

Size: 178 (reconstr. 198)  $\times$  21–23 (reconstr. 74)  $\times$  95 cm; bottom th. 23 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The central panel has a moulded frame, it is finely finished and prepared for the inscription. The lateral panels also have a moulded frame. The short sides are left rough. The front side is five modules long.

Lit.: Unpublished.

### 8. SARCOPHAGUS FOR AELII PL. 4

Prov.: Ptuj, Vičava, during water pipeline works, 1974.

Loc.: Ptuj, PMPO, Inv. No. RL 967.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 09; H. W. Müller).

Condition: Bottom part with missing left corner in the width of the decoration panel.

Size:  $194 \times 46$  (reconstr. 74)  $\times$  119 cm; bottom th. 37 cm, side th. 20 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The central panel has a moulded frame, it is finely finished and bears an inscription. The lateral panels also have a moulded frame. The surviving right short side has a moulded frame and is coarsely dressed in preparation for the relief to be carved. The front side is six modules long.

Iconography: The right decoration panel shows the nude crossed legs of a boyish figure, shown frontally with the weight on the left leg, on a pedestal with concave sides. To his right is the lower part of an inverted torch, possibly also part of a wreath. It is the depiction of a mourning eros leaning onto a torch and possibly holding a wreath in his lowered right hand. The missing left decoration panel presumably held his mirror image.

Inscription: --- ] / [P(ublius)] Aelius Marinus d[ec(urio) col(oniae) Poetov(ionensis)] / eq(uo) publ(i-co) praef(ectus) coh(ortis) II Hispanorum et / P(ublius) Aelius Marcianus dec(urio) col(oniae) eiusdem / eq(uo) publ(ico) praef(ectus) coh(ortis) I Germanorum / parentibus pientissimis

Dating: Antonine (Sašel Kos) or Early Severan.

Lit.: Jevremov 1988, 115–116, No. 132; Šašel Kos 1993, 236; Djurić 2001b, 53, No. 7; Djurić – Hebert *et al.* 2004, 400 (PET 9); Pochmarski 2015, 219; Ragolič 2023, 14–15, No. 1.

www: Lupa 4218; EDCS-03700679; HD052957; TM 197278.

### 9. SARCOPHAGUS

Prov.: Spodnja Hajdina near Ptuj, excavations for a house on Lot No. 863, Hajdina cadastral municipality, property of Svenšek, 1972.

PL. 5

Loc.: Ptuj, PMPO, Inv. No. RL 938.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 05; H. W. Müller).

Condition: Left bottom part with severe surface damage.

Size:  $106 \times 30 \times 42$  cm; bottom th. 31 cm, side th. 15–19 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels (right one missing). The central and lateral panels have a moulded frame that is almost completely abraded.

Iconography: The left decoration panel shows part of a nude male figure, his legs surviving above the knees and the torso below the waist. His weight is on the right leg. To his right is the remains of a vertically positioned rod-like object. It does not seem to be a depiction characteristic of a mourning eros with the weight on the leg opposite the torch on which he leans, but possibly one of a nude Mars or hero.

Dating: Second half of the  $2^{nd} - 3^{rd}$  century. Lit.: Šubic 1974, 152; Djurić 2001b, 53, No. 8; Djurić – Hebert *et al.* 2004, 400 (PET 5); Ragolič 2023, 169, No. 166.

#### 10. SARCOPHAGUS FRAGMENT PL. 5

Prov.: Ptuj, church of St George, façade renovation, 1968.

Loc.: Ptuj, PMPO, Inv. No. RL 883.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 27; H. W. Müller).

Condition: Right front corner with missing top part and damaged surface.

Size:  $46 \times 64 \times 30$  cm; bottom th. 31 cm, side th. 13 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The right decoration panel has a moulded frame. The surviving right short side has a simple frame. The front side is five modules long.

Iconography: The right front panel depicts a male figure in contrapposto, with the weight on the left leg, standing on a footing. The half-missing head is damaged, possibly bearded. The left arm is bent, with the elbow and hand destroyed, likely placed over the belt, possibly holding a scroll. The right arm is stretched away from the hip and resting on a staff with a rounded terminal - vitis. The man is dressed in a belted tunica manicata reaching above the knees, with sleeves extending to mid-forearm. The belt is relatively wide, the belt buckle damaged, while the excess belt is tucked under the belt on the right hip and looped forward above it. He also wears a sagum reaching to his knees, draped across his left shoulder and fastened on the right one with a disc brooch. The lower edge of the sagum is decorated with fringes. It is a depiction of a centurio in 'camp dress' (Speidel 1976, 124).

The right short side shows a youthful nude winged eros. He is shown mid-stride, with his right leg extended backward, surviving up to the waist along with part of his right wing. It is one of a pair of erotes holding an object (shell,

medallion) between them.

Dating: Severan (Pochmarski).

Lit.: Šubic 1968–69, 164–165; Jevremov 1988, 124, No. 149; Djurić 2001b, 48, No. 9; Djurić – Hebert *et al.* 2004, 401 (PET 27); Pochmarski 2015, 219; Handy – Pochmarski 2020, 300; Ragolič 2023, 165–166, No. 159.

www: Lupa 4219.

### 11. SARCOPHAGUS FRAGMENT PL. 5

Prov.: Ptuj.

Loc.: Ptuj, PMPO, Inv. No. RL 463.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 10; H. W. Müller).

Condition: Left front corner with missing bottom part and surface damage, particularly on the left short side.

Size:  $44 \times 53 \times 36$  cm; side th. 20 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The left front panel has a moulded frame, formed as a Norico-Pannonian volute in the upper part. The surviving left short side also has a moulded frame with the upper part formed as a Norico-Pannonian volute. The front side is five modules long.

Iconography: The left front panel depicts a winged nude youth with his head turned to his left. The youthful, full face is damaged, as is the ear. The hair is styled in strands pulled back into a melon hairstyle and tied into a round chignon at the nape. The shoulders are depicted frontally, the hips are slightly turned to his right. The legs, surviving above the knees, are crossed. The genitalia are clearly visible. The wings on either side reach down to the hips. Folds of a cloak fall along the body under the arms, though it is not visible on the shoulders. He is holding a slightly downward-curving floral garland diagonally across his chest, from the left hip to the right shoulder. The cuffs of the garland are depicted at the outer edges of his hands, and both ends of the garland are pointed and curved. The youthful figure represents a personification of Spring or an eros holding a garland.

The left short side shows a nude child figure with drapery over the left shoulder and arm. Rising from the figure's back is a triangular wing that identifies it as Psyche. Her body survives from the waist up, it is slightly tilted and turned to the right. Her head has the face broken off and is turned upwards. Only the rear part of the hairstyle survives, showing curls and a chignon at the neck. Holding the head at the chin is the hand of a possibly slightly larger, now missing destroyed figure<sup>317</sup> depicted in the centre of the panel.

Dating: Early Severan.

Lit.: Jevremov 1988, 124, No. 150; Djurić 2001b, 48, No. 10; Djurić – Hebert *et al.* 2004, 400 (PET 10); Pochmarski 2015, 217–219; Ragolič 2023, 166, No. 160.

www: Lupa 4220.

### 12. SARCOPHAGUS FRAGMENT PL. 6

Prov.: Ptuj, Mala vojašnica, 1912.

Loc.: Ptuj, PMPO, Inv. No. RL 546.

Material: Eastern Alpine marble, Gummern quarry (Sample PET 31; H. W. Müller).

Condition: Left front corner with a missing lower part.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The left front panel has a moulded frame, formed as a Norico-Pannonian volute in the upper part, and is left rough. The surviving left short side has an outlined decoration panel. The front side is five modules long.

Size:  $58 \times 35 \times 35$  cm; side th. 16–18 cm.

Lit.: Diez 1948, 153; Cermanović 1965, 99, No. 12; Jevremov 1988, 90, No. 81; Djurić 2001b, 53,

317 Possibly Eros? or Aphrodite?; see Scrinari 1972, 105; Verzar-Bass 2005, 54, Fig. 24; Lupa 13954.

No. 11; Djurić – Hebert *et al.* 2004, 402 (PET 31); Ragolič 2023, 163, No. 154.

# 13. SARCOPHAGUS FRAGMENT PL. 6

Prov.: Ptuj, Vičava, 1901.

Loc.: Ptuj, PMPO, Inv. No. RL 113.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 32; H. W. Müller).

Condition: Upper part of the front inscription panel with damage to the bedding surface and tool marks on the interior side characteristic of sarcophagus chests.

Size:  $81 \times 33 \times 22$  cm; side th. 22 cm.

Structure: Chest with a presumably tripartite front including a central inscription panel with a moulded frame.

Inscription: ---]L(uci) Luperci dec(urionalibus) o[rn(amentis)] / [Aq]uinc(i) d(ecreto) d(ecurionum) Aquin[c(ensium) orn(ati)] / et Tiber(iniae) Favent[inae]

Lit.: Gurlitt 1901, 221–222; Abramić 1925, 52, No. 18; Jevremov 1988, 90, No. 80; Djurić 2001b, 53, No. 12; Djurić – Hebert *et al.* 2004, 402 (PET 32); Ragolič 2023, 72–73, No. 31; CIL III 15186.

www: Lupa 9354; EDCS-32700115; HD068849; TM 410079.

# **14. SARCOPHAGUS FRAGMENT** PL. 6

Prov.: Ptuj, Mala vojašnica, 1912.

Loc.: Ptuj, PMPO, Inv. No. RL 114.

Material: Eastern Alpine marble, Gummern quarry (Sample PET 30; H. W. Müller).

Condition: Two fragments of the upper part of the front inscription panel with damaged bedding surface and tool marks on the interior side characteristic of sarcophagus chests.

Size:  $81 \times 26 \times 19$  cm; side th. 19 cm.

Structure: Chest with a presumably tripartite front including a central inscription panel with a moulded frame.

Inscription: --- | calciolar | iorum

Lit.: Abramić 1925, 58, No. 53; Abramić 1931, 200, No. 24; Hoffiller – Saria 1938, 165, No. 367; Jevremov 1988, 93, No. 87; Djurić 2001b, 53, No. 13; Djurić – Hebert *et al.* 2004, 402 (PET 30); CIL III 15186; Ragolič 2023, 135, No. 100.

www: Lupa 9375; EDCS-11301050; HD068959; TM 407228.

### 15. SARCOPHAGUS FRAGMENT PL. 6

Prov.: Videm pri Ptuju, precinct wall of the church of St Vitus, 1966.

Loc.: Ptuj, PMPO, Inv. No. RL 864.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 28; H. W. Müller).

Condition: Fragment of the inscription panel with tool marks on the bottom characteristic of sarcophagus chests.

Size:  $47 \times 59 \times 23$  cm; bottom th. 23 cm.

Structure: Chest with a presumably tripartite front.

Inscription: --- i/n agro ped/es ---

Lit.: Šubic 1966; Šubic 1967, 189; Pahič 1977b, 85; Jevremov 1988, 63, No. 36; Djurić 2001b, 53, No. 14; Djurić – Hebert *et al.* 2004, 402 (PET 28); Ragolič 2023, 310, No. 408; CIL III 15186.

www: Lupa 13117; EDCS-10001167; HD013977.

# 16. SARCOPHAGUS FRAGMENT PL. 6

Prov.: Ptuj, during construction at Miklošičeva 12, 1936.

Loc.: Ptuj, PMPO, Inv. No. RL 78.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 17; H. W. Müller).

Condition: Fragment of the front inscription panel and tool marks on the interior side characteristic of sarcophagus chests.

Size:  $51 \times 13 \times 20$  cm; side th. 20 cm.

Structure: Chest with a presumably tripartite front including a central inscription panel.

Inscription: --- |renia| ---

Lit.: Schmid 1936, 98, No. 2; Hoffiller – Saria 1938, 188, No. 416; Djurić 2001b, 53, No. 16; Djurić – Hebert *et al.* 2004, 401 (PET 17); Ragolič 2023, 145, No. 120.

www: EDCS 11301078; HD 069085.

### 17. SARCOPHAGUS FRAGMENT PL. 6

Prov.: Ptuj, church of St George.

Loc.: Ptuj, PMPO, Inv. No. RL 1019.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 01; H. W. Müller).

Condition: Right front corner of a sarcophagus chest with missing upper part and standing surface. The front side is almost entirely missing, with only a small part of the relief visible in the lower right corner. The lower left part holding a superficially damaged relief of the right short side.

Size:  $73 \times 30 \times 63$  cm; bottom th. 35 (?) cm.

Structure: Chest with a presumably tripartite front and with the short side panels in a simple frame.

Iconography: Only the relief on the short side is identifiable. It has a centrally positioned two-handled vessel – *kantharos* – surviving up to half its height and flanked on either side by a panther. The animal is sitting and facing outward, likely with its head turned back, resting its right front paw on a curved goat's horn. Vine tendrils and grape bunch are shown behind it. This is a canonical, symmetrically composed Dionysian motif of a *kantharos* with vine laden with grape bunches, flanked by a heraldic pair of outward-facing seated panthers.

Dating: 3<sup>rd</sup> century.

Lit.: Djurić 2001b, 53, No. 17; Djurić – Hebert *et al.* 2004, 400 (PET 1); Djurić 2020; Ragolič 2023, 167–168, No. 163.

# 18. SARCOPHAGUS FRAGMENT PL. 6

Prov.: Ptuj, during construction at Miklošičeva 12, 1936.

Loc.: Ptuj, PMPO, Inv. No. RL 450.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 15; H. W. Müller).

Condition: Left front corner of a sarcophagus chest with minor surface damage.

Size:  $13 \times 20 \times 51$  cm.

Structure: Chest with a presumably tripartite front composed of a central inscription and lateral decoration panels. The lateral front panels have a moulded frame, formed as a Norico-Pannonian volute in the upper part. The short sides have a simple frame.

Iconography: The left decoration panel of the front shows part of the right wing with feathers of a winged figure.

Shown *en face* in the centre of the left short side is a winged child figure with a full face and curly hair that falls onto the neck at the back. The figure survives from the mid-chest to just above the head. Despite the damage, a longitudinal braided crest of hair running from the forehead to the nape can be discerned in the centre of the head. The ears are not visible beneath the hair. Only one outstretched wing is preserved, with precisely rendered feathers of two types: short, rounded feathers on the wing interior and long, pointed flight feathers on the exterior. There is an unidentifiable object in the background. It is a depiction of a winged eros who is possibly seated under a shell.

Dating: Late Antonine (?).

Lit.: Djurić 2001b, 48, No. 18; Djurić – Hebert *et al.* 2004, 400 (PET 15); Pochmarski 2015, 217; Ragolič 2023, 168, No. 164.

### **19. SARCOPHAGUS FRAGMENT** PL. 7

Prov.: Veliko Tinje, church of Sts Peter and Paul, south wall.

Loc.: Veliko Tinje, church of Sts Peter and

Paul, south wall.

Material: Eastern Alpine marble.

Condition: Left front panel with missing left and bottom edges, and minimal surface damage.

Size:  $39 \times 47$  cm.

Structure: Chest with a presumably tripartite front composed of a central inscription and lateral decoration panels. The lateral panels have a moulded frame, formed as a Norico-Pannonian volute in the upper part.

Iconography: The panel shows a female figure standing on a low pedestal and turned slightly to the right, toward the inscription panel. She stands in contrapposto, with her weight on the left leg, dressed in a tunic with short sleeves and a stola girt below her breasts. Her right arm is extended beside the body, holding a small kettle. Her left arm is bent, with the forearm positioned horizontally outward and holding a long-handled vessel facing upward. A mappa (towel) hangs over her left shoulder. Her head is shown in profile, turned to the right, with a melon coiffure tied into a chignon at the nape. The figure is a servant (camilla, delicatus/delicata) at a banquet, offering water and a towel for handwashing.

Dating: 3<sup>rd</sup> century (?).

Lit.: Muchar 1845, 343; Orožen 1889, 220; Klemenc – Saria 1939, 64; Pahič 1977a, 59; Ragolič 2023, 212, No. 244.

www: Lupa 4156.

# 20. SARCOPHAGUS FRAGMENT PL. 7

Prov.: Ptuj.

Loc.: Ptuj, PMPO, Inv. No. RL 1029.

Material: Eastern Alpine marble.

Condition: Upper left part of the front side with damaged bedding surface.

Size:  $76 \times 30 \times 17$  cm; side th. 17 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and

lateral decoration panels. The inscription panel has a moulded frame. The lateral decoration panels also have a moulded frame, formed as a Norico-Pannonian volute in the upper part.

Inscription: D(is) [M(anibus)] / Scanti[us?---] / V/---

Iconography: The left front panel shows a roughly carved female figure with long hair combed back and gathered in a net (?), then turned up above the neck and secured at the crown (*Scheitelfrizur*)

Dating: Second half of the 3<sup>rd</sup> century.

Lit.: Djurić – Hebert *et al.* 2004, 182, No. 16; Ragolič 2023, 99, No. 58.

www: Lupa 9420.

# 21. SARCOPHAGUS FRAGMENT PL. 7

Prov.: Ptuj, city walls, northwest roundel, 2022.

Loc.: Ptuj, city walls, northwest roundel.

Material: Eastern Alpine marble.

Condition: Bottom fragment with the standing surface damaged through reuse as base.

Size: 125 (visible)  $\times$  90 cm  $\times$  22 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The lateral decoration panel has a moulded frame, and is left rough.

Lit.: Cigler – Pukšič 2022, 36.

#### 22. SARCOPHAGUS FRAGMENT PL. 7

Prov.: Ptuj, Mala vojašnica, 1936.

Loc.: Ptuj, PMPO, Inv. No. G 2060 PL.

Material: Eastern Alpine marble, Pohorje quarry/Gummern (Sample PET 04; H. W. Müller).

Condition: Left part of the short side with missing top and partly damaged relief. The backside bears a Styrian coat-of-arms in relief.

Size:  $47 \times 61 \times 46$  cm.

Structure: Ionic base moulding characteristic of Eastern architectural sarcophagi and gar-

land spanning the width of the short side.

Iconography: The presumed left corner of the short side depicts a downward-pointed palm branch that reaches to the lower third of the surface. Its upper part is not visible due to damage. Next to it is a garland of oak leaves with acorns (*corona lunga*). Its upper end is damaged and unidentifiable, but does show an inwardly coiled tendril. Within the garland is a rosette of vine leaves and grape bunches (one is visible) with a damaged and unidentifiable raised central part.

Lit.: Schmid 1936, 101, No. 10; Djurić 2001b, 48, No. 19; Djurić – Hebert *et al.* 2004, 400 (PET 4); Ragolič 2023, 169, No. 167.

### 23. SARCOPHAGUS FRAGMENT PL. 8

Prov.: Ptuj, Panorama, 1983.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Lower left corner of the front side.

Size:  $68 \times 24 \times 55$  cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The short sides have a moulded frame on three sides, while the frame on the lower side is defined with a line.

Iconography: Depicted on the left front panel is a pedestal vessel (kantharos?) and tendril.

Lit.: Tušek 1986, 354; Djurić 2001b, 53, No. 28; Ragolič 2023, 167, No. 161.




Figure 49. Drawing of the sarcophagus fragment (by M. Lubšina Tušek)

### 24. SARCOPHAGUS FRAGMENT PL. 8

Prov.: Ptuj, Panorama, 1983.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Lower left corner of the rear side.

Structure: Chest with the short side bearing a frame that is moulded on three sides and simple on the lower side, and otherwise left rough.

Size:  $46 \times 31 \times 70$  cm.

Lit.: Tušek 1986, 354; Djurić 2001b, 53, No. 28;

Ragolič 2023, 167, No. 161.

# 25. SARCOPHAGUS FRAGMENT PL. 8

Prov.: Ptuj.

Loc.: Ptuj, castle, east façade of the west tower.

Material: Eastern Alpine marble.

Condition: Middle part of the bottom with

part of a short side.

Size:  $66 \times 45$  cm.

Structure: Chest with a short side bearing an

outlined panel that is coarsely finished.

Lit.: Unpublished.

### **26. SARCOPHAGUS FRAGMENT** PL. 8

Prov.: Ptuj.

Loc.: Ptuj, castle, east façade of the west tower.

Material: Eastern Alpine marble.

Condition: Part of the front side.

Size:  $33.5 \times 26$  cm.

Structure: Chest with an unrecessed tripartite

front. The panels are outlined and left rough.

Lit.: Unpublished.

### 27. SARCOPHAGUS FRAGMENT PL. 8

Prov.: Ptuj.

Loc.: Ptuj, castle, east façade of the west tower.

Material: Eastern Alpine marble.

Condition: Short side with damage to the bot-

tom and left edges.

Size:  $79 \times 84$  cm.

Structure: Chest with a short side bearing a decoration panel with a frame that is moulded on three sides and only outlined on the lower side.

Lit.: Unpublished.

### 28. LID FRAGMENT

PL. 8

Prov.: Ptuj, during the construction of a new school (*Benifiziatenhaus*), today Slovenski trg 4, 20 May 1853; rediscovered during the renovation of the house at Ob Grajeni 1, 1979.

Loc.: Ptuj, PMPO, Inv. No. RL 1018.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 36; H. W. Müller).

Condition: Left front corner fragment with an acroterium. The edges of the acroterium and other parts are damaged, the surface of the female portrait in the acroterium is also damaged.

Size:  $62 \times 42 \times 52$  cm.

Structure: High gabled lid of the Proconnesian type with large acroteria that do not exceed the height of the ridge. The ridge is missing. The front slope imitates a roof with tegulae and imbrices, which are also presented in outline on the vertical front side. The acroterium holds a portrait in relief. The pediment on the short side is undecorated.

Iconography: The left front acroterium holds a half-length portrait of a woman dressed in a tunic and rich, symmetrically worn cloak likely of a local type. Her hair is combed back to partially cover the ears, gathered at the nape into a wide mass, then secured at the crown (*Scheitelfrisur*).

Inscription: D(is) [M(anibus)] // P(ublius) Ael(ius) Vitalis Qv[---] / filius eor(um) et [---

Dating: Second quarter of the 3<sup>rd</sup> century.

Lit.: Knabl 1853, 213–214; Klemenc – Saria 1936, 47; Tušek 1986, 345; Šašel Kos 1993, 240; Djurić 2001b, 53, No. 22; Pochmarski 2015, 219; Ragolič 2023, 83–84, No. 41; CIL III 4072.

www: Lupa 4252; EDCS-28800800; HD068859; TM 195596.

### 29. LID FRAGMENT

PL. 9

Prov.: Ptuj.

Loc.: Ptuj, PMPO, Inv. No. RL 752.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 02; H. W. Müller).

Condition: Left rear corner with an acroterium, covering roughly half the whole width.

Size:  $89 \times 59 \times 71$  cm.

Structure: High gabled lid of the Proconnesian type with large acroteria that do not exceed the height of the missing ridge. The rear slope is smooth. The pediment and acroterium on the short side hold a coarsely finished decoration panel with a simple frame. The acroterium on the rear side does not have a defined decoration panel.

Lit.: Djurić 2001b, 53, No. 20; Djurić – Hebert *et al.* 2004, 400 (PET 2).

# **30. LID FRAGMENTS** PL. 9

Prov.: Ptuj, wall in the house at Prešernova 16, 1992.

Loc.: Ptuj, PMPO, Inv. No. RL 1016.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 16; H. W. Müller).

Condition: Left and right front corners with two acroteria and parts of the pediments. The relief depictions in the acroteria and pediments show partial surface damage.

Size: fragment 1  $42 \times 42 \times 53$  cm; fragment 2  $49 \times 43 \times 67$  cm.

Structure: Gabled lid with corner acroteria and plain slopes. The half-length figures in the acroteria are located in the corners and placed on a raised edge of the lid. The figures in the pediments are depicted in decoration panels with thin simple frames.

Iconography: The left acroterium holds a half-length youthful figure with curly hair, a cloak fastened at the right shoulder with a disc brooch. Next to the figure is a low-footed vessel (basket?) filled with flowers. It is the

personification of a season (*Tempus Anni*) – Spring. The right acroterion also holds a half-length youthful figure with curly hair and wearing a cloak. The figure has a bent right arm with an upward-facing open hand. Next to it is a low-footed vessel (basket?) filled with ears of grain. It is the personification of a season (*Tempus Anni*) – Summer. Depicted in both tympana is a gorgoneion with acanthus leaves.

Lit.: Tušek 1992b, 287 with fig.; Tušek 1993a; Tušek 1993b, 204; Djurić 2001b, 53, No. 23; Djurić – Hebert *et al.* 2004, 400 (PET 16); Ragolič 2023, 162–163, No. 153.

www: Lupa 9441.

### 31. LID FRAGMENT

Prov.: Ptuj, excavations in the basement at Slovenski trg 6, 1952.

PL. 10

Loc.: Ptuj, PMPO, Inv. No. RL 612.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 18; H. W. Müller).

Condition: Left front fragment of the lid broken off at the left front acroterium. Partially damaged surface of the inscription panel.

Size:  $37 \times 21 \times 23$  cm.

Structure: Gabled (?) lid possibly with corner acroteria, bearing an inscription panel with a simple frame on the vertical front side.

Inscription: D(is) [M(anibus)] // P(ublius) Fl(avius) Va[lerius?] / coniugi [---

Lit.: Bratanič 1953, 282; Djurić 2001b, 53, No. 24; Djurić – Hebert *et al.* 2004, 401 (PET 18); Ragolič 2023, 91–92, No. 50; ILJug 346.

www: EDCS 10000397, HD 074710.

### **32. LID FRAGMENT** PL. 10

Prov.: Spodnja Polskava, church of St Stephen, east wall.

Loc.: Spodnja Polskava, church of St Stephen, east wall.

Material: Eastern Alpine marble, Gummern quarry (Sample PET 42; H. W. Müller).

Condition: Part of an acroterium broken off on all sides and weathered.

Size:  $25 \times 34$  cm.

Structure: Gabled lid with corner acroteria (?).

Iconography: Half-length female figure shown en face, wearing a peplos fastened on the left shoulder with a rosette-shaped brooch and leaving the right shoulder and breast bare. Her hair is tied in a topknot. It is likely the depiction of a Hora, the personification of a season. Without attributes.

Lit.: Klemenc – Saria 1939, 48; Pahič 1977a, 55; Pahič 1977c, 267–268; Djurić 2001b, 53, No. 26; Djurić – Hebert *et al.* 2004, 403 (PET 42); Ragolič 2023, 252, No. 308.

www: Lupa 5308.

#### 33. LID FRAGMENT

PL, 10

Prov.: Miklavž na Dravskem polju, church of St. Nicholas, north wall.

Loc.: Miklavž na Dravskem polju, church of St. Nicholas, north wall.

Material: Eastern Alpine marble, Pohorje quarry/Gummern (Sample PET 43; H. W. Müller).

Condition: Part of a left front acroterium with missing top and left parts. Surface partially damaged.

Size:  $31 \times 23$  cm.

Structure: Gabled lid with corner acroteria bearing decorative fields in simple frames.

Iconography: Half-length figure shown *en face* and dressed in a tunic, next to it a basket with flowers. It is the personification of a season (*Tempus Anni*) – Spring.

Lit.: Pahič 1969, Note 223, 103, Pl. 5; Pahič 1977a, 51; Djurić 2001b, 53, No. 27; Djurić – Hebert *et al.* 2004, 403 (PET 43); Ragolič 2023, 275, No. 348.

www: Lupa 5888.

### 34. LID FRAGMENT

PL. 10

Prov.: Ptuj, between 1941 and 1945.

Loc.: Ptuj, PMPO, Inv. No. RL 449.

Material: Eastern Alpine marble.

Condition: central part of an acroterium with surface damage.

Size:  $39 \times 13 \times 26$  cm.

Structure: Gabled lid with corner acroteria.

Iconography: Positioned in the corner of the acroterium is a female (?) head shown *en face* with the hair combed back (?) and down the neck. It probably represents a Hora, a personification of a season. Without attributes.

Lit.: Unpublished.

# 35. LID FRAGMENT

PL. 11

Prov.: Ptuj (?).

Loc.: Ptuj, PMPO, Inv. No. RL 483.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 06; H. W. Müller).

Condition: Lower part of the lid broken off at the left front acroterium.

Size:  $51 \times 34 \times 22$  cm.

Structure: Gabled lid with imitation tegulae and imbrices on the front slope that terminate at the relatively narrow vertical front edge bearing an inscription, and presumably with corner acroteria.

Inscription: /---/ VAL(---

Lit.: Djurić 2001b, 53, No. 21; Djurić – Hebert *et al.* 2004, 400 (PET 6); Ragolič 2023, 151, No. 132.

### **36. LID FRAGMENT**

PL. 11

Prov.: Ptui.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Lower part of a lid.

Size:  $38 \times 28 \times 9$  cm; front edge h. 13 cm.

Structure: Gabled lid with imitation tegulae and imbrices probably on the front slope, ter-

minating at a vertical front edge.

Lit.: Unpublished.

### 37. LID FRAGMENT

PL. 11

Prov.: Šmartno na Pohorju, church of St Mar-

tin, presbytery window.

Loc.: Šmartno na Pohorju, church of St Mar-

tin, presbytery window.

Material: Eastern Alpine marble.

Condition: Fragmented part of a lid with ridge

and slope.

Size: unknown.

Structure: Gabled lid with a flat ridge.

Lit.: Unpublished.

# 38. LID FRAGMENT

PL. 11

Prov.: Ptuj, Osnovna šola Ljudski vrt, excava-

tion by Ivan Žižek in 2009–2010.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Complete lid with heavily eroded

surface and destroyed acroteria.

Size:  $260 \times 150 \times 50$  cm.

Structure: Hipped lid with a flat ridge, plain slopes and corner acroteria. One of the short sides has a clamp hole. The vertical front edge is finely finished.

Lit.: Horvat – Dolenc Vičič 2010, 122–123, No. 55; Djurić 2019, 53–54; Ragolič 2023, 172–173, No. 174.

#### **39. LID FRAGMENT** PL. 11

Prov.: Ptuj (?).

Loc.: Graz, Universalmuseum Joanneum, with-

out inv. no.

Material: Eastern Alpine marble.

Condition: Upper part of an acroterium with a

weathered surface.

Size:  $24 \times 15 \times 22$  cm.

Structure: Gabled lid with corner acroteria.

Iconography: Top of a head with a topknot, probably belonging to a half-length (female?) figure, to the right of it a basket of fruit. The

figure is a personification of a season – Spring.

Lit.: Unpublished. www: Lupa 16580.

### 40. LID FRAGMENT

Prov.: Starše. Loc.: Lost.

Material: Eastern Alpine marble.

Condition: Right part of a sarcophagus lid

Size:  $87 \times 28 \times ?$  cm.

Structure: Hipped lid with imitation tegulae and imbrices, possibly only on the front slope.

Source: R. Gaupmann, Verzeichniß sämmtlicher in St. Johann am Draufelde zum Verkaufe liegender Römerstein[e], Pettau 1874 (BDA-INVE\_ZK\_25\_1874\_177) (information by Stephan Karl)

Lit.: Unpublished.




Figure 50. Drawing of the sarcophagus lid (Vienna, Bundesdenkmalamt-INVE\_ZK\_25\_1874\_177\_2\_8, by R. Gaupmann)

### 41. LID FRAGMENT

PL. 11

Prov.: Ptuj.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Central part of the front side.

Size: Unknown.

Structure: Possibly gabled lid with imitation tegulae and imbrices, perhaps only on the front slope.

Lit.: Unpublished.

# **ASH CHESTS**

### 42. ASH CHEST

PL. 12

Prov.: Ptuj, Prešernova 4, prior to 1850.

Loc.: Ptuj, PMPO, Inv. No. RL 37.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 34; H. W. Müller).

Condition: Complete chest with damage to the lower front edge and reliefs.

Size:  $77 \times 44 \times 54$  cm; bottom th. 23 cm; side th. 9–10 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame on all four sides. The lateral front panels have a simple frame, the upper part of which is in the form of a geometrically irregular Norico-Pannonian volute.

Inscription: Cartoria Calandina / v(iva) f(ecit) sibi et Aur(elio) Verin/o co(n)iugi qui vixit / an(nos) LXX(?) (e)t Aure/li(a)e Ver(a)e 'e't Aurel/i(a)e Verecund(a)e

Iconography: The left front panel holds an en face and full-figure depiction of standing Cartoria Calandina. She is shown in a tunic and symmetrically worn, traditional rectangular cloak (Rothe 2012, 191) with a thick border around the neck and down to the waist, emphasising the uncovered chest and head. Her right arm is bent and placed above the waist, holding an unidentified object. Her left arm is extended beside the body, also holding an unidentified object. She wears a necklace. Her face is damaged. The hair is gathered behind the ears at the nape into a wide, flat mass and turned upward (Scheitelfrisur); she may be wearing a wig or her hair may be covered with a bonnet. The right front panel holds an en face and full-figure depiction of Aurelius Verinus standing in contrapposto, with his weight on the right leg. He is wearing a belted knee-length tunica manicata, over it a sagum fastened on his right shoulder with a disc brooch and hanging over his bent left arm, in which he holds a scroll at waist height, pointing to it with the index and middle fingers of his bent right arm. His face is severely damaged, but does show a short beard and short hair.

Dating: First half of the 3<sup>rd</sup> century.

Lit.: Gurlitt 1892, 179; Abramić 1925, 57, No. 40; Ložar 1927, 23–24, No. 79; Hoffiller – Saria 1938, 178, No. 394; Diez 1948, 154, No. 1; Jevremov 1988, 88, No. 77; Djurić 2001a, 122 No. 1; Djurić – Hebert *et al.* 2004, 402 (PET 34); Pochmarski 2015, 216; Ragolič 2023, No. 47; CIL III 13412.

www: Lupa 3758; EDCS-29601598; HD068855; TM 409586.

### 43. ASH CHEST

PL. 12

Prov.: Hajdina, cemetery, prior to 1827.

Loc.: Graz, Universalmuseum Joanneum, Inv. No. 93.

Material: Eastern Alpine marble.

Condition: Complete chest with damaged reliefs.

Size:  $89 \times 56 \times 61$  cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame on all four sides. The lateral front panels have a simple frame, the upper part of which is in the form of a geometrically irregular Norico-Pannonian volute.

Inscription: M(arcus) Ulp(ius) Tertullus / v(ivus) f(ecit) sibi et Ulp(iae) Antoniae / coniugi an(norum) XL et Ulp(io) / Tutori filio an(norum) XXXVI /

et Ulp(ius) Tertius / fil(ius) / Ulp(ia) Tutorina / et Ulp(ius) Tutorinus nepotes

Iconography: The right and left front panels show mirror images of a mourning eros standing on a low pedestal with concave sides, the legs crossed and the weight resting on the outer leg. Both are leaning onto an inverted torch; they have one arm bent and supporting the head, while the elbow is resting on the opposite hand that is placed on the torch next to the inscription panel. Their small wings are turned downward. The left eros has a damaged head, turned inward in a three-quarter profile. His hair is gathered into a bun at the nape, with a hair crest running from his forehead to the crown. The right eros has his head turned en face and tilted inward, with long hair covering his neck and a hair crest running from his forehead to the crown.

The left short side holds a depiction of an ascia, the right short side that of an archipendulum.

Dating: Late Antonine to Early Severan.

Lit.: Povoden 1818, 210–211; Steinbüchel 1829, 64; Hoffiller – Saria 183–184, No. 407; Diez 1948, 155, No. 4; Modrijan – Weber 1979–81, 87, No. 93; Djurić, 2001a, 122, No. 4; Pochmarski 2014, 361; Pochmarski 2015, 213; Ragolič 2023, 105–107, No. 65; CIL 03, 04084.

www: Lupa 1697; EDCS-26600469; HD066997; TM 407681.

# **44. ASH CHEST** PL. 13

Prov.: Maribor, Koroška cesta 7, prior to 1902. Loc.: Maribor, PMMb Inv. No. A 2309.

Material: Eastern Alpine marble, Gummern quarry (Sample MAR 15, Harald W. Müller).

Condition: Chest with missing top part. The head of the right figure is remodelled.

Size:  $129 \times 57$  (reconstr. 64)  $\times$  84 cm; bottom th. 18 cm; side th. 11 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame. The lateral front panels have a moulded frame.

Inscription: M(arco) Ulpio Ca[tul]/lino qui vixit / ann(os) XLV M(arcus) Ulp(ius) Seve(r)i/anus et Ulpia Severian(a) / filii et Iulia / Ianuaria ux{s} or her(edes) / f(aciendum) curav(erunt) sec(undum) / vol(untatem) testam(enti)

Iconography: The left and right front panels hold mirror images of a mourning eros on a high pedestal with concave sides, the legs crossed and the weight resting on the outer leg. With the head raised, they are leaning onto a vertically positioned inverted torch with the inner arm raised and bent, while the other hand hangs loosely at the side and holds a pruning knife (falx). The small wings with distinctly carved feathers are raised beside the head that is turned inward. The hair is pulled back and tied into a bun at the nape.

Dating: Late Antonine to Severan.

Lit.: Premerstein 1904, 181, Fig. 129; Hoffiller – Saria 48, No. 111; Saria 1939, 76, Fig. 4; Diez 1948, 155, No. 5; Pahič 1970, 190, Fig. 23; Pahič 1977a, 50; Pahič 1983, 124; Pochmarski 1998, 183, No. 10; Djurić, 2001a, 122, No. 4; Drack 2008, 98–99; Pochmarski 2014, 361; Pochmarski 2015, 213; Ragolič 2023, 254–255, No. 312; CIL III 04084.

www: Lupa 2129; HD066917; EDCS-14400611; TM 403924.

### **45. ASH CHEST** PL. 13

Prov.: Ptuj, prior to 1600 at the church of St George, in 1829 recorded at Kurelčeva ulica 31, Varaždin.

Loc.: Varaždin, Gradski muzej, Inv. No. 66345.

Material: Eastern Alpine marble.

Condition: Chest largely broken just above the bottom, with only the left part of the left short side and part of the front surviving above. Reliefs weathered.

Size:  $102 \times 51 \times 68$  cm; bottom th. 17 cm, side th. 12–13 cm.

Structure: Chest with a tripartite front com-

posed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame on all four sides. The lateral front panels have a simple frame, formed as a Norico-Pannonian volute in the upper part.

Inscription: Victori Qua/drati et Iuli(a)es(!) / Veranill(a)es(!) / Iulius Victori/us Quadratus / filius eorum hic / positus

Iconography: The left front panel shows a full-length figure of a man standing on a pedestal with concave sides. He is dressed in a belted tunic reaching above his knees and a *sagum* that extends to the upper part of his calves and is fastened at the right shoulder. His right arm is bent and placed diagonally across the chest to the left shoulder, with the hand showing extended index and middle fingers, possibly holding an object. His left arm is extended along the body, possibly holding an object. His face is damaged and unrecognizable, as is his short hairstyle. The right front panel shows a two-handled vessel – kantharos – with vine growing from it.

Dating: 3<sup>rd</sup> century.

Lit.: Saria 1946, 62–64, No. 17, Fig. 35; Diez 1948, 156, No. 9; Ilijanić 1961; Fulir 1969, 405; Fulir 1970, 9; Djurić 2001a, 122, No. 9; Ragolič 2023, 112–113, No. 71; CIL III 4082; ILJug 351.

www: Lupa 4262; EDCS-28800808; HD074455; TM 407679.

### **46. ASH CHEST** PL. 13, 14

Prov.: Savci, vineyard of Filip Petek, 1796.

Loc.: Graz, Universalmuseum Joanneum, Inv. No. 84.

Material: Eastern Alpine marble.

Condition: Chest without bottom. Surface heavily weathered.

Size:  $89 \times 36 \times 65$  cm; bottom th. 13 cm, side th. 11-13 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame. The lateral front panels have a simple frame, formed as a Norico-Pannonian volute in the upper part. The short sides have decoration panels within simple frames that have a rectangular widening in the centre of the upper edge, intended for a clamp hole. The bedding surface has a raised semicircular edge along the interior to keep the lid in place.

Inscription: D(is) M(anibus) / Val(erius) Valens v(ivus) f(ecit) s(ibi) et / Ulp(iae) Licini(a)e coniug(i) / carissim(ae) q(uae) v(ixit) an(nos) XXV et / T(i-to) Val(erio) Valentino f(ilio) et / Valeriano Iustino n(epotibus)

Iconography: The left front panel holds a fulllength and en face depiction of a man wearing a belted and knee-length tunica manicata. The belt is hidden under the overlapping tunic. He also wears a *sagum* fastened at his right shoulder with a disc (?) brooch. His bent left arm, held at waist height, holds a scroll, to which he is pointing with the fingers of his bent right arm. His beardless face is damaged, his hair is short. The right front panel also holds a full-length and en face depiction of a man wearing a belted, knee-length tunica manicata and a sagum fastened at the right shoulder. The belt is hidden beneath the overlapping tunic. His arms are bent and positioned at waist height. His face and hairstyle are damaged, but the silhouette suggests a medium-length beard.



Gabernigg
Pfarre St. Lorenzen
unter Pettau
Weißer Marmor





Figure 51. Drawing of the ash chest (from Knabl 1851)

The right short side bears a Dionysian motif of a two-tiered kantharos, from which grow two intertwining vines with leaves, grape bunches and tendrils. The left short side shows a peacock reaching with his head toward the basket with ears of grain (?) held by a winged eros shown in profile and identified as a personification of a season (*Tempus Anni*) – Summer.

Dating: First half of the 3<sup>rd</sup> century.

Lit.: Knabl 1851, 64–66; Skrabar 1935, 36–37; Klemenc – Saria 1936, 66; Hoffiller – Saria 1938, 196, No. 445; Diez 1948, 156, No. 10; Pahič 1977a, 50; Modrijan-Weber 1979–81, 94, No. 84; Hudeczek 2004, No. 8; Djurić, 2001a, 122, No. 9; Lamut 2013; Pochmarski 2014, 357, Fig. 4; Lamut 1915, 312–319; Pochmarski 2015, 216–217; Handy – Pochmarski 2020, 281, No. 25; Ragolič 2023, 314–316, No. 419; CIL III 04081+p.1044.

www: Lupa 1696; EDCS-26600467; HD066088; TM 407678.

# **47. ASH CHEST** PL. 14, 15

Prov.: Ptuj, reused in the late 16<sup>th</sup>/early 17<sup>th</sup> century as a wash basin in the Minorite Monastery, in 1945 found in the ruins of a house in Dravska ulica, opposite the water tower.

Loc.: Ptuj, PMPO, Inv. No. RL 453, now in the Minorite Church in Ptuj

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 14; H. W. Müller).

Condition: Converted into a wash basin by carving a deep rectangular hole into the front side and hollowing out the bottom to form the lower part of the basin. The front side is almost entirely carved away and the upper surface removed.

Size:  $112 \times 69 \times 45$  cm; bottom th. 22–35 cm, side th. 11 cm.

Structure: Chest with a tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a moulded frame, presumably straight on all four sides. The lateral front panels have a moulded frame, possibly formed as a Norico-Pannonian

volute in the upper part. The short sides have decoration panels within a simple frame.

Iconography: The left front panel shows a fulllength figure of a man on a rectangular pedestal. He is dressed in a belted tunic that reaches just above his knees and likely has long sleeves (tunica manicata). Only the terminal part of the belt, identified as a cingulum militare, survives, which he holds with his right hand in a manner known from some depictions of soldiers from the first half of the 3rd century. He has a long sagum draped over his shoulders, probably fastened with a missing brooch at the right shoulder. The outline of his heavily damaged head suggests a thick beard, such as is mainly characteristic of the Severan period. All surviving elements identify him as a military figure in 'camp dress'.

The left short side shows a forward-facing, standing panther with its left front paw on a drinking horn made from a goat horn. The right short side shows two crossing vines with two leaves, two grape bunches and tendrils growing from a centrally placed, two-tiered vessel on foot without handles; albeit without handles, parallels suggest it can be identified as a kantharos.

Dating: Severan

Lit.: Diez 1948, 156, No. 12; Djurić 2001a, 122, No. 11; Djurić 2001b, 50, Fig. 11; Djurić – Hebert *et al.* 2004, 400 (PET 14); Ragolič 2023, 157, No. 143; Djurić 2023.

www: Lupa 9439.

# 48. ASH CHEST

PL. 15

Prov.: Velika Nedelja, 1894.

Loc.: Ptuj, PMPO, Inv. No. RL 104.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 29; H. W. Müller).

Condition: Complete chest with missing part of the upper right corner and damaged upper and lower edges. Broken along two horizontal lines. Reused as a trough, with a large round drainage hole on the right side of the inscription panel. Weathered relief surface.

Size:  $173 \times 70 \times 93$  cm; bottom th. 35 cm, side th. 17–18 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame on all four sides. The lateral front panels have a moulded frame on three sides, formed as a Norico-Pannonian volute in the upper part. In the right front panel, the lower frame removed to fit the legs of the figure. The short sides have decoration panels within a fillet moulded frame on three sides, formed as a double Norico-Pannonian volute in the upper part with a rectangular widening between them intended for a clamp hole, while the lower side has a simple frame.

Inscription: Fann(ius) Florentinus / mil(es) leg(io-nis) XIIII G(eminae) et Ulp(ia) / Severina coni(ux) v(ivi) f(ecerunt) s(ibi) / et Fanni(i)s Florentin(a)e ann(orum) / XVI et Super(a)e ann(orum) IIII et / Floriano ann(orum) II et Floro / ann(i) I fili(i)s

Iconography: The right front panel holds a full-length *en face* depiction of a man (Fannius Florentinus), without a pedestal, wearing a belted *tunica manicata*, reaching above his knees, and a *sagum* that extends to his knees at the back, fastened at the right shoulder with a disc brooch. He has a belt with a large ring buckle on his hips, with a long strap end curving from the middle to the right hip, where it loops under the belt and hangs vertically down his side. His right arm is bent and positioned at waist height, while his left hand may be resting on the hilt of a sword suspended at his left hip. His face and his short hairstyle are unclear.

The left front panel holds a full-length *en face* depiction of a woman (Ulpia Severina) dressed in a belted floor-length *tunica manicata* and an asymmetrical *palla* draped over her left shoulder and held in her slightly bent left arm. Her belt has an oval buckle. Her right arm is bent above the belt to reach across the chest. Her

face is unclear. She wears a melon coiffure with the hair falling onto the neck and likely gathered into a braided chignon.

The right short side shows a laurel (?) garland with a ribbon and under it full-length *en face* depictions of four children, two daughters and two sons. The surviving lower part of the woman on the far left is wearing a floor-length tunic and *palla*. The woman on her right is shown in a floor-length *tunica manicata*, her arms are bent and placed on the waist. She is holding an unidentifiable round object. The boys on the right-hand side wear a tunic, reaching just below their knees, and a *sagum* fastened at the right shoulder. Their right arms are bent and placed on the chests just above the belt, while the left arms are extended beside the body, holding an unidentifiable object.

The left short side shows an oversized mensa tripes with cabriole legs in the centre, laden with small loaves of bread, flanked by a household slave-servant (camilla and camillus, delicati) on either side. On the left is a female servant in contrapposto, with the weight on her left leg, wearing a floor-length and short-sleeved tunic and a stola girt below the breasts with a wide belt. With her slightly bent right arm held beside the body, she is holding a small kettle, while her raised and bent left arm carries a vessel with a long handle; a mantela hangs over her left shoulder. Placed on the ground between her and the table are two flasks in wicker containers with a ring handle. To the right of the table stands a camillus in contrapposto, with the weight on his left leg, dressed in a short-sleeved tunic reaching just below his knees. His left arm is extended along his body and holds a glass flask in a wicker container with a ring handle. His right arm is bent and raised in front of his chest, holding a cup. Placed on the ground between him and the table is a one-handled jug with a constricted neck and a wide mouth. Both figures have damaged heads and unclear faces. The woman has a melon coiffure with the hair falling onto her neck, while the man has short hair.

Dating: First half of the 3<sup>rd</sup> century.

Lit.: Gurlitt 1895, 64; Hoffiller – Saria 1938, 197, No. 446; Diez 1948, 158, No. 15; Pahič 1977a, 59; Jevremov 1988, 86–87, No. 75; Djurić 2001a, 122, No. 12; Djurić – Hebert *et al.* 2004, 402 (PET 29); Pochmarski 2015, 215, Fig. 5; Handy – Pochmarski 2020, 291, No. 70; Ragolič 2023, 327–329, No. 436; CIL III 14065.

www: Lupa 3781; EDCS-29900136; HD069150; TM 409775.

### 49. ASH CHEST

Prov.: Ptuj, Vičava, while digging a trench at Vurberška cesta, 1946.

Loc.: Ptuj, PMPO, Inv. No. RL 448.

Material: Eastern Alpine marble.

Condition: Complete chest broken during transport to the museum above the bottom and diagonally across the middle. Restored.

Size:  $137 \times 70 \times 76$  cm; bottom th. 32 cm, side th. 15 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame on all four sides. The lateral front panels have a simple frame, formed as a Norico-Pannonian volute in the upper part. The short sides have decoration panels marked with a carved line and with a rectangular widening at the centre of the upper edge intended for a clamp hole. The bedding surface has a raised semicircular edge along the interior to hold the lid. The standing surface has a sunken centre.

Iconography: The left and right front panels hold mirror depictions of nude winged boys in *contrapposto*, with the weight on the outer leg. The outer arm is bent and placed with the hand on the opposite shoulder, while the inner arm is extended along the inverted torch, serving as support, and holding a hand garland that is wrapped around the torch. The head is shown in three-quarter profile, looking downward. The melon hairstyle has a central ridge extend-

ing onto the forehead and curls covering the back of the neck.

Dating: Late Antonine to Early Severan.

Lit.: Jevremov 1988, 90–91, No. 83; Djurić 2001a, 122, No. 27; Pochmarski 2014, 361, Fig. 7; Pochmarski 2015, 216, Fig. 2; Ragolič 2023, 156–157, No. 142.

www: Lupa 4213.

### 50. ASH CHEST

PL. 17

Prov.: Ptuj.

PL. 16, 17

Loc.: Ptuj, City Tower, Inv. No. RL 783.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 51; H. W. Müller).

Condition: Bottom part with heavily weathered surface.

Size:  $119 \times 27$  (reconstr. 49)  $\times$  43 cm; bottom th. 27 cm, side th. 16–17 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a moulded frame. The lateral front panels have a moulded frame.

Iconography: The left and right front panels show mirror images of a mourning eros on a low pedestal. They stand in *contrapposto* with the weight on the outer leg and an inverted torch along the inner leg.

Lit.: Abramić 1925, 142; Diez 1948, 156, No. 6; Pochmarski 1998, 191, No. 78; Djurić 2001a, 122, No. 6; Pochmarski 2015, 213; Ragolič 2023, 162, No. 152.

www: Lupa 5780.




Figure 52. Drawing of the ash chest (Vienna, graphic imprint, Steinbüchel?, Pl. VII)

# 51. ASH CHEST

PL. 17

Prov.: Hajdina, golf course, Lot No. 1120/2, Hajdina cadastral municipality, 1997.

Loc.: Ptuj, PMPO, Inv. No. 1023. Material: Eastern Alpine marble.

Condition: Bottom part.

Size:  $147 \times 28 \times 90$  cm; bottom th. 24 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame, presumably on all four sides. The lateral front panels have a moulded frame. The short sides have a simple frame.

Inscription: --] / R+M Q+++QVL Iustinianum / annorum quatuor meser (=mensium ?) / IIII Ursinum annorum dece(m) m(ensium) V / Fl(avius) Iustianus et Valeria Vivia vi/vi fecerunt parentes infelicissimi

Iconography: The left and right front panels show a pedestal with concave sides, the right one also the lower legs of a full-length figure standing on it. The short sides show vine with grape bunches and tendrils growing from a pedestal vessel, most likely a two-tiered kantharos with crossing vines.

Lit.: Lubšina Tušek 2001, 95 with fig.; Pochmarski 2014, 354, Fig. 1; Pochmarski 2015, 219; Ragolič 2023, 90–91, No. 49.

www: Lupa 9437.

# **52. ASH CHEST BOTTOM** PL. 18

Prov.: Dravinjski vrh near Videm pri Ptuju, church of St John the Baptist, altar table.

Loc.: Dravinjski vrh near Videm pri Ptuju, church of St John the Baptist, altar table.

Material: Eastern Alpine marble.

Condition: Bottom part with missing left part and right front corner.

Size:  $148 \times 14 \times 83$  cm.

Structure: Chest with an unrecessed tripartite

front composed of a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame, while the lower side has a simple frame. The lateral front panels have a moulded frame on two sides, the lower side has a fillet moulded frame. The short sides have decoration panels probably with a simple frame.

Iconography: The right front panel shows a pedestal with concave sides. The right short side shows the remains of a relief along the lower edge.

Lit.: Šubic 1969, 99; Pahič 1977a, 47; Ragolič 2023, 313, No. 416.

### **53. ASH CHEST FRAGMENT** PL. 18

Prov.: Črešnjevec, church of St Michael, north wall.

Loc.: Črešnjevec, church of St Michael, north wall.

Material: Eastern Alpine marble.

Condition: Bottom part covering three quarters of the front side with missing upper part and all raised surfaces removed.

Size:  $77 \times 37$  cm.

Structure: Chest with a tripartite front composed of a central inscription and lateral decoration panels. The inscription panel likely had a straight moulded frame. The lateral front panels likely also had a moulded frame.

Inscription: --] et Potentinia Cl[---] / con(iux) vivi fec(erunt) sibi / et Aureli(a)e Antoni(a)e / fili(a)e {vi}viv(a)e

Iconography: The right front panel shows a man on a high pedestal with concave sides. The man is in *contrapposto* with the weight on his left leg, wearing a belt knee-length tunic and a *sagum* reaching to the mid-calf.

Lit.: Pahič 1984, 222, Fig. 28; Djurić 2001a, 122, No. 46; Ragolič 2023, 234, No. 274.

www: Lupa 4693; HD018366; EDCS-06100495; TM 214744.

# **54. ASH CHEST FRAGMENT** PL. 18

Prov.: Kebelj, church of St Margaret of Antioch, renovation in 2003.

Loc.: Kebelj, church of St Margaret of Antioch.

Material: Eastern Alpine marble.

Condition: Bottom part with missing standing surface and right lower corner. Surface severely weathered.

Size:  $89 \times 29 \times 40$  cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame. The lateral front panels have a simple frame.

Inscription: S AN +++ / RIVS. Secundo et / Secundino, filiis vivis (reading A. Ragolič).

Iconography: Both lateral front panels show high pedestals with concave sides holding a male (?) figure with bear legs surviving from the knees down.

Lit.: Gulič 2006, 126.

### 55. ASH CHEST

PL. 19

Prov.: VelikoTinje, church of Sts Peter and Paul, north wall foundations.

Loc.: Veliko Tinje, church of Sts Peter and Paul, north wall foundations.

Material: Eastern Alpine marble.

Condition: The preserved chest is built into the foundation of the church, its front side invisible.

Size:  $75 \times 50 \times 60$  cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded (?) frame.

Iconography: The lateral front panels hold mirror depictions of mourning erotes holding torches diagonally across the chest.

Inscription: D(is) M(anibus) / Valentinus / li(ber-

tus) vi(vus) fe(cit) si(bi) et / sui(s) Ursul(a)e / con(iugi) car(issimae) an(norum) / XXV et Ursi(!) fi(lio) / an(norum) V

Lit.: CIL III 11717; Hoffiller – Saria 1938, 39–40, No. 88; Klemenc – Saria 1939, 64; Diez 1948, 160–161, No. 20; Cermanović 1965, 98, No. 2; Pahič 1977b, 59; Djurić 2001a, 122, No. 20; Gulič 2007, 18–19; Pochmarski 2014, 362; ILLPRON 1925; Ragolič 2023, 210–211, No. 242.

www: Lupa 3625; EDCS-14600199; HD066803.




Figure 53. Drawing of the ash chest (by V. Kmetič, from Hoffiler – Saria 1938)

# **56. ASH CHEST FRAGMENT** PL. 19

Prov.: Dravinjski vrh near Videm pri Ptuju, church of St John the Baptist, 1966.

Loc.: Dravinjski vrh near Videm pri Ptuju, church of St John the Baptist, east wall.

Material: Eastern Alpine marble.

Condition: Right short side with missing surface and lower part.

Size:  $12 \times 56 \times 84$  cm.

Structure: Chest with a tripartite front composed of a central inscription and lateral decoration panels.

Iconography: The right front panel shows a figure of a youthful man wearing a tunic and probably trousers. The tunic is girt, with the

belt hidden under the overlapping tunic. The left leg is extended as the supporting leg, while the right leg is bent and crossed over the left. The poorly distinguishable left arm is bent and placed diagonally at waist level, while the right arm is bent and raised toward the face. It is likely the depiction of *Attis tristis*, or the Sad Easterner, with a downturned *pedum* to his right.

Lit.: Šubic 1967, 98–99; Šubic 1975, 95, No. 9; Pahič 1977b, 47, Fig. 9; Djurić 2001a, 123, No. 44; Ragolič 2023, 313, No. 417.

www: Lupa 4275.

# **57. ASH CHEST FRAGMENTS** PL. 19

Prov.: Ptuj, Trstenjakova ulica 9, Lot No. 1112, Ptuj cadastral municipality, 1959.

Loc.: Ptuj, PMPO, Inv. No. RL 720.

Material: Eastern Alpine marble.

Condition: Left upper part of the front side with a weathered surface.

Size:  $54 \times 26 \times 16$  cm; side th. 16 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame. The lateral front panels have a simple frame, formed as a Norico-Pannonian volute in the upper part.

Inscription: [---]/Pauli[ --- /  $qui \ vix$ [--- / [..] MF/---

Iconography: The left front panel holds an en face depiction of a man dressed in a tunic and sagum, fastened on the right shoulder with a missing fibula. Both arms are bent towards the chest. The left hand holds a rod-like object, likely a scroll, to which he points with the index and middle fingers of his right hand. The face and hairstyle are damaged and unclear. The outline of the head shows no traces of a beard.

Lit.: Mikl 1960–61, 158, Fig. 2; Djurić 2001a, 122, No. 40; Ragolič 2023, 119, No. 77; ILJug 1154.

www: EDCS-100001157; HD 074729.

# **58. ASH CHEST FRAGMENT** PL. 19

Prov.: Ptuj, restoration of the Minorite church of Sts Peter and Paul, Lot No. 1407, Ptuj cadastral municipality, 1951.

Loc.: Ptuj, PMPO, Inv. No. RL 600.

Material: Eastern Alpine marble.

Condition: Right upper part of the front side with slightly damaged surface.

Size:  $54 \times 26 \times 12$  cm; side th. 12 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame. The lateral front panels have a simple frame, formed as a Norico-Pannonian volute in the upper part.

Inscription: [---]us / [---]le / [---

Iconography: The right front panel holds the depiction of a nude youth surviving just above the hip. His curved torso is draped with a cloak over his left shoulder. His left arm is extended down along the body, while his right arm is bent upward and holds a *thyrsus* with a plant tip, possibly of ears of grain. His beardless head is turned slightly toward the inscription panel, has large almond-shaped eyes and curly hair with a central ridge. He is likely a personification of a season (*Tempus Anni*) – Summer.

Lit.: Bratanič 1952, 305, Fig. 5; Djurić 2001a, 123, No. 41; Pochmarski 2015, 213; Ragolič 2023, 141, No. 112; ILJug 349.

www: EDCS 10000400; HD 068836.

# **59. ASH CHEST FRAGMENT** PL. 20

Prov.: Ptuj, Dominican Monastery.

Loc.: Ptuj, Dominican Monastery, above the passage from the monastery to the bell tower.

Material: Eastern Alpine marble.

Condition: Left upper part of the front side with missing lower part and well-preserved surface. The groin area has been remodelled.

Size:  $44 \times 34$  cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame. The lateral front panels have a moulded frame, formed as an irregular Norico-Pannonian volute in the upper part.

Iconography: The left front panel shows a winged child-like figure *en face*, with the head turned down and to the left, and curly hair tied in a chignon at the nape. The genitalia were most likely removed or remodelled when the piece was built into the monastery (eros transformed into an angel). Both arms are bent upward, resting on top of an inverted torch. The legs are probably crossed, with the weight on the right leg.

Dating: Late Antonine (?).

Lit.: Hoffiller – Saria 1938, 190, No. 426; Diez 1948, 156, No. 7; Cermanović 1965, 99, No. 10; Pochmarski 1998, 185, No. 24; Djurić 2001a, 122, No. 7; Pochmarski 2015, 213, 215; Ragolič 2023, 165, No. 157.

www: Lupa 3776; EDCS 30300697.

### **60. ASH CHEST FRAGMENT** PL. 20

Prov.: Ptuj (?).

Loc.: Ptuj, PMPO, Inv. No. RL 33.

Material: Eastern Alpine marble.

Condition: Left upper corner of the front side with heavily weathered surface.

Size:  $51 \times 17 \times 35$  cm; side th. 13–14 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame. The lateral front panels have a simple frame, formed as a Norico-Pannonian volute in the upper part.

Inscription: Aur(elio) Barbo V/--- / AEI(?)/---

Iconography: The left front panel shows a standing *en face* figure of a deceased woman in a tunic and symmetrically worn cloak with a thickened border curving around the neck and

onto the chest across the middle of the shoulders. Her right arm is bent and placed above the waist, holding an unidentifiable object. She is wearing a necklace. The face is damaged, her hair is gathered behind the ears into a wide, flat mass, turned up at the neck and secured at the crown (*Scheitelfrizur*). The left short side shows a stylised depiction of a garland with a ribbon.

Dating: 3<sup>rd</sup> century.

Lit.: Hoffiller – Saria 1938, 177, No. 392; Diez 1948, 154, No. 2; Cermanović 1965, 98, No. 5; Djurić 2001a, 122, No. 2; Ragolič 2023, 84–85, No. 43.

www: EDCS-11301061; HD069024

### **61. ASH CHEST FRAGMENT** PL. 21

Prov.: Črešnjevec, church of St Michael, east precinct wall, 1858.

Loc.: Črešnjevec, park in front of the church of St Michael.

Material: Eastern Alpine marble.

Condition: Left lower part of the front side with missing corner and removed raised surface

Size:  $36 \times 42 \times 38$  cm; bottom th. 38 cm, side th. 13 cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame on all four sides.

Inscription: Max[---] / (obiit)) an(norum) [---] / et Ma[---] / infe[licissima] / eoru[m ---] / <math>Am(an) tia [---]

Iconography: the left front panel shows an outline of a man dressed in a long garment, probably standing on a pedestal.

Lit.: Knabl 1859, 87; Abramić 1933, 132, Fig. 43; Hoffiller – Saria 1938, 38, No. 84; Diez 1948, 158, No. 17; Pahič 1977a, 46; Pahič 1990, 172–173, Fig. 41; Djurić 2001a, 122, No. 17; Ragolič 2023, 236, No. 277; CIL III ad 5302; ILLPRON 1760.

www: Lupa 1684; HD 066947; EDCS-14400591; TM 403914.

# **62. ASH CHEST FRAGMENT** PL. 21

Prov.: Ptuj, church of St George, renovation in 1968.

Loc.: Ptuj, PMPO, Inv. No. RL 928.

Material: Eastern Alpine marble.

Condition: Left upper part of the front side

with missing left corner.

Size:  $54 \times 26 \times 12$  cm; side th. 13 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame. The lateral panels have a simple frame and are left rough.

Inscription: Sept[imi?---] / VET[--] / [--]E[---] Lit.: Šubic 1977, 92, Pl. III.3; Djurić 2001a, 123, No. 42; Ragolič 2023, 100–101, No. 60.

# **63. ASH CHEST FRAGMENT** PL. 22

Prov.: Ptuj, Vičava, Lot No. 336/9, Krčevina cadastral municipality, 1965.

Loc.: Ptuj, PMPO, Inv. No. RL 836.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 69; H. W. Müller).

Condition: Fragment of the front side with an inscription panel missing its right and upper edges, broken in two fragments at the bottom. Surface fairly weathered.

Size:  $54 \times 47 \times 35$  cm; bottom th. 28 cm, side th. 13 cm.

Structure: Chest with a tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame on all four sides.

Inscription: [---]  $\triangle OI$  δ΄ ή δη γείνατο A [---] / πάτρης ἐκ γαίης Bειθυνίδος  $\hat{o}$ ς  $\triangle$ ιον[ $\dot{v}$ ]/σου / κλήματι τερπόμενος ήδος ἔχει στρατε[ $\iota$  ---] / ἵππφ  $\triangle$ AINEAΛΗ με τετιμένον ἐκ / βασιλήων / ξυνη μοῖρα βίου καὶ ψανάτου δάμ[ασεν] / Οὔνομα  $\triangle$ ΕΙΣΙΜΟΙ  $\triangle$ ημήτριος / οὖδε με τύμβφ / ἄμνηστον στοργη θηκεν ἐμῶν [γο]/[ $\nu$ ]έων

Lit.: Šubic 1965, 203; Jordan – Šašel Kos – Wallace

1985, 85; Kovács 2007, 27, No. 62; Ragolič 2023, 127–128, No. 87.

www: Lupa 9447; HD035596; EDCS-39500040; TM 196276; PH295871.

### **64. ASH CHEST FRAGMENT** PL. 22

Prov.: Ptuj, 1908, west tower of the castle.

Loc.: Ptuj, PMPO, old Inv. No. 25.

Material: Eastern Alpine marble.

Condition: Fragment of the front side with the left upper corner of the inscription panel.

Size:  $41 \times 15 \times 17$  cm; side th. 14 cm.

Structure: Chest with a presumably tripartite front with a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame.

Inscription: Severus VI/---

Lit.: Hoffiller – Saria 1938, 182, No. 404; Ragolič 2023, 122, No. 81.

www: EDCS-11301070; HD 069068.

### **65. ASH CHEST FRAGMENT** PL. 22

Prov.: Ptuj, Panorama, excavation by Abramić in 1911.

Loc.: Ptuj, PMPO, Inv. No. RL 487.

Material: Eastern Alpine marble.

Condition: Left upper corner of the front side. Weathered surface.

Size:  $28 \times 18 \times 8$  cm; side th. 8 cm.

Structure: Chest with a tripartite front composed of a central inscription and lateral decoration panels. The lateral front panels have a simple frame, formed as a Norico-Pannonian volute in the upper part.

Iconography: The left front panel holds the depiction of a young man with a *Helmfrisur* that falls onto the neck, with details unclear. To his left is presumably the tip of a thyrsus with a bunch of flowers. It is most likely a personification of the season (*Tempus Anni*) – Spring.

Lit.: Abramić 1914, 105, Fig. 79; Ragolič 2020, 118, No. 39.

# **66. ASH CHEST FRAGMENT** PL. 23

Prov.: Kebelj, church of St Margaret of Antioch, renovation in 2003.

Loc.: Kebelj, church of St Margaret of Antioch, southwest corner.

Material: Eastern Alpine marble.

Condition: Right bottom part of the chest with visible right short side damaged at its front and bottom edges. The drainage hole made in the upper right part shows the chest had previously been used as a trough.

Size:  $75 \times 26 \times 30$  cm.

Structure: Chest with the right short side bearing the decoration panel in a simple frame, wider in its lower part.

Iconography: The right short side shows a female figure reclining on her side and supporting her upper body on her left elbow, propped against a rock. She is lying on bed of seaweed. She is wearing a cloak that covers her left shoulder, envelops her left arm and continues down her body so as to cover the legs with the exception of the right foot. Her fingers hold the drapery, with the index finger and thumb extended. The left third of the relief shows a pair of bare male legs striding toward the right, as well as a slanted ship gangway behind his left leg. The depiction can be identified as the motif of Theseus abandoning the sleeping Ariadne on the island of Naxos (Dia).

Dating: 3<sup>rd</sup> century.

Lit.: Gulič 2006, 126; Djurić 2025.

# **67. ASH CHEST FRAGMENT** PL. 23

Prov.: Kebelj, church of St Margaret of Antioch.

Loc.: Kebelj, church of St Margaret of Antioch, northwest corner of the bell tower.

Material: Eastern Alpine marble.

Condition: Rear lower part of the left short side broken off at the level of the bottom. Substantially damaged relief.

Size:  $50 \times 16 \times 63$  cm.

Structure: Chest with the left short side bearing the decoration panel in a simple frame.

Iconography: The left short side shows a feline on the right side, facing right, with prominent teats on the belly. In the centre is a round object with a feature to the left that can together be identified as a two-wheel chariot. It is most likely the depiction of the motif of the Triumph of Dionysus upon his return from India, where Dionysus and Ariadne stand on a chariot drawn by panthers.

Dating: 3<sup>rd</sup> century.

Lit.: Djurić 2025.

# **68. ASH CHEST FRAGMENT** PL. 23

Prov.: Orešje, Lot No. 248/24, Krčevina cadastral municipality, ploughing in 1984.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Left upper corner of the left short side.

Size:  $50 \times 31 \times 10.5$  cm; side th. 12 cm.

Structure: Chest with the left short side bearing a decoration panel in a simple frame that has a rectangular widening in the centre of the upper edge, intended for a clamp hole.

Iconography: Vine leaf and tendril, probably forming part of the motif of a kantharos from which two crossed vines grow.

Lit.: Tušek 1986, 360, Pl. 16.3; Ragolič 2023, 170, No. 168.

# **69. ASH CHEST FRAGMENT** PL. 24

Prov.: Ptuj.

Loc.: Ptuj, City Tower, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Left central part of a short side. Heavily weathered.

Size:  $39 \times 16$  cm.

Structure: Chest with the short side bearing a

decoration panel in a simple frame.

Iconography: Three downturned vine leaves and one grape bunch.

Lit.: Unpublished.

# **70. ASH CHEST FRAGMENT** PL. 24

Prov.: Ptuj.

Loc.: Ptuj, Prešernova 16, east wall of the entrance passage.

Material: Eastern Alpine marble.

Condition: Left lower part of a short side. Surface damaged in parts.

Size:  $39.5 \times 26.4$  cm.

Structure: Chest with the short side bearing a decoration panel in a simple frame.

Iconography: sitting panther, probably forming part of a heraldic composition of two panthers flanking a central vessel (kantharos?) from which two vines grow.

Lit.: Unpublished. www: Lupa 33313.

### 71. ASH CHEST FRAGMENT PL. 24

Prov.: Ptuj.

Loc.: Ptuj, PMPO, old Inv. No. 64.

Material: Eastern Alpine marble.

Condition: Left upper corner of the rear side.

Size:  $72 \times ? \times 43$  cm; side th. 13 cm.

Structure: Rectangular chest.

Lit.: Unpublished.

#### **72. ASH CHEST** PL. 24

Prov.: Veliko Tinje, church of Sts Peter and Paul, south wall.

Loc.: Veliko Tinje, church of Sts Peter and Paul, south wall.

Material: Eastern Alpine marble.

Condition: The visible short side is damaged on the corners with partially visible left front panel. The short side is finely dressed without a defined decoration panel.

Size:  $25 \times 80$  cm.

Structure: Chest with a presumably tripartite

front

Lit.: Gulič 2007, 58–59; Ragolič 2023, 212, No. 245.

### 73. ASH CHEST

PL. 25

Prov.: Šmartno na Pohorju, at Lober farmstead prior to 1829, then used as a trough by blacksmith Tomaž Ačko in Ogljenšak, until 1885 in the Frajštajn (Freistein) manor near Spodnja Polskava.

Loc.: Graz, Universalmuseum Joanneum, Inv. No. 95.

Material: Eastern Alpine marble, Pohorje quarry (Sample LMJ 95, H. W. Müller).

Condition: Chest with the bedding surface irregularly removed. Lower part of the front abraded and left lower corner missing.

Size:  $115 \times 43 \times 72$  cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a straight moulded frame. The lateral panels have a defined frame and are left rough. The short sides are finely dressed.

Inscription: --] suum / miseranda dolorem num/qua(m) feci dolum neque duos / par tibi ama(n)tes (h) oc mi'h'i indign(a)e / positum [i]n pectore vo'u'lnus / dulcem superstitui natum / miseranda genetrix tertio [a]n/no misera florentem condere sax[s]o

Lit.: Knabl 1856, 525–527; Pichler 1871, 118–119; JJ 74, 12; Diez 1948, 160, No. 19; Pahič 1977a, 58; Modrijan – Weber 1979–81, 74, No. 95; Grassl 1976; Djurić, 2001a, 122, No. 19; Djurić – Hebert *et al.* 2004, 384, 408; Ragolič 2023, 222–224, No. 258; CIL III 5295 + 11709; ILLPRON 1889; AE 1984, 715.

www: Lupa 1683; HD001842; EDCS-14500606; TM 214577.

# 74. ASH CHEST

PL. 25

Prov.: Studenice, church of the Three Kings, corner of the church extension, prior to 1826.

Loc.: Studenice, church of the Three Kings, corner of the church extension.

Material: Eastern Alpine marble.

Condition: Complete chest with three holes made in both arches of the Norico-Pannonian volutes and in the lower left part of the inscription panel.

Size:  $115.5 \times 59 \times 89.5$  cm.

Structure: Chest with a tripartite front composed of a recessed central inscription and lateral decoration panels. The inscription panel has a straight moulded frame on all four sides. The lateral panels have a fillet moulded frame, with the upper part formed as a Norico-Pannonian volute, and are left rough. The visible short side is finely dressed.

Inscription: D(is) M(anibus) C(aius) Iul(ius) / Romanus et / Verina con(iux) v(ivi) / f(ecerunt) s(ibi) et Romulae fil(iae) / ((obitae)) an(norum) XXX et fil(iis) Romulo / et Suriano

Lit.: Steinbüchel 1829, 64; Muchar 1844, 435; Knabl 1855, 159–163; Pahič 1977a, 58; Pahič 1983, 247–248, Fig. 70; Djurić 2001 122, No. 35; Ragolič 2023, 249–250, No. 302; CIL III 05299; ILLPRON 1922.

www: Lupa 4155; EDCS-14500610; HD066806; TM 411911.

### 75. ASH CHEST

PL. 25

Prov.: Ptuj, Volkmerjeva cesta, north of the church of St Oswald, 1905, southern cemetery of Poetovio.

Loc.: Ptuj, PMPO, Inv. No. RL 36.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 11; H. W. Müller).


Condition: Chest with missing upper part slightly above the bottom and obliquely broken across the middle. Restored. Size:  $80 \times 40 \times 52$  cm; bottom th. 32 cm; side th. 11–15 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a fillet moulded frame. The lateral panels have a defined frame and are left rough. The underside has a slightly sunken centre.

Inscription: ---] / c(oniugi) k(arissimo) mil(iti) l(egionis) XIIII / g(eminae) q(ui) v(ixit) ann(os) LXV
et / Munat(io) Valentino / f(ilio) k(arissimo) q(ui)
v(ixit) ann(os) XVIII

Lit.: Skrabar 1905, 302; Abramić 1925, 57 No. 39; Klemenc – Saria 1936, 43; Hoffiller – Saria 1938, 171, No. 378; Diez 1948, 155, No. 3; Jevremov 1988,125–126, No. 152; Djurić 2001a, 122, No. 3; Djurić – Hebert *et al.* 2004, 400 (PET 11); Horvat – Dolenc Vičič 2010, 108; Ragolič 2023, 60–61, No. 22.

www: Lupa 3754; EDCS-11301054; HD068971; TM 407230.



# 76. ASH CHEST FRAGMENT

PL. 26

Prov.: Ptuj.

Loc.: Ptuj, west tower of the castle.

Material: Eastern Alpine marble.

Condition: Bottom part of the chest. Heavily weathered.

Size:  $96 \times 34$  cm; bottom th. 32 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a moulded frame. The lateral panels have a simple frame and are left rough.

Inscription: ---- / /--- / +++++(?) / +++/--- /el l

/ [---]ae sv / [---]mess

Lit.: Karl 2013, 245; Djurić – Ragolič 2022.

# 77. ASH CHEST FRAGMENT PL. 26

Prov.: Ptuj, castle.

Loc.: Ptuj, City Tower, PMPO, Inv. No. RL 780.

Material: Eastern Alpine marble.

Condition: Central part of the front side with the inscription panel and part of the right decoration panel.

Size:  $54 \times 26 \times 12$  cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a moulded frame. The lateral panels have a simple frame and are left rough.

Inscription: --] / III Salvia Qu[in]/tian(a)(?) coniugi / karissimo v(iva) f(ecit) / et sibi et Tit/[---

Lit.: Pococke – Milles 1752, 109, No. 4; Steinbüchel 1829, 35; Muchar 1844, 413; Djurić 2001a, 122, No. 31; CIL III 4079; Ragolič 2023, 98–99, No. 57.

www: Lupa 6096; EDCS-28800806; HD074423; TM 407676.

# **78. ASH CHEST FRAGMENT** PL. 26

Prov.: Črešnjevec, church of St Michael, north wall.

Loc.: Črešnjevec, church of St Michael, north wall.

Material: Eastern Alpine marble.

Condition: Central part of the front side with part of the central and left panels. Surface in the left third is completely removed and coarsely levelled, elsewhere the surface is picked for better mortar adhesion.

Size:  $73 \times 15$  cm.

Structure: Chest with a tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a moulded frame.

Inscription: ---- / /---/+/---/ /((obitus?))

an(norum) XX et Pegissa (?) [---] / Brutti, ((obitus)) an(norum) XX. F(ilia?) GEN+[---] / [n]epoti [---]

Lit.: Predan 2001, 132, No. 92; Ragolič 2023, 240, No. 282.

www: Lupa 31461.

# **79. ASH CHEST FRAGMENT** PL. 26

Prov.: Ptuj, Miklošičeva 12, 1936.

Loc.: Ptuj, PMPO, Inv. No. RL 68.

Material: Eastern Alpine marble.

Condition: Fragment of the front side with part of the central and left panels.

Size:  $46 \times 25 \times 14$  cm; side th. 13 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription and lateral decoration panels have a moulded frame.

Inscription: --]omu [--- / actuari[o --- / ve Magnae c[--- / XXXV et mens[es ---

Lit.: Klemenc – Saria 1936, 48–49; Hoffiller – Saria 1938, 177, No. 390; Diez 1948, 156, No. 16; Djurić 2001a, 122, No. 13; CIL 3, 14065; Ragolič 2023, 80, No. 38.

# **80. ASH CHEST WITH LID** PL. 26

Prov.: Ptuj, Gregorčičev drevored, Lot Nos. 489/5–8, 493/4–5, Ptuj cadastral municipality, 1956, southern cemetery of Poetovio.

Loc.: Ptuj, PMPO, Inv. No. RL 711.

Material: Eastern Alpine marble, Pohorje quarry (Sample PET 13; H. W. Müller).

Condition: Complete chest broken into three fragments, with a broken and partially surviving lid in the shape of an unworked slab. Restored.

Size: chest  $102 \times 56 \times 70$  cm; bottom th. 26 cm; side th. 15 cm; lid th. 5 cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a moulded frame. The lateral panels have a defined frame, with the upper part formed as a Norico-Pannonian volute, and are left rough. The bedding surface has a raised semicircular edge along the interior to keep the lid in place.

Lit.: Mikl 1960–61, 157–158; Jevremov 1988, 49, No. 19; Djurić 2001a, 122, No. 28; Djurić – Hebert *et al.* 2004, 400 (PET 13); Horvat – Dolenc Vičič 2010, 149; Ragolič 2023, 155–156, No. 141.

www: Lupa 4209.

# **81. ASH CHEST WITH LID** PL. 27

Prov.: Ptuj, Ptuj-Hospital, 1991, eastern cemetery of Poetovio.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Complete and very well-preserved chest and lid, with only slight damage to the front right corner of the lid. It was found closed, containing the skeleton of a child buried with a gold phallus on gold wire.

Size: chest  $84 \times 50 \times 64$  cm; bottom th. 39 cm, side th. 12–13 cm; lid  $100 \times 33 \times 75$  cm.

Structure: Chest with unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has an unfinished moulded frame on three sides, while the lower side only has a line; the surface is coarsely finished. The lateral panels have a defined frame, with the upper part formed as a Norico-Pannonian volute, and are coarsely finished. The short sides are coarsely dressed and have a clamp hole in the centre of the upper edge.

Gabled lid with an overhang, flat ridge and without acroteria. All surfaces are coarsely finished. It is fastened to the chest with an iron clamp filled with lead on both short sides. Part-finished product in the quarry phase of production.

Lit.: Tušek 1992a, 284; Djurić 2001a, 122, No. 33.

### 82. ASH CHEST

PL. 28

Prov.: Spodnja Hajdina near Ptuj, while deepening the road between Hajdina and Pragersko, 1972, western cemetery of Poetovio.

Loc.: Ptuj, PMPO, Inv. No. 944.

Material: Eastern Alpine marble.

Condition: Chest broken vertically in the left third and missing the left rear corner.

Size:  $88 \times 57 \times 61$  cm; bottom th. 35 cm, side th. 12–13 cm.

Structure: Chest with unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a fillet moulded frame on three sides and a simple frame in the lower part. The lateral panels have a defined frame, with a pedimental frame on the upper side, and are left rough.

Lit.: Šubic 1974, 153.

# 83. ASH CHEST FRAGMENT PL. 28

Prov.: Ptuj, Zgornji Breg, Leskoškova njiva, 28 September 1908.

Loc.: Ptuj, PMPO, Inv. No. RL 562.

Material: Eastern Alpine marble.

Condition: Three fragments of the upper front and short sides (two of them survive and are now in the PMPO), broken off above the bottom.

Size:  $85 \times 21$  (reconstr. 45)  $\times$  30 cm; side th. 8-10 cm.




Figure 55. Drawing of the ash chest (Historical Archives Ptuj, document No. 7272)

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a moulded frame. The lateral panels have a defined frame, with the upper part formed as a Norico-Pannonian volute, and are left rough.

Lit.: Diez 1948, 156, No. 8; Djurić 2001a, 122, No. 8; Ragolič 2023, 163, No. 155.

# **84. ASH CHEST FRAGMENT** PL. 28

Prov.: Kebelj, church of St Margaret of Antioch, renovation in 2003.

Loc.: Kebelj, church of St Margaret of Antioch.

Material: Eastern Alpine marble.

Condition: Bottom part with missing left corner.

Size:  $80 \times 15$  cm.

Structure: Chest with an unrecessed front composed of a central inscription and lateral decoration panels. The inscription panel has a moulded frame on either side and a line in the lower part. The lateral panels have a defined frame and are left rough.

Lit.: Gulič 2006, 126.

# **85. ASH CHEST FRAGMENT** PL. 28

Prov.: Ptuj.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Left central part of the front side.

Size:  $40 \times 11 \times 14$  cm; side th. 13 cm.

Structure: Chest with a tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a moulded frame. The lateral front panels have a simple frame.

Lit.: Unpublished.

# **86. ASH CHEST FRAGMENT** PL. 28

Prov.: Ptuj.

Loc.: Ptuj, PMPO, without inv. no. Material: Eastern Alpine marble.

Condition: Part of the lateral front panel.

Size:  $17 \times 17 \times 44$  cm; side th. 16 cm.

Structure: Chest with a presumably tripartite front composed of a central inscription and lateral decoration panels. The lateral panels have a moulded frame.

Lit.: Unpublished.

# **87. ASH CHEST FRAGMENT** PL. 29

Prov.: Kebelj, church of St Margaret of Antioch, renovation in 2003.

Loc.: Kebelj, church of St Margaret of Antioch.

Material: Eastern Alpine marble.

Condition: Lower left corner of the front side. Damaged left edge, surface weathered.

Size:  $60 \times 30$  cm.

Structure: Chest with the front side bearing a sunken inscription panel in a moulded frame at the centre, flanked by a wide band on either side.

Inscription: -- / *Iulius* [---] / *dec*(..) *Ma*[---] (reading A. Ragolič)

Lit.: Gulič 2006, 126.

# **88. ASH CHEST FRAGMENT** PL. 29

Prov.: Črešnjevec, church of St Michael, southwest corner of the foundations, 1964.

Loc.: Črešnjevec, church of St Michael, southwest corner of the foundations.

Material: Eastern Alpine marble.

Condition: Left lower part of the front side with weathered surface.

Size:  $109 \times 33$  cm.

Structure: Chest with an unrecessed tripartite front composed of a central inscription and lateral decoration panels. The inscription panel has a moulded frame. The lateral front panels have a simple frame and are left rough.

Lit.: Pahič 1962-64; 1964; Predan 2001, 175, Pl. 26.

# **89. ASH CHEST FRAGMENT** PL. 29

Prov.: Črešnjevec, church of St Michael, west precinct wall, 1857.

Loc.: Črešnjevec, in front of the church of St Michael.

Material: Eastern Alpine marble.

Condition: Heavily damaged chest in two pieces. The front side is almost complete, with only the upper left corner missing, all other sides are almost entirely missing and the bottom is damaged on the underside and missing the right rear corner.

Size:  $103 \times 56 \times 70$  cm; bottom th. 38 cm, side th. 13–15 cm.

Structure: Chest with the front side bearing a sunken inscription panel in a moulded frame at the centre, flanked by a wide coarsely dressed band on either side. All other sides are also coarsely dressed.

Inscription: [ ---]ia Verc/[--- ] et Deusa / liberta arc(am) / fecit patro/n(a)e su(a)e

Lit.: Knabl 1859, 87; Abramić 1933, 133, Fig. 43; Hoffiller – Saria 1938, 39, No. 85; Diez 1948, 158, No. 18; Pahič 1977a, 46; Pahič 1990, 172–173, Fig. 42; Djurić 2001a, 122, No. 18; Ragolič 2023, 237–238, No. 279; CIL III ad 5303; ILLPRON 1763.

www: Lupa 1685; HD066953; EDCS-14500614; TM 402628.

### **90. ASH CHEST** PL. 30

Prov.: Ptuj, used as a trough in the house at No. 100 (?) until 1822, in 1823 built into City Tower.

Loc.: Ptuj, City Tower, PMPO, Inv. No. RL 792. Material: Eastern Alpine marble, Pohorje quar-

ry (Sample PET 62; H. W. Müller).

Condition: Chest with missing upper and lower

right corners, as well as damaged lower left corner of the front. Surface weathered.

Size:  $97 \times 37$  cm.

Structure: Chest with the front side bearing a sunken inscription panel in a moulded frame at the centre, flanked by a wide band on either side.

Inscription: Calligeniae filiae dulcis/simae an(norum) III m(ensium) VI d(ierum) XV Aur(elius) / Callimorphus et Ael(ia) Sabina / parentes infelicis-simi

Lit.: Steinbüchel 1829, 61; Diez 1948, 153; Ragolič 2023, 85–86, No. 44; CIL III 4073.

www: Lupa 4259; EDCS-28800801; HD074443; TM 407672.



Figure 56. Drawing of the ash chest (Vienna, KHM, Antikensammlung, Archive No. 23 ex 1830, Somenzari, Pl. VII)

### **91. ASH CHEST FRAGMENT** PL. 30

Prov.: Starše.

Loc.: Graz, Universalmuseum Joanneum, without inv. no.

Material: Eastern Alpine marble.

Condition: Bottom fragment with part of the front side.

Size:  $73 \times 26 \times 70$  cm.

Structure: Chest with the front side bearing a sunken inscription panel, in a frame that is moulded in the lower part, that covers the entire height and width.

Inscription: --] / [--] iusseru[nt] PAT[----]V[--] non for[-----] / nunc matris pietaten 'm' (h)abet per

dom(i)nica r[ura] / [e]t licuit matri corpus sepere dolendu[m] / qu(a)e nunc (h)abet titul(um) non terr(a) e inimic(a)e ia[centem] / se'd' potius donis sollemnibus esse colend[um] / Surilla ego so(m)(!) qu(a)e per'i'mor filia C(h)loe[s---]

Lit.: Pichler 1871, 122–128; Grassl 1976, 49–55; Pahič 1977a, 57; Ragolič 2023, 284–285, No. 362; CIL 03, 05695 = 11827; Weber, Inschr. No. 396; CLEPann 21.

www: Lupa 1693; EDCS-14501073; HD064098; TM 188708.

# 92. ASH CHEST FRAGMENT PL. 30

Prov.: Veliko Tinje, church of Sts Peter and Paul, north wall.

Loc.: Veliko Tinje, church of Sts Peter and Paul, north wall.

Material: Eastern Alpine marble.

Condition: Bottom part with damaged lower front corners.

Size:  $71 \times 22$  cm.

Structure: Chest with the front side bearing a sunken inscription panel, in a simple frame, that covers the entire height and width.

Inscription: ---] / et Primus filius / vivi fecer(unt) sibi / Iuli(o) Iust(o) an(norum) XV

Lit.: Orožen 1889, 220; Klemenc – Saria 1939, 64; Diez 1948 cit. 32; Pahič 1968–69, 171 with fig.; Pahič 1977b, 59, Fig. 25; Ragolič 2023, 208–209, No. 240; CIL III 11716; ILLPRON 1926.

www: Lupa 13363; EDCS-14600198; HD066802.

# 93. ASH CHEST FRAGMENT (?) PL. 30

Prov.: Smartno na Pohorju, church of St Martin, bell tower.

Loc.: Šmartno na Pohorju, church of St Martin, bell tower.

Material: Eastern Alpine marble, Pohorje quarry (Sample SMA 2, Harald W. Müller).

Condition: Complete chest with damaged left lower corner of the front.

Size:  $118 \times 55 \times 70$  cm.

Structure: Chest with the front side bearing a sunken inscription panel, in a frame moulded on all four sides, that covers the entire height and width.

Iconography: an *ascia* is depicted on the right short side.

Lit.: Pahič 1977e; Pahič 1984a; Djurić – Hebert *et al.* 2004, 403 (SMA 2); Ragolič 2023, 224, No. 259.

www: Lupa 25471.

# 94. LID OF AN ASH CHEST PL. 31

Prov.: Ptui.

Loc.: Ptuj, PMPO, Inv. No. RL 64.

Material: Eastern Alpine marble.

Condition: Complete lid with a horizontal break. Both left acroteria are damaged, as is the ridge in the rear part. Part of the front edge below the ridge is broken off. Fairly damaged and weathered surface.

Size:  $109 \times 35 \times 78$  cm.

Structure: Gabled lid with a raised flat ridge and four corner acroteria. The lid slopes are plain. The tympanum panel has relief depictions in a simple frame.

Inscription: D(is) M(anibus)

Iconography: The tympanum holds *en face* and half-length portraits of four family members consisting of the father and mother in the centre flanked on either side by an underage son. The father and both sons are dressed in a *sagum* fastened at the right shoulder with an unidentifiable brooch. The mother's clothing is damaged beyond identification. The father's portrait imitates that of Gordian III. The mother's face is elongated, with a melon coiffure with long hair that leave the ears exposed and turn upward at the nape. The portraits of the sons are severely damaged.

Dating: Mid-3<sup>rd</sup> century.

Lit.: Abramić 1925, 142, No. 16; Hoffiller – Saria 1938, 189, No. 422; Diez 1948, 158, No. 21; Jevremov 1988, 64, No. 38; Djurić 2001a, 122, No. 21;

Mander 2012, 287, No. 609; Pochmarski 2018, 226, Fig. 5; Ragolič 2023, 130, No. 91.

www: Lupa 3773; EDCS-11301084; HD 069091.

### **95. LID FRAGMENT** PL. 31

Prov.: Ptuj.

Loc.: Ptuj, PMPO, Inv. No. RL 748.

Material: Eastern Alpine marble.

Condition: Front part with missing right third and top of the left acroterium. Surface dam-

aged and weathered.

Size:  $111 \times 40 \times 78$  cm.

Structure: Gabled lid with a raised flat ridge and corner acroteria. The lid slopes are plain. The separate tympanum and acroterium panels have relief depictions in simple frames.

Iconography: The tympanum holds en face and half-length portraits of five family members (the one on the far right is missing) beneath a shell. The three left figures represent three generations of women. The one positioned in the centre is a girl dressed in a tunica manicata and an asymmetrical palla. Her arms are bent and placed on her chest. In her right hand, she holds a bird, while her left hand is unclear. Around her neck is a necklace of large round beads. Her face is unclear. She has a melon coiffure above the ears and nape. The woman further left is probably the mother, in the same dress. Her right arm is bent and placed on her chest, while her left hand likely rests on her daughter's right shoulder. Her face is unclear and her long hair is gathered into a net(?) behind her exposed ears, turned upward at the nape and secured at the crown (Scheitelfrizur). The woman on the far left is elderly and dressed in a tunica manicata girt below the breasts and a symmetrically worn cloak. Her right arm is bent and placed on the chest, holding a flower. Her face is unclear, with a rather broad outline and large almond-shaped eyes. Her hair is raised to mid-ear level and covered with a turban-like headdress (Type H 6 after Rothe). To the right of the central figure is a man in a tunica manicata and *sagum* fastened at the right shoulder with a disc brooch. His face is unclear, his hair short. The left front acroterium holds the depiction of a basket of flowers as a representation of a season – Spring.

Dating: Mid-3<sup>rd</sup> century.

Lit.: Diez 1948, 161, No. 22; Jevremov 1988, 70, No. 47; Djurić 2001a, 122, No. 22; Pochmarski 2015, 217; Ragolič 2023, 174, No. 177.

www: Lupa 4255.

### **96. LID OF AN ASH CHEST** PL. 32

Prov.: Ptuj.

Loc.: Ptuj, PMPO, Inv. No. RL 123.

Material: Eastern Alpine marble.

Condition: Front part of the lid with horizontal breaks. Surface damaged and weathered.

Size:  $125 \times 40 \times 35$  cm.

Structure: Gabled lid with a raised flat ridge and corner acroteria. The lid slopes are plain. The separate tympanum and acroterium panels have relief depictions in simple frames.

Iconography: The tympanum holds en face and half-length portraits of three family members beneath a shell and a curtain (parapetasma), consisting of a mother, father and son. Positioned in the centre is a severely damaged image of a young man. Standing to his left is the mother, dressed in a girt tunic with wide long sleeves (tunica manicata) and a symmetrically worn cloak. Her right arm is bent and placed on her chest. She wears a thin necklace. Her face is unclear and her long hair gathered into a net (?) behind her exposed ears, turned upward at the nape and secured at the crown (Scheitelfrizur). On the right is the father, dressed in a tunic and sagum fastened at the right shoulder. His left arm is bent and placed on his chest, holding a scroll.

The acroteria hold half-length images of nude young men with curly hair and a topknot, positioned on the corner. They are holding a thyrsus in the inner hand, tipped with bunches of flowers (left) and ears of grain (right). They are personifications of the seasons - Spring and Summer.

Dating: Mid-3<sup>rd</sup> century.

Lit.: Diez 1948, 162, No. 23; Jevremov 1988, 67, No. 42; Djurić 2001a, 122, No. 22; Mander 2012, 288, No. 611; Pochmarski 2015, 217; Ragolič 2023, 171-172, No. 172.

www: Lupa 4254.

### 97. LID FRAGMENT

PL. 32

Prov.: Ptuj, hospital field, 1930.

Loc.: Ptuj, PMPO, Inv. No. RL 490.

Material: Eastern Alpine marble.

Condition: Right front part with a damaged

corner. Surface heavily weathered.

Size:  $40 \times 28 \times 28$  cm.

Structure: Gabled lid with corner acroteria. The lid slope is plain. The separate tympanum and acroterium panels have relief depictions in simple frames.

Iconography: The tympanum holds en face and half-length portraits of the deceased, of which only the right figure survives, of a boy dressed in a sagum. His left arm is bent and placed on his chest, holding an unidentifiable object. His face is damaged, his hair short. The acroterium panel shows a downward- and inward-facing dolphin with a strong snout, almond-shaped eye and small tail fin.

Lit.: Diez 1948, 162, No. 24; Djurić 2001a, 122, No. 24; Ragolič 2023, 172, No. 173.

#### 98. LID OF AN ASH CHEST PL. 32

Prov.: Pernica, church of St Margaret, prior to 1844.

Loc.: Pernica, church of St Margaret, west wall. Material: Eastern Alpine marble, Pohorje quarry (Sample MAR 2; H. W. Müller).

Condition: Front side with missing top and corner of the right acroterium. Fairly weathered surface. The figures crowning the lid are completely built into the wall.

Size:  $167 \times 50$  cm.

Structure: Gabled lid with corner acroteria. The separate tympanum and acroterium panels in front and sides have relief depictions in simple frames. The frames between the front acroteria and the tympanum bear a pilaster with a spirally fluted shaft and capital. Crowning the lid is a pair of figures in the round.

Iconography: The tympanum holds en face and half-length portraits of five family members beneath a shell, consisting of a mother in the centre, father to the right of her, two older sons to the left and the youngest daughter between the mother and the father. The mother is dressed in a tunica manicata and an asymmetrical palla. Her right arm is bent and placed on her daughter's upper arm, with extended thumb, index and ring fingers. Her face is heavily damaged. She has a melon coiffure with exposed ears and neck. The father is dressed in a tunic and sagum, fastened at the right shoulder with a brooch. His left arm is bent and extended outward, holding a scroll, to which he is pointing with the fingers of his right hand, placed on his chest. His face is also heavily damaged, but shows a medium-length beard and short, indistinct hair. Depicted on the far left is the eldest son, dressed in a tunica manicata and sagum, fastened at the right shoulder with a brooch. His right arm is bent and extended leftward with an outstretched index finger. His face is oval, possibly with a short beard, his hair is short. Standing between him and the mother is his younger brother, also wearing a tunica manicata and sagum, fastened with a disc brooch on the right shoulder. His right arm is bent and placed on his chest, with the index and middle fingers extended. The front of his head is broken off. The daughter, placed between the parents, is dressed in a tunic and asymmetrical palla. She wears a necklace with large round beads. Her face and hairstyle are unclear.

The left acroterium holds an en face depiction of a female servant (camilla) wearing a long, short-sleeved tunic reaching down to her feet, possibly with a *stola* over it. Her arms are slightly bent and extended downward. She is holding a jug in her right hand and a vessel with a long handle in her left hand. A mantele hangs over her left shoulder. The right acroterium bears an en face depiction of a male servant (camillus) in an unbelted tunic, with his head turned to the right. His right arm is slightly bent and extended toward the family, holding a cup. His left arm is extended beside his body, probably holding a bottle. In a drawing published by Muchar, a winged Eros with a bow is depicted on the left side of the left acroterium, and a stylized half-palmette on the right side of the right acroterium, while an outward-facing pair of heraldic lions carved in the round crown the front side of the lid.

Dating: First half of the 3<sup>rd</sup> century.

Lit.: Muchar 1844, 399; Diez 1948, 162, No. 25; Garbsch 1965, 7, No. 2; Djurić 2001a, 122, No. 25; Mander 2012, 276, No. 554; Pochmarski 2015, 217, Fig. 6; Ragolič 2023, 278, No. 354.

www: Lupa 4143.




Figure 57. Drawing of the ash chest lid (from Muchar 1844)

# **99. LID OF AN ASH CHEST** PL. 33

Prov.: Slivnica pri Mariboru, Marian church, north wall.

Loc.: Slivnica pri Mariboru, Marian church, north wall.

Material: Eastern Alpine marble.

Condition: Front side of a lid with missing left acroterium, most of the right acroterium and top. Portraits are severely damaged, surface heavily weathered.

Size:  $144 \times 43$  cm.

Structure: Gabled lid with a flat ridge and corner acroteria. The tympanum panel has relief depictions in a simple frame.

Iconography: The tympanum holds en face and half-length portraits of six family members symmetrically positioned beneath a shell. At the centre is a pair, a man and a woman, who are likely the eldest of the group. Two younger persons are shown at either end of the group, while the youngest persons are depicted between these and the central pair, one on either side. The woman in the central pair is heavily damaged. She wears a cloak and a thin necklace with round beads, her hair is gathered above her ears, possibly held by a scarf or head covering. Her husband, to the left of her, is clad in a sagum and has his left hand on the chest holding a scroll. Of the second and younger pair, the woman at the far left is dressed in a tunic and a symmetrically worn cloak. Her right arm is bent and placed on her chest, holding a round object, likely a pomegranate. She also wears a necklace with round beads. Her face is destroyed and her long hair is gathered in a net (?), turned upward deep at the nape and secured at the crown (Scheitelfrizur), similar to the hairstyles spanning from Iulia Mamaea to Herennia Etruscilla. Shown on the far right is her husband, wearing a sagum fastened at the right shoulder. His left hand rests on his chest. His face and hairstyle are destroyed. The two youngest men, in the foreground, are also dressed in a sagum. The one on the right holds a scroll against his chest with his left hand, pointing at it with the fingers of his right hand. The young man on the left has his right hand placed in the same position, while his left hand is damaged and unclear.

The panel of the heavily damaged right acroterium shows a half-length figure, possibly the personification of a season.

Dating: Second quarter or mid-3<sup>rd</sup> century.

Lit.: Muchar 1844, 424; Klemenc – Saria 1939, 57; Pahič 1977a, 54, Fig. 16; Djurić 2001a, 123, No. 57; Mander 2013, 275, No. 553; Pochmarski 2014, 359, Fig. 6; Ragolič 2023, 266, No. 331.

www: Lupa 4145.

#### 100. LID OF AN ASH CHEST PL. 33

Prov.: Ptuj, naselje bratov Reš, Lot No. 523/9, Krčevina cadastral municipality, Pivkova ulica 3, 1967, base of an inhumation grave.

Loc.: Ptuj, PMPO, Inv. No. RL871.

Material: Eastern Alpine marble.

Condition: Complete lid with restored acroterium tops. Relief heavily weathered.

Size:  $134 \times 36 \times 101$  cm.

Structure: Gabled lid with a flat ridge and four corner acroteria. The lid slopes are plain. The separate tympanum and acroterium panels have relief depictions in a simple frame that has concave left and right sides. The acroteria have two-sided decorative panels with a simple frame.

Inscription: D(is) M(anibus)

Iconography: The tympanum holds en face and half-length portraits of three family members consisting of a father, mother and daughter between them. The mother, on the left, is dressed in a tunic and symmetrically worn cloak, open around the neck and chest, where her right hand rests on its thick border. The details of her face and hairstyle are indistinct, though her hairstyle may be a Scheitelfrizur. The man is dressed in a tunica manicata and sagum, fastened on his right shoulder with a disc brooch. Both of his arms are bent and placed on his chest. In his left hand, he holds a scroll, to which he is pointing with the fingers of his right hand. Shown in the centre is a young woman in a tunic and cloak. Her arms are bent and positioned above her waist, holding an unidentifiable object, possibly a bird, in her right hand. She also wears a necklace with round beads. The details of her face and short hairstyle are unclear.

The acroteria hold the half-length images on the corners. Although unclear in details, they are the personification of the seasons.

Lit.: Šubic 1967, 94; Jevremov 1988, 70, No. 48; Djurić 2001a, 122, No. 25; Mander 2012, 287, No. 610; Pochmarski 2015, 217; Ragolič 2023, 170, No. 169.

www: Lupa 9410.

# **101. LID OF AN ASH CHEST** PL. 34

Prov.: Ptuj, Ptuj-Hospital, 1991, eastern cemetery of Poetovio.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Complete lid with missing acroteria and upper edge. Relief weathered.

Size:  $95 \times 40 \times 78$  cm.

Structure: Gabled lid with a flat ridge and four corner acroteria. The lid slopes are plain. The tympanum panel has relief depictions in a simple frame.

Inscription: *D(is) M(anibus)* 

Iconography: The tympanum holds en face and half-length portraits of four family members consisting of a father, mother and two boys. The father, positioned on the right, is dressed in a tunic and sagum fastened on his right shoulder with a disc brooch. His face is broad, his hairstyle is short. Next to him is the mother, wearing a tunic and symmetrically worn cloak with a thickened edge running from her left shoulder across her chest to her right shoulder. She wears a necklace of round beads. Her hair is long, gathered in a net (?) behind her ears, turned upward at the nape and secured at the crown (Scheitelfrizur). The two boys are dressed in a tunic and sagum fastened at the right shoulder with a disc brooch. Their hair is short, the facial features unclear.

Dating: Second quarter or mid-3<sup>rd</sup> century.

Lit.: Unpublished.

# **102. LID OF AN ASH CHEST** PL. 34

Prov.: Ptuj, Ptuj-Hospital, 1991, eastern ceme-

tery of Poetovio.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Complete lid with a weathered sur-

face.

Size:  $104 \times 29 \times 67$  cm.

Structure: Gabled lid with a flat ridge and four corner acroteria. The lid slopes are plain. The separate tympanum and acroterium panels have relief depictions in simple frames.

Inscription: *D(is) M(anibus)* 

Iconography: The tympanum holds an *en face* and half-length portrait of a man. He is dressed in a *tunica manicata* and *sagum* fastened at the right shoulder with a brooch. His arms are bent and raised in front of his chest. In his left hand, he holds a scroll, to which he is pointing with the index and middle fingers of his right hand. He has a short beard, his hair is short and curly.

The left and right acroteria depict situla-like baskets, the left one filled with flowers, the right one with ears of grain; they symbolise the seasons – Spring and Summer.

Dating: Severan.

Lit.: Unpublished.

# 103. LID FRAGMENT PL. 34

Prov.: Črešnjevec, church of St Michael, south wall.

Loc.: Črešnjevec, church of St Michael, south wall.

Material: Eastern Alpine marble.

Condition: Left half of the front side with missing acroterium and upper edge. Relief weathered and whitewashed.

Size:  $35 \times 33$  cm.

Structure: Gabled lid with a flat ridge. The lid slopes are presumably plain.

Iconography: The tympanum holds en face and half-length portraits of at least four, but most likely five family members (three of them survive) beneath a shell, consisting of the mother, underage daughter to the left and grandmother at the far left. Placed centrally is the mother, dressed in a tunic and cloak with a prominent fold running from her right shoulder to the centre of her chest and likely continuing to her left shoulder. She may be wearing a necklace. Her face is damaged, her long hair gathered in a net (?) behind her exposed ears, turned upward at the nape and fastened at the crown (Scheitelfrizur). The grandmother is dressed in a tunic and symmetrically worn cloak. Her right arm is bent and placed on her granddaughter's right arm. She wears a necklace with large round beads. Her face is damaged, her Helmfrisur not clear and possibly covered with a turban-like headdress (Type H 7 after Rothe). The girl between them wears a tunic and cloak. Her arms are bent and positioned slightly above her waist. In her right hand, she holds a bird. She wears a necklace with round beads. Her face and short hairstyle are unclear.

Dating: Second quarter or mid-3<sup>rd</sup> century.

Lit.: Pahič 1977d, 205 with fig.; Djurić 2001a, 123, No. 53.

### **104. LID OF AN ASH CHEST** PL. 34

Prov.: Črešnjevec, church of St Michael, south wall.

Loc.: Črešnjevec, church of St Michael, south wall.

Material: Eastern Alpine marble.

Condition: Front side with missing right end of the tympanum, right acroterium and top part. Relief is heavily damaged and weathered.

Size:  $93 \times 23$  cm.

Structure: Gabled lid with a likely flat ridge and corner acroteria. The tympanum panel has a

simple frame. The acroteria are undecorated and finely dressed.

Inscription: *D(is)* [*M(anibus)*]

Iconography: The tympanum holds en face and half-length portraits of seven family members (six of them survive). Centrally placed is an older woman dressed in a tunic and cloak, wearing a necklace with round beads. Her face is damaged, her hair is gathered under a head covering (?). To the right is a younger woman, probably her daughter, dressed in a tunic and an asymmetrical palla. She also wears a necklace with round beads. Her face, with large almond-shaped eyes, is heavily eroded. Her hair is pulled up and covered with a scarf of Type H 6 after Rothe. Shown at the far right is a man, likely the husband, wearing a sagum (?). His face is damaged, his eyes large, his hair short. To the left of the central figure is a woman dressed in a tunic and palla. Her face and hairstyle are unclear. Further left is a younger man in a tunic and sagum. His face is destroyed, his hair short. At the far left is a boy in a tunic and possibly sagum, his face and hairstyle unclear.

Dating: First half of the 3<sup>rd</sup> century.

Lit.: Pahič 1984, 222, Fig. 29; Djurić 2001a, 123, No. 54; Ragolič 2023, 244, No. 290.

www: Lupa 4692.

## **105. LID FRAGMENT** PL. 34

Prov.: Ptuj (?).

Loc.: Graz, Universalmuseum Joanneum, with-

out inv. no.

Material: Eastern Alpine marble.

Condition: Front side with the right part of the tympanum and most of the right acroterium. Relief is damaged, the part on the far left is broken off.

Size:  $56 \times 24 \times 36$  cm.

Structure: Gabled lid with corner acroteria. The separate tympanum and acroterium panels have simple frames.

Iconography: The tympanum holds *en face* and half-length portraits of family members (only one at the far right survives). The surviving figure shows a man wearing a *sagum* fastened on the right shoulder with a disc brooch. His left arm is bent and placed above his belt, holding a scroll and extending his index finger towards the missing figure of a woman (?) to the left, who partially overlaps him. His face is damaged, beardless, with fairly large and protruding ears, the upper part of his head is broken off.

The right front acroterium shows a severely damaged winged eros in a pronounced stride to the right. His right leg is stretched back, his left leg is bent forward. His (left?) arm is extended horizontally forward, likely holding an object that identifies him as an eros (bow), less likely as a personification of a season (attribute). His right hand is unclear. His head is damaged.

Lit.: Pochmarski 2015, 217; Ragolič 2023, 173, No. 176.

www: Lupa 8488.

#### 106. LID FRAGMENT PL. 35

Prov.: Črešnjevec, church of St Michael, east precinct wall.

Loc.: Črešnjevec, archaeological park in front of the church of St Michael.

Material: Eastern Alpine marble, Pohorje quarry (Sample CSR 4; H. W. Müller).

Condition: Left front quarter with missing ridge and standing surface. Relief is damaged in places, Triton's head is broken off.

Size:  $112 \times 54 \times 50$  cm.

Structure: High gabled lid with corner acroteria and imitation tegulae and imbrices, the ridge was presumably flat. The separate tympanum and acroterium panels have simple frames. The short sides are finely dressed.

Iconography: The tympanum shows a centrally placed Triton with legs terminating in a trilobate fin. His head is shown in profile facing left, blowing into a spindle-shaped shell. To the left is a downward-facing dolphin with the same trilobate tail fin, which presumably had its heraldic pendant to the right of the Triton.

The left acroterium holds a nude winged youth – eros, depicted in *contrapposto* with the weight on his right leg. He holds a torch diagonally across his body, from his left hip over his right shoulder. His left arm is extended downward, while his right arm is bent up.

Lit.: Muchar 1845, 342; Abramić 1933, 132; Modrijan – Weber 1979–81, 105, No. 96; Pahič 1977a, 46; Djurić 2001a, 53, No. 25; Djurić – Hebert *et al.* 2004, 403 (CRS 4); Drack 2008, 103–104; Ragolič 2023, 243, No. 289.

www: Lupa 4696.

# 107. LID FRAGMENT

PL. 36

Prov.: Ptuj, Ptuj-Hospital, 1991, eastern cemetery of Poetovio.

Loc.: Ptuj, PMPO, Inv. No. RL 1011.

Material: Eastern Alpine marble.

Condition: Fragment of the front tympanum.

Size:  $23 \times ? \times 6.5$  cm. Structure: unknown.

Iconography: Part of the chest and right arm of a young woman dressed in a tunic and *palla*, holding a bird in her right hand.

Lit.: Vomer Gojkovič 1993, 461, Pl. 14.6; Vomer Gojkovič 1997.

### **108. LID FRAGMENT** PL. 35

Prov.: Ptuj, Ptuj-Hospital, 1991, eastern cemetery of Poetovio.

Loc.: Ptuj, PMPO, without inv. no.

Material: Eastern Alpine marble.

Condition: Rear (?) corner of a lid.

Size:  $60 \times 21 \times 48$  cm.

Structure: Gabled lid with a flat ridge and four corner acroteria. The underside is sunken with a wide standing surface and a rectangular dowel hole for securing the lid to the chest.

Lit.: Unpublished.

# **109. LID OF AN ASH CHEST** PL. 36

Prov.: Črešnjevec, church of St Michael, south wall.

Loc.: Črešnjevec, church of St Michael, south wall.

Material: Eastern Alpine marble.

Condition: Block with outlined pediment and acroteria.

Size:  $123 \times 45$  cm.

Structure: Basic design of a gabled lid with a flat ridge and corner acroteria, as well as roughly carved separate tympanum and acroterium panels. Part-finished product.

Lit.: Pahič 1984, 222, Fig. 29; Djurić 2001a, 123, No. 55; Ragolič 2023, 243, No. 288.

#### 110. LID OF AN ASH CHEST PL. 36

Prov.: Črešnjevec, church of St Michael, north wall

Loc.: Črešnjevec, church of St Michael, north wall.

Material: Eastern Alpine marble, Pohorje quarry (Sample CRS 3, Harald W. Müller).

Condition: block with outlined pediment and acroteria, missing the upper and left parts.

Size:  $110 \times 18$  cm.

Structure: Basic design of a gabled lid with corner acroteria, as well as roughly carved separate tympanum and acroterium panels. Part-finished product.

Lit.: Pahič 1984; Djurić 2001a, 123, No. 56; Djurić – Hebert *et al.* 2004, 40 (sample CRS 3); Ragolič 2023, 244, No. 291.

### 111. LID OF AN ASH CHEST PL. 36

Prov.: Šmartno na Pohorju, church of St Martin, precinct wall.

Loc.: Smartno na Pohorju, church of St Martin, precinct wall.

Material: Eastern Alpine marble.

Condition: Complete lid with damaged acroteria.

Size:  $100 \times 74 \times 18$  cm.

Structure: Gabled lid with a flat ridge, four corner acroteria and deeply sunken underside.

Lit.: Pahič 1977a, 59, No. 7; Djurić 2001a, 123, No. 58

#### 112. LID FRAGMENT PL. 36

Prov.: Malečnik, 1958.

Loc.: Malečnik, church of St Peter (?), possibly lost.

Material: Eastern Alpine marble.

Condition: Lid with missing rear part and damaged surface and acroteria.

Size:  $87 \times ? \times 86$  cm.

Structure: Gabled lid with a flat ridge and corner acroteria.

Lit.: Pahič 1960–61; Pahič 1977a, 50, No. 7; Djurić 2001a, 123, No. 59; Ragolič 2023, 269, No. 338.

#### 113. LID OF AN ASH CHEST PL. 37

Prov.: Veliko Tinje, church of Sts Peter and Paul, south wall.

Loc.: Veliko Tinje, church of Sts Peter and Paul, south wall.

Material: Eastern Alpine marble.

Condition: Part of a lid with corner acroteria missing the top parts. Surface weathered.

Size:  $? \times 25 \times 80$  cm.

Structure: Gabled lid with a presumably flat ridge and corner acroteria.

Lit.: Gulič 2007, 58–59; Ragolič 2023, 213, No. 247.

#### 114. LID OF AN ASH CHEST PL. 37

Prov.: Veliko Tinje, church of Sts Peter and Paul, north wall.

Loc.: Veliko Tinje, church of Sts Peter and Paul, north wall.

Material: Eastern Alpine marble.

Condition: Fragment of the front side with the left acroterium. Surface weathered.

Size:  $40 \times 23 \times 20$  cm.

Structure: Gabled lid with a presumably flat ridge and corner acroteria.

Inscription:  $\langle D(is) \rangle M(anibus)$ 

Lit.: Gulič 2007, 21; Ragolič 2023, 211–212, No. 243.

# 115. LID OF AN ASH CHEST PL. 37

Prov.: Veliko Tinje, church of Sts Peter and Paul, north wall.

Loc.: Veliko Tinje, church of Sts Peter and Paul, north wall.

Material: Eastern Alpine marble.

Condition: Fragment of the front side with the left acroterium. Surface weathered.

Size:  $64 \times 15 \times ?$  cm.

Structure: Gabled lid with a presumably flat ridge and corner acroteria.

Lit.: Gulič 2007, 21; Ragolič 2023, 214, No. 249.

### 116. LID FRAGMENT PL. 37

Prov.: Veliko Tinje, church of Sts Peter and Paul, north foundations.

Loc.: Veliko Tinje, church of Sts Peter and Paul, north foundations.

Material: Eastern Alpine marble.

Condition: Fragment of the front side with the right acroterium bearing a decoration panel. Surface weathered.

Size:  $? \times 45 \times 22$  cm.

Structure: Gabled lid with a presumably flat ridge and corner acroteria.

Lit.: Gulič 2007, 34–36; Ragolič 2023, 214, No. 250.

#### 117. LID FRAGMENT PL. 37

Prov.: Veliko Tinje, church of Sts Peter and Paul, north wall, 2007.

Loc.: Veliko Tinje, next to the church of Sts Peter and Paul.

Material: Eastern Alpine marble.

Condition: Fragment of the rear side with missing left and upper parts.

Size:  $81 \times 54 \times 27$  cm; short side edge h. 8 cm; standing surface w. 13 and 16 cm.

Structure: Gabled lid with a sunken underside hollowed out using a point chisel.

Lit.: Unpublished.

# 118. LID FRAGMENT PL. 38

Prov.: Veliko Tinje, church of Sts Peter and Paul, north wall, 2007.

Loc.: Veliko Tinje, church of Sts Peter and Paul.

Material: Eastern Alpine marble.

Condition: Corner fragment with missing acroterium.

Size:  $? \times 24 \times 80$  cm.

Structure: Gabled lid with a finely dressed plain slope and corner acroteria. The edge of the short side is finely dressed and has a clamp hole.

Iconography: An *ascia* is carved on the short side acroterium.

Lit.: Unpublished.

## 119. LID OF AN ASH CHEST PL. 38

Prov.: Ptuj, Lot No. 2119/4, Zgornji Breg cadastral municipality, 1965.

Loc.: Ptuj, PMPO, Inv. No. RL 839.

Material: Eastern Alpine marble.

Condition: Complete lid with missing acroterium tops and damaged pediment. Surface weathered.

Size:  $94 \times 18 \times 73$  cm.

Structure: Longitudinally gabled lid with plain slopes, narrow flat ridge and corner acroteria. Decoration panels in the acroteria and in one of the tympana. Clamp hole in each of the short sides. Inscription: D(is) M(anibus)

Iconography: All four acroterium panels depict *en face* busts of female figures that represent the personifications of the seasons without the attributes. One of the long sides shows an ivy vine with heart-shaped leaves growing from a central acanthus cup. One of the short sides and one of the slopes bear a silhouette of an *ascia*.

Lit.: Šubic 1965, 203; Šubic 1967b, 189, Fig.; Jevremov 1988, 125, No. 151; Djurić 2001a, 123, No. 60; Ragolič 2023, 131, No. 93; ILJug 1157.

#### 120. LID OF AN ASH CHEST PL. 38

Prov.: Ptuj, Vodnikova ulica – Pošta, Lot No. 1233, Ptuj cadastral municipality, 3 September 1997.

Loc.: Ptuj, PMPO, Inv. No. RL 1028.

Material: Eastern Alpine marble.

Condition: Complete lid with one corner missing. Surface weathered.

Size:  $104 \times 24 \times 84$  cm.

Structure: Longitudinally gabled lid with plain slopes and narrow flat ridge, without acroteria. The ridge has three evenly spaced rectangular holes.

Inscription: *D(is) M(anibus)* 

Lit.: Unpublished.

#### **121. LID OF AN ASH CHEST** PL. 39

Prov.: Ptuj.

Loc.: Ptuj, PMPO, Inv. No. RL 120.

Material: Eastern Alpine marble.

Condition: Complete lid with missing ridge tip and with a transverse break. Possibly part-finished product.

Size:  $131 \times 28 \times 94$  cm.

Structure: Longitudinally gabled lid with plain slopes, narrow flat ridge and four corner acroteria. One pediment has a deep recess with a round hole. Lit.: Jevremov 1988, 90, No. 82; Djurić 2001a, 123, No. 61; Ragolič 2023, 171, No. 170.

### **122. LID FRAGMENT** PL. 39

Prov.: Slovenska Bistrica, church of St Bartholomew.

Loc.: Slovenska Bistrica, church of St Bartholomew, south wall.

Material: Eastern Alpine marble.

Condition: Front right part of a lid with missing standing surface.

Size:  $50 \times 28$  cm.

Structure: Gabled lid with corner acroteria. The separate tympanum and acroterium panels have simple frames. The lid between the ridge and the right acroterium holds a figure in the round.

Iconography: The tympanum shows a leaf garland with ribbons. The right front acroterium shows a winged eros holding a basket as a personification of a season. The same acroterium on the right short side has a part of a conical object, possibly a head wearing an Eastern-style cap. Positioned on top of the lid is a male figure reclining on his left side, with his head to the right. He is dressed in a knee-length girt tunic and sagum draped over his left shoulder and fastened on the right shoulder, draping under his head and upper body. His bare legs from the knees down are crossed, with his right calf resting on the left one. His right arm is extended beside the body, with his palm resting on his right thigh, while the left arm is raised, with the lower arm placed under his head. He may be holding an unidentifiable object in his right hand. The face and hairstyle are severely damaged and unidentifiable.

Lit.: Pahič 1968–69a; Pahič 1977a, 54; Ragolič 2023, 227, No. 264.

www: Lupa 5384.

#### 123. LID FRAGMENT PL. 40

Prov.: Laporje near Slovenska Bistrica, church

of Sts Philip and Jacob, during renovation in 1993–95.

Loc.: Laporje near Slovenska Bistrica, church of Sts Philip and Jacob, north wall.

Material: Eastern Alpine marble.

Condition: Left front side of a lid with missing right part up to the central motif, missing lower and top parts. Relief slightly damaged.

Size:  $45 \times 20$  cm.

Structure: Gabled lid with plain slopes.

Iconography: The tympanum panel shows a kantharos with a curved neck and hemispherical body in the centre that has two uncrossed vines with leaves and grape bunches growing from it.

Lit.: Ragolič 2023, 231, No. 271.

#### 124. LID FRAGMENT

PL. 40

Prov.: Videm pri Ptuju, church of St Vitus, west wall.

Loc.: Videm pri Ptuju, church of St Vitus, west wall

Material: Eastern Alpine marble.

Condition: Front pediment missing right and lower parts, as well as some of the left part.

Size:  $42 \times 17$  cm.

Structure: gabled lid with a tympanum panel in a simple frame.

Iconography: The tympanum panel shows a kantharos with a curved neck and hemispherical body in the centre that has two uncrossed vines with round-lobed leaves and grape bunches growing from it.

Lit.: Ragolič 2023, 310, No. 409.

# 125. LID FRAGMENT

PL. 40

Prov.: Ptuj, Dominican Monastery.

Loc.: Ptuj, Dominican Monastery, west wall of

the inner court.

Material: Eastern Alpine marble.

Condition: Front pediment with missing right and lower parts, as well as some of the left part.

Size:  $54 \times 29$  cm.

Structure: gabled lid with a flat ridge and tympanum panel.

Iconography: The tympanum panel shows a kantharos with S-shaped handles, curved neck and hemispherical body in the centre that has two uncrossed vines with round-lobed leaves and grape bunches growing from it. There is a round fruit above the rim of the kantharos between the two vines.

Lit.: Diez 1948, 157, No. 11; Djurić 2001, 122, No. 11; Ragolič 2023, 165, No. 158.

## 126. LID OF AN ASH CHEST PL. 41

Prov.: Draženci, property of the village community, used as a trough until 1959.

Loc.: Ptuj, PMPO, RL 733.

Material: Eastern Alpine marble.

Condition: Complete lid with a transverse break across the middle and missing half of one pediment. Damaged tops of the acroteria. Reliefs severely damaged, surface heavily weathered.

Size:  $150 \times 39 \times 110$  cm.

Structure: Longitudinally gabled lid with plain slopes, narrow flat ridge and four corner acroteria.

Iconography: The acroterium panels hold corner depictions of half-length personification of the seasons.

Lit.: Pahič 1977a, 47; Jevremov 1988, 87; Ragolič 2023, 301, No. 397.

## **127. LID FRAGMENT** PL. 41

Prov.: Šmartno na Pohorju, church of St Martin, sacristy interior.

Loc.: Šmartno na Pohorju, church of St Martin, sacristy interior.

Material: Eastern Alpine marble.

Condition: Right front corner with missing acroterium.

Size:  $43 \times 15$  cm.

Structure: Longitudinally gabled lid with corner acroteria and decoration panels along the lower edge and in the acroteria.

Inscription: \( \int D(is) \rightarrow M(anibus) \)

Iconography: Ivy scroll with heart-shaped leaves in the panel along the lower edge. Probably a rosette in the right acroterium.

Lit.: Unpublished.

### 128.LID FRAGMENT

PL, 42

Prov.: Žetale, church of St Michael.

Loc.: Žetale, church of St Michael, south wall.

Material: Grey-brown Neogene sandstone.

Condition: Front part with damaged upper section and right acroterium, with missing left acroterium. Relief damaged and heavily weathered. The stone surface is red-brown as the result of fire exposure.

Size:  $95 \times 25$  cm.

Structure: Gabled lid with a tympanum panel, possibly with corner acroteria.

Iconography: The tympanum holds *en face* bust portraits of seven family members consisting of five men and two women (second and fifth figure from the left). They are severely damaged and details unclear. The men are dressed in a tunic and *sagum* fastened at the right shoulder. The women wear a tunic and cloak, as well as a necklace of large round beads. The facial features of the figures are unclear, though all have short hairstyles or hair combed back above the ears.

Lit.: Mikl Curk 1974, with fig.; Pahič 1977a, 62; Djurić 2001a, 123, No. 63; Ragolič 2023, 300, No. 396.

## 129. LID OF AN ASH CHEST PL. 42

Prov.: Hajdina near Ptuj.

Loc.: Graz, Uiversalmuseum Joanneum, Inv.

No. 1.

Material: Neogene limestone.

Condition: complete lid. Size:  $100 \times 43 \times 57$  cm.

Structure: cross-gabled lid with plain slopes, flat perpendicular ridges with four tympana

and four acroteria.

Lit.: Modrijan – Weber 1979–81, 104, No. 1.

# **130. ASH CHEST WITH LID** PL. 42

Prov.: Obrež near Središče ob Dravi, Lot No. 447, Središče cadastral municipality, 1953.

Loc.: Ptuj, PMPO, Inv. No. RL 686.

Material: calcareous sandstone (?).

Condition: Complete chest. Complete lid with damaged lower edge and missing two acroteria. The chest interior held two pottery vessels used as urns.

Size: chest 61  $\times$  41  $\times$  49 cm, lid 70  $\times$  59  $\times$  17 cm.

Structure: Chest with plain sides. Longitudinally gabled lid with plain slopes, sharp ridge and four corner acroteria.

Lit.: Bratanič 1954, 374–375.

# LIST OF PROVENANCE FOR THE SARCOPHAGI

		Cat. No.
Hajdir	na	2
,	vž na Dravskem polju	33
	e pri Ptuju	4
Ptuj	church of St George	10, 17
,	Ptuj Castle, W tower	25, 26, 27
	Ljudski vrt	39
	Mala vojašnica	12, 14, 22
	City	11, 20, 29, 34, 35, 36, 37, 40, 42
	Miklošičeva 12	16, 18
	Minorite Monastery	7
	City walls – NW tower	21
	Panorama	23, 24
	Prešernova 16	30
	Rogaška cesta 14	3
	Slovenski trg 4	28
	Slovenski trg 6	31
	Vičava	8, 13
	Zgornji Breg	6
Spodn	ija Hajdina	9
Spodn	ija Polskava	32
Starše		41
Šmarti	no na Pohorju	38
Veliko	Tinje	19
Videm	n pri Ptuju	15
Zgorn	ija Hajdina	1, 5

# LIST OF PROVENANCE FOR THE ASH CHESTS

		Cat. No.
Črešnjev	vec .	54, 62, 88, 102, 103, 105, 108, 109
Draženc		125
Dravinjs		53, 57
Hajdina		44, 52, 128
Kebelj		55, 67, 84, 87
,	near Slovenska Bistrica	122
Malečnik		111
Maribor		45
Obrež n	ear Središče ob Dravi	129
Orešje n	iear Ptuj	68
Pernica	,	97
Ptuj c	church of St George	63
	Dominican Monastery	60, 124
	Ptuj Castle	78
I	Ptuj Castle, W tower	65, 77
(	Gregorčičev drevored	80
(	City	46, 51, 61, 69, 71, 72, 85, 86, 89, 93, 94, 95, 104, 120
1	Miklošičeva 12	79
1	Minorite Church	59
1	Minorite Monastery	48
1	Naselje bratov Roš	99
I	Panorama	66
I	Porodnišnica	82, 96, 100, 101, 106, 107
I	Pošta	119
I	Prešernova 4	43
I	Prešernova 16	70
	Trstenjakova 9	58
7	Vičava	50, 64
7	Volkmerjeva cesta	76
Ź	Zgornji Breg	83, 118
Savci		47
Slivnica	pri Mariboru	98
Slovensk	xa Bistrica	121
Spodnja	Hajdina	81
Starše		90
Studenic		75
	o na Pohorju	74, 92, 110, 126
Velika N		49
Veliko T		56, 73, 91, 112, 113, 114, 115, 116, 117
Videm p	ori Ptuju	123
Žetale		127

# LIST OF MUSEUMS AND OTHER LOCATIONS OF THE SARCOPHAGI

Graz (Austria) Inv. Cat. No.	, Universalmuse 50 without	eum Joanneum Sarcophagus with lid Fragment of a sarcophagus lid	Cat. No.	2 39
Maribor, Pokr	ajinski muzej			
Inv. Cat. No.	A 2330	Sarcophagus for Quintina	Cat. No.	5
Ptuj, city walls	, NW tower			
,		Fragment of a sarcophagus	Cat. No.	21
Ptui, Pokrajisk	i muzej Ptuj-O1	rmož		
Inv. Cat. No.	G 2060 PL	Fragment of a sarcophagus	Cat. No.	22
	RL78	Fragment of a sarcophagus		16
	RL113	Sarcophagus for Lupercus		13
	RL114	Fragment of a sarcophagus		14
	RL447	Frieze sarcophagus		1
	RL449	Fragment of a sarcophagus lid		34
	RL450	Fragment of a sarcophagus		18
	RL463	Fragment of a sarcophagus		11
	RL483	Fragment of a sarcophagus		35
	RL546	Fragment of a sarcophagus		12
	RL612	Fragment of a sarcophagus lid		31
	RL736	Sarcophagus		7
	RL752	Fragment of a sarcophagus lid		29
	RL864	Fragment of a sarcophagus		15
	RL872	Sarcophagus with lid		3
	RL883	Fragment of a sarcophagus		10
	RL938	Sarcophagus		9
	RL967	Sarcophagus for the Aelii		8
	RL1016	Fragments of a sarcophagus lid		30
	RL1018	Lid fragment of a sarcophagus for the Aelii		28
	RL1019	Fragment of a sarcophagus		17
	RL1020	Sarcophagus		6
	RL1029	Fragment of a sarcophagus		20
	RL1034	Sarcophagus		4
	without	Fragment of a sarcophagus		23
	without	Fragment of a sarcophagus		24
	without	Fragment of a sarcophagus		25
	without	Fragment of a sarcophagus		26
	without	Fragment of a sarcophagus		27

	without without	Fragment of a sarcophagus lid Fragment of a sarcophagus lid		36 37			
	without	Sarcophagus lid		38			
	without Fragment of a sarcophagus lid						
Miklavž na Dr	ravskem polju, o	church of St Nicholas					
		Fragment of a sarcophagus lid	Cat. No.	33			
Spodnja Polsk	ava, church of	-		20			
č . D	1 . 1 1	Fragment of a sarcophagus lid	Cat. No.	32			
Smartno na Po	ohorju, church		C . N	27			
		Fragment of a sarcophagus lid	Cat. No.	37			
Veliko Tinje, o	church of Sts P	eter and Paul					
		Fragment of a sarcophagus	Cat. No.	19			
LIST OF	MUSEUMS	AND OTHER LOCATIONS OF TH	E ASH CHE	ESTS			
Črešnievec, ch	urch of St Mic	hael					
	Fragment of		Cat. No.	53			
	Fragment of			61			
	Fragment of			89			
	_	an ash chest lid		103			
	_	an ash chest lid		104			
	_	an ash chest lid		106			
	Lid of an ash			109			
	Lid of an ash	chest		110			
Draviniski vrh	a, church of St	John the Baptist					
,	Fragment of	•	Cat. No.	52			
	Fragment of			56			
Graz (Austria)	, Universalmus	eum Joanneum					
Inv. Cat. No.	1	Lid of an ash chest	Cat. No.	129			
	84	Ash chest		46			
	93	Ash chest		43			
	95	Ash chest		73			
	without	Fragment of an ash chest		91			
	without	Fragment of an ash chest lid		105			

Kebelj, church		Argaret of Antioch  Fragment of an ash chest  Fragment of an ash chest	Cat. No.	54 66 67 84 87
Laporje near S	Slovenska	Bistrica, church of Sts Philip and Jacob		
		Fragment of an ash chest lid	Cat. No.	123
Malečnik, chu	rch of St	Peter		
,		Fragment of an ash chest lid	Cat. No.	112
Maribor, Pokr	,		C ( NI	4.4
Inv. Cat. No.	A 2309	Asn cnest	Cat. No.	44
Pernica, churc	h of St M			
,		Lid of an ash chest	Cat. No.	98
Ptuj, Dominic		stery Fragment of an ash chest	0.33	=0
	Cat. No.	59		
		Fragment of an ash chest lid		125
Ptuj, Ptuj Cast	tle, W tow	ver		
,,		Fragment of an ash chest	Cat. No.	76
Ptuj, City Tow		D. I. I	0. 1	
Lee Cat Na	without	,	Cat. No.	69 77
Inv. Cat. No.	RL780 RL792	Fragment of an ash chest Ash chest		77 90
	KL/92	Ash chest		90
Ptuj, Pokrajisk	ki muzej P	tuj-Ormož		
Inv. Cat. No.	RL33	Fragment of an ash chest	Cat. No.	60
	RL36	Ash chest		75
	RL37	Ash chest		42
	RL64	Lid of an ash chest		94
	RL68	Fragment of an ash chest		79
	RL104	Ash chest		49
	RL120	Lid of an ash chest		121
	RL123	Lid of an ash chest		96
	RL448	Ash chest		49
	RL453	Ash chest		47
	RL487	Fragment of an ash chest		65
	RL490	Fragment of an ash chest lid		97

	RL562	Ash chest		83
	RL600	Fragment of an ash chest		58
	RL686	Ash chest with lid		130
	RL711	Ash chest with lid		80
	RL720	Fragment of an ash chest		57
	RL733	Lid of an ash chest		126
	RL748	Fragment of an ash chest lid		95
	RL783	Ash chest		50
	RL836	Fragments of an ash chest		63
	RL839	Lid of an ash chest		119
	RL871	Lid of an ash chest		100
	RL928	Fragments of an ash chest		62
	RL944	Ash chest		82
	RL1011	Fragment of an ash chest lid		107
	RL1023	Ash chest		51
	RL1028	Lid of an ash chest		120
Old Cat. No.	25	Fragment of an ash chest		64
	without	Fragment of an ash chest		69
	without	Fragment of an ash chest		70
	without	Ash chest with lid		81
	without	Fragment of an ash chest		85
	without	Fragment of an ash chest		86
	without	Lid of an ash chest		101
	without	Lid of an ash chest		102
	without	Fragment of an ash chest lid		108
Ptuj, Prešerno	ova 16			
<i>,</i>	Fragment o	of an ash chest	Cat. No.	70
Slivnica pri M	ariboru, Mari	ian church		
1	Lid of an a		Cat. No.	99
Slovenska Bis	trica church	of St Bartholomew		
010 ( 01101111 2 12		of an ash chest lid	Cat. No.	122
Studenice, chu	irch of the T	hree Kings		
Studernee, en	Ash chest	firee Kings	Cat. No.	74
	11311 CHESC		Cat. 140.	, ,
Šmartno na Po	, .	ch of St Martin		0.2
	0	of an ash chest(?)	Cat. No.	93
	Lid of an a	sh chest of an ash chest lid		111 127
	- rraument o	n an ash chest ha		1//

Varaždin (Cro	atia), Gradski n	nuzej		
Inv. Cat. No.	66345	Ash chest	Cat. No.	45
Veliko Tinie. c	hurch of Sts P	eter and Paul		
		Ash chest	Cat. No.	55
		Ash chest	340.110.	72
		Fragment of an ash chest		92
		Lid of an ash chest		113
		Lid of an ash chest		114
		Lid of an ash chest		115
		Lid of an ash chest		116
		Lid of an ash chest		117
		Lid of an ash chest		118
Videm pri Ptu	ju, church of S	t Vitus		
1	, ,	Lid of an ash chest	Cat. No.	124
Žetale, church	of St Michael			
ŕ		Fragment of an ash chest lid	Cat. No.	128

# LIST OF TABLES

Pl. 1	Cat. No. 1a	Frieze sarcophagus, front side. ©PMPO. Photo O. Harl.
	Cat. No. 1b-c	Frieze sarcophagus, front side, bedding surface and interior side. ©PMPO. Laser scanning Gnom d.o.o., image G. Rutar.
Pl. 2	Cat. No. 2	Sarcophagus with lid. ©Joanneum. Photo B. Djurić.
	Cat. No. 3	Sarcophagus with lid. ©PMPO. Photo M. Pajk.
	Cat. No. 4a	Sarcophagus, front side. ©PMPO. Photo B. Djurić.
Pl. 3	Cat. No. 4b-c	Sarcophagus, short sides. ©PMPO. Photo B. Farič.
	Cat. No. 5a	Sarcophagus for Quintina. ©PM Maribor. Photo B. Djurić.
	Cat. No. 5b	Sarcophagus for Quintina. ©B. Hebert, Graz, legacy of E. Diez.
	Cat. No. 6a	Sarcophagus, bottom. ©PMPO. Photo B. Djurić.
Pl. 4	Cat. No. 6	Sarcophagus, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 7a	Sarcophagus. ©PMPO. Photo B. Djurić.
	Cat. No. 7b	Sarcophagus, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 8	Sarcophagus for the Aelii, front side. ©PMPO. Photo M. Pajk.
Pl. 5	Cat. No. 9	Sarcophagus, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 10	Fragment of a sarcophagus. ©PMPO. Photo M. Pajk.
	Cat. No. 11	Fragment of a sarcophagus. ©PMPO. Photo M. Pajk.
Pl. 6	Cat. No. 12	Fragment of a sarcophagus. ©PMPO. Photo M. Pajk.
	Cat. No. 13	Sarcophagus for Lupercus. ©PMPO. Photo M. Pajk.
	Cat. No. 14	Fragment of a sarcophagus. ©PMPO. Photo B. Djurić.
	Cat. No. 15	Fragment of a sarcophagus. ©PMPO. Photo M. Pajk.
	Cat. No. 16	Fragment of a sarcophagus. ©PMPO. Photo B. Djurić.
	Cat. No. 17	Fragment of a sarcophagus. ©PMPO. Photo M. Pajk.
	Cat. No. 18	Fragment of a sarcophagus. ©PMPO. Photo M. Pajk.
Pl. 7	Cat. No. 19	Fragment of a sarcophagus. Photo B. Djurić.
	Cat. No. 20	Fragment of a sarcophagus. ©PMPO. Photo M. Pajk.
	Cat. No. 21	Fragment of a sarcophagus. Photo L. Pukšič.
	Cat. No. 22	Fragment of a sarcophagus. Photo B. Farič.
Pl. 8	Cat. No. 23	Fragment of a sarcophagus. Photo M. Lubšina Tušek.
	Cat. No. 24	Fragment of a sarcophagus. Photo B. Djurić.
	Cat. No. 25	Fragment of a sarcophagus. Photo B. Djurić.
	Cat. No. 26	Fragment of a sarcophagus. Photo B. Djurić.
	Cat. No. 27	Fragment of a sarcophagus. Photo B. Djurić.
	Cat. No. 28	Lid fragment of a sarcophagus for the Aelii. ©PMPO. Photo M. Pajk.
Pl. 9	Cat. No. 29	Fragment of a sarcophagus lid. ©PMPO. Photo M. Pajk.
	Cat. No. 30a	Fragment of a sarcophagus lid, right front acroterium. ©PMPO. Photo M. Pajk.
	Cat. No. 30b	Fragment of a sarcophagus lid, left front acroterium. ©PMPO. Photo M. Pajk.
Pl. 10	Cat. No. 31	Fragment of a sarcophagus lid. ©PMPO. Photo B. Djurić.
	Cat. No. 32	Fragment of a sarcophagus lid. Photo B. Djurić.

	Cat. No. 33	Fragment of a sarcophagus lid. Photo B. Djurić.
	Cat. No. 34	Fragment of a sarcophagus lid. ©PMPO. Photo M. Pajk.
Pl. 11	Cat. No. 35	Fragment of a sarcophagus lid. ©PMPO. Photo M. Pajk.
	Cat. No. 36	Fragment of a sarcophagus lid. ©PMPO. Photo B. Djurić.
	Cat. No. 37	Fragment of a sarcophagus lid. Photo ZVKDS OE Mb.
	Cat. No. 38	Lid of a sarcophagus. ©PMPO. Photo B. Djurić.
	Cat. No. 39	Fragment of a sarcophagus lid. ©Joanneum. Photo O. Harl.
	Cat. No. 41	Fragment of a sarcophagus lid. ©PMPO. Photo B. Djurić.
Pl. 12	Cat. No. 42	Ash chest. ©PMPO. Photo O. Harl.
	Cat. No. 43a	Ash chest, front side. ©Joanneum. Photo O. Harl.
	Cat. No. 43b	Ash chest, right short side. ©Joanneum. Photo O. Harl.
	Cat. No. 43c	Ash chest, left short side. ©Joanneum. Photo O. Harl.
Pl. 13	Cat. No. 44	Ash chest, front side. ©PM Maribor. Photo I. Kacafura.
	Cat. No. 45	Ash chest, front side. ©Gradski muzej Varaždin. Photo O. Harl.
	Cat. No. 46a	Ash chest, front side. ©Joanneum. Photo O. Harl.
Pl. 14	Cat. No. 46b	Ash chest, right short side. ©Joanneum. Photo B. Djurić.
	Cat. No. 46c	Ash chest, left short side. ©Joanneum. Photo B. Djurić.
	Cat. No. 47a	Ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 47b	Ash chest, right short side. ©PMPO. Photo B. Djurić.
	Cat. No. 47c	Ash chest, left short side. ©PMPO. Photo B. Djurić.
Pl. 15	Cat. No. 47d	Ash chest, underside-wash basin. ©PMPO. Photo B. Djurić.
	Cat. No. 48a	Ash chest, front side. ©PMPO. Photo S. Habič.
	Cat. No. 48b	Ash chest, right short side. ©PMPO. Photo S. Habič.
	Cat. No. 48c	Ash chest, left short side. ©PMPO. Photo S. Habič.
Pl. 16	Cat. No. 49a	Ash chest, front side. ©PMPO. Photo M. Pajk.
	Cat. No. 49b	Ash chest, upper side. ©PMPO. Photo Gnom d.o.o.
	Cat. No. 49c	Ash chest, rear side. ©PMPO. Photo Gnom d.o.o.
Pl. 17	Cat. No. 49e	Ash chest, right short side. ©PMPO. Photo Gnom d.o.o.
	Cat. No. 49f	Ash chest, left short side. ©PMPO. Photo Gnom d.o.o.
	Cat. No. 50	Ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 51a	Ash chest, front side. ©PMPO. Photo O. Harl.
	Cat. No. 51b	Ash chest, right short side. ©PMPO. Photo O. Harl.
	Cat. No. 51c	Ash chest, left short side. ©PMPO. Photo O. Harl.
Pl. 18	Cat. No. 52a	Bottom of an ash chest, front side. Photo B. Djurić.
	Cat. No. 52b	Bottom of an ash chest, right short side. Photo B. Djurić.
	Cat. No. 53	Fragment of an ash chest, front side. Photo L. Pukšič.
	Cat. No. 54	Fragment of an ash chest, front side. Photo L. Pukšič.
Pl. 19	Cat. No. 55	Ash chest, short side. Photo B. Djurić.
	Cat. No. 56a	Fragment of an ash chest, right short side. Photo B. Djurić.
	Cat. No. 56b	Fragment of an ash chest, front side. Photo B. Djurić.
	Cat. No. 57	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.
D1 00	Cat. No. 58	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.
Pl. 20	Cat. No. 59	Fragment of an ash chest, front side. Photo B. Djurić.
	Cat. No. 60a	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.

	No. 60b	Fragment of an ash chest. ©PMPO. Photo B. Djurić.
Pl. 21	Cat. No. 61	Fragment of an ash chest, front and upper side. Photo B. Djurić.
	Cat. No. 62	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.
Pl. 22	Cat. No. 63	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 64	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 65	Fragment of an ash chest, front side. ©PMPO. Photo M. Pajk.
Pl. 23	Cat. No. 66	Fragment of an ash chest, right short side. Photo B. Djurić.
	Cat. No. 67	Fragment of an ash chest, left short side. Photo B. Djurić.
	Cat. No. 68	Fragment of an ash chest, left short side. ©PMPO. Photo B. Djurić.
Pl. 24	Cat. No. 69	Fragment of an ash chest, short side. ©PMPO. Photo B. Djurić.
	Cat. No. 70	Fragment of an ash chest, short side. 3D photo P. V. Bayer.
	Cat. No. 71	Fragment of an ash chest. ©PMPO. Photo B. Djurić.
	Cat. No. 72	Ash chest, short side. Photo B. Djurić.
Pl. 25	Cat. No. 73	Ash chest, front side. © and photo Inštitut za arheologijo ZRC.
	Cat. No. 74	Ash chest, front side. Photo M. Pajk.
	Cat. No. 75	Ash chest, front side. ©PMPO. Photo O. Harl.
Pl. 26	Cat. No. 76	Fragment of an ash chest, front side. Photo B. Djurić.
	Cat. No. 77	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 78	Fragment of an ash chest, front side. Photo O. Harl.
Pl. 27	Cat. No. 79	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 80	Ash chest with lid, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 81	Ash chest with lid, front side. ©PMPO. Photo B. Djurić.
Pl. 28	Cat. No. 82	Ash chest, front side. ©PMPO. Photo M. Pajk.
	Cat. No. 83	Fragments of an ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 84	Fragment of an ash chest, front side. Photo L. Pukšič.
	Cat. No. 85	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 86	Fragment of an ash chest, front side. ©PMPO. Photo B. Djurić.
Pl. 29	Cat. No. 87	Fragment of an ash chest, front side. Photo L. Pukšič.
	Cat. No. 88	Fragment of an ash chest, front side. Photo S. Pahič, archive of PMMb.
	Cat. No. 89	Fragment of an ash chest, front side. Photo B. Djurić.
Pl. 30	Cat. No. 90	Ash chest, front side. Photo B. Djurić.
	Cat. No. 91	Fragment of an ash chest, front side. ©Joanneum. Photo O. Harl.
	Cat. No. 92	Fragment of an ash chest, front side. Photo B. Djurić.
	Cat. No. 93	Fragment of an ash chest(?), front side. Photo L. Pukšič.
Pl. 31	Cat. No. 94a	Lid of an ash chest, front side. ©PMPO. Photo M. Pajk.
	Cat. No. 94b	Lid of an ash chest, upper side. ©PMPO. Photo M. Pajk.
	Cat. No. 95	Fragment of an ash chest lid, front side. ©PMPO. Photo M. Pajk.
Pl. 32	Cat. No. 96	Lid of an ash chest, front side. ©PMPO. Photo I. Kacafura.
	Cat. No. 97	Fragment of an ash chest lid, front side. ©PMPO. Photo M. Pajk.
	Cat. No. 98a	Lid of an ash chest, front side, Pernica. Photo B. Djurić.
	Cat. No. 98b	Lid of an ash chest, front side. 3D photo P. V. Bayer.
Pl. 33	Cat. No. 99	Lid of an ash chest, front side. Photo B. Djurić.
	Cat. No. 100a	Lid of an ash chest, front side. ©PMPO. Photo M. Pajk.

	Cat. No. 100b	Lid of an ash chest. ©PMPO. Photo M. Pajk.
	Cat. No. 100c	Lid of an ash chest. ©PMPO. Photo M. Pajk.
Pl. 34	Cat. No. 101	Lid of an ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 102	Lid of an ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 103	Fragment of an ash chest lid, front side. Photo B. Djurić.
	Cat. No. 104	Fragment of an ash chest lid, front side. Photo B. Djurić.
	Cat. No. 105	Fragment of an ash chest lid, front side. ©Joanneum. Photo O. Harl.
Pl. 35	Cat. No. 106	Fragment of an ash chest lid, front and upper sides. Photo B. Djurić.
	Cat. No. 108	Fragment of an ash chest lid. ©PMPO. Photo B. Djurić.
Pl. 36	Cat. No. 107	Fragment of an ash chest lid, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 109	Lid of an ash chest, front side. Photo B. Djurić.
	Cat. No. 110	Lid of an ash chest, front side. Photo B. Djurić.
	Cat. No. 111	Lid of an ash chest, bottom side. Photo B. Djurić.
	Cat. No. 112	Lid of an ash chest. Photo B. Djurić.
Pl. 37	Cat. No. 113	Lid of an ash chest. Photo B. Djurić.
	Cat. No. 114	Lid of an ash chest. Photo B. Djurić.
	Cat. No. 115	Lid of an ash chest. Photo B. Djurić.
	Cat. No. 116	Fragment of an ash chest lid. Photo B. Djurić.
	Cat. No. 117	Fragment of an ash chest lid. Photo B. Djurić.
Pl. 38	Cat. No. 118a	Fragment of an ash chest lid. Photo B. Djurić.
	Cat. No. 118b	Fragment of an ash chest lid. Photo B. Djurić.
	Cat. No. 119a	Lid of an ash chest. ©PMPO. Photo B. Djurić.
	Cat. No. 119b	Lid of an ash chest, front side. ©PMPO. Photo B. Djurić.
	Cat. No. 120	Lid of an ash chest. ©PMPO. Photo B. Djurić.
Pl. 39	Cat. No. 121	Lid of an ash chest. ©PMPO. Photo S. Habič.
	Cat. No. 122 PMMb).	Fragment of a lid. Photo L. Pukšič in S. Pahič (Arhiv
Pl. 40	Cat. No. 123	Fragment of an ash chest lid. Photo B. Djurić.
	Cat. No. 124	Fragment of an ash chest lid. Photo B. Djurić.
	Cat. No. 125	Fragment of an ash chest lid. Photo B. Djurić.
Pl. 41	Cat. No. 126a	Lid of an ash chest. ©PMPO. Photo B. Djurić.
	Cat. No. 126b	Lid of an ash chest. ©PMPO. Photo B. Djurić.
	Cat. No. 127	Fragment of an ash chest lid. Photo B. Djurić.
Pl. 42	Cat. No. 128	Fragment of an ash chest lid B. Djurić.
	Cat. No. 129	Lid of an ash chest. ©Joanneum. Photo B. Djurić.
	Cat. No. 130	Ash chest with lid. ©PMPO. Photo S. Habič.

## LIST OF FIGURES

- Figure 1. Marble spolia used in the construction of Ptuj Castle, here shown in the east façade of the west tower
- Figure 2. Foundations with marble spolia: Črešnjevec, church of St Michael, southwest corner of the first church (left), and Veliko Tinje, church of Sts Peter and Paul, northwest corner (right)
- Figure 3. Marble spolia reused as building blocks in the south wall of the Romanesque church of St Michael in Črešnjevec
- Figure 4. Quoins of marble spolia in the Romanesque bell tower of St Michael's church in Šmartno na Pohorju (left) and in the church of St Margaret of Antioch in Kebelj (right)
- Figure 5. Various uses of the known sarcophagi and ash chests of Poetovio, expressed in percentage (key: 1 primary use; 2 secondary use in Antiquity; 3 damaged in Antiquity; 4 secondary use in post-Antiquity; 5 building material; 6 intentional display; 7 unknown
- Figure 6. Stratigraphic position of a sarcophagus upon discovery (Cat. No. 3; Šubic 1972)
- Figure 7. Incidence of inscriptions and decorations on the known sarcophagi and ash chests of Poetovio, expressed in percentage
- Figure 8. Territory of Poetovio according to Horvat et al. 2003
- Figure 9. Territory of Poetovio according to Ragolič 2014
- Figure 10. The δ18O and δ13C isotope diagram for Pohorje (blue) and Gummern marbles (green) used for the sarcophagi
- Figure 11. The δ18O and δ13C isotope diagram for Pohorje (blue) and Gummern marbles (green) used for the ash chests
- Figure 12. The  $\delta$ 18O in  $\delta$ 13C isotope diagram of the samples taken from the known Pohorje quarries plotted against the data fields of Pohorje (blue) and Gummern marbles (green) according to Müller
- Figure 13. Diagrams showing the width, length and height of the chests of Pannonian marble sarcophagi
- Figure 14. Diagram showing the length and weight of the chests of Pannonian marble sarcophagi
- Figure 15. Examples of sarcophagi in the quarry production state (Cat. Nos. 4 and 3)
- Figure 16. Sarcophagus lid in the quarry production state (Cat. No. 29)
- Figure 17. Surface finish of the interior side and bottom, as well as bedding (Cat. Nos. 1 and 6)
- Figure 18. Dividing a rectangle into five equal parts (dashed line) using applied geometry (Brunes star)
- Figure 19. Dividing a rectangle into six equal parts (dashed line) using applied geometry (Brunes star)
- Figure 20. Dividing a rectangle into five equal parts (dashed line) and determining the width of the lateral front panels (dotted line) using applied geometry (Brunes star)
- Figure 21. Diagrams showing the width, length and height of the marble ash chests
- Figure 22. Diagram showing the length and weight of the marble ash chests

- Figure 23. Examples of ash chests in the quarry production state: A Ptuj (Cat. No. 81), B Črešnjevec (Cat. No. 89)
- Figure 24. A basic design of an ash chest lid on a block of marble, Črešnjevec (Cat. No. 109); B sunken underside of an ash chest lid, Veliko Tinje (Cat. No. 117)
- Figure 25. Dividing a rectangle into four equal parts (dashed line) using applied geometry (Cat. No. 80)
- Figure 26. Perpendicular (A) and longitudinal forms (B) of ash chest lids
- Figure 27. Designing a Norico-Pannonian volute using a combination of three aligned circles
- Figure 28. The analysis of the Norico-Pannonian volute on a sarcophagus (Cat. No. 12)
- Figure 29. Designing a Norico-Pannonian volute using a combination of four aligned circles
- Figure 30. The analysis of the Norico-Pannonian volute on a sarcophagus from Pécs (Lupa 827)
- Figure 31. The analysis of the Norico-Pannonian volute on an ash chest (Cat. No. 83)
- Figure 32. Sarcophagus with a barrel-shaped lid (PMPO RL 734)
- Figure 33. Diagrams showing the width, length and height of the limestone ash chests
- Figure 34. Lid of an ash chest from Hajdina (Cat. No. 129)
- Figure 35. Examples of full- and half-length portraits of men: a- sarcophagus Cat. No. 10; ash chests b- Cat. No. 43, c- Cat. No. 47, d- Cat. No. 49, e- Cat. No. 46, f- Cat. No. 58, g- Cat. No. 98, h- Cat. No. 100, i- Cat. No. 94, j- Cat. No. 102
- Figure 36. Examples of full- and half-length portraits of women: ash chests a- Cat. No. 43; b- Cat. No. 49, c- Cat. No. 95, d- Cat. No. 100, e- Cat. No. 103, f- sarcophagi Cat. No. 28, g- Cat. No. 103, h- Cat. No. 95, i- Cat. No. 103
- Figure 37. Depictions of female servants: a- Cat. No. 19, b- Cat. No. 48, c- Cat. No. 98
- Figure 38. Representations of the Seasons: a- sarcophagi Cat. No. 11, b,c- Cat. No. 30; ash chests d- Cat. No. 59, e- Cat. No. 33, f,g- Cat. No. 96, h- Cat. No. 102
- Figure 39. Hora, Spodnja Polskava Cat. No. 32
- Figure 40. Eros the archer: a- Pernica (Cat. No. 98; from Muchar 1844, Pl. VII 2), b- Cat. No. 105
- Figure 41. Part of the composition with a pair of erotes (Cat. No. 11) and the complete motif on an ash chest from Sisak (Lupa 3801)
- Figure 42. Depiction of mourning erotes on ash chests: a- Cat. No. 44, b- Cat. No. 50, c- Cat. No. 60, d- Cat. No. 45, e- Cat. No. 105
- Figure 43. The depiction of 'Attis' on an ash chest from Dravinjski vrh (Cat. No. 56)
- Figure 44. Theseus abandoning Ariadne on Naxos, Kebelj (Cat. No. 66)
- Figure 45. Chariot drawn by a female panther as part of the Triumph of Dionysus, Kebelj (Cat. No. 67)
- Figure 46. Dionysian motifs: a- Ptuj (Cat. No. 17), b- Vranje (Lupa 1653)
- Figure 47. Dionysian motif of vines growing from a kantharos: a- Savci (Cat. No. 47), b- Ptuj (Cat. No. 48)
- Figure 48. Fragments of ash chest lids with the motif of vines growing from a kantharos: a- Ptuj, Dominican Monastery (Cat. No. 125), b- Videm pri Ptuju (Cat. No. 124), c- Laporje (Cat. No. 123)


- Figure 49. Drawing of the sarcophagus fragment (by M. Lubšina Tušek)
- Figure 50. Drawing of the sarcophagus lid (Vienna, Bundes denkmalamt-INVE\_ZK\_25\_1874\_177\_2\_8, by R. Gaupmann)
- Figure 51. Drawing of the ash chest (from Knabl 1851)
- Figure 52. Drawing of the ash chest (Vienna, graphic imprint, Steinbüchel?, Pl. VII)
- Figure 53. Drawing of the ash chest (by V. Kmetič, from Hoffiler Saria 1938)
- Figure 54. Drawing of the ash chest (from Skrabar 1905)
- Figure 55. Drawing of the ash chest (Historical Archives Ptuj, document No. 7272)
- Figure 56. Drawing of the ash chest (Vienna, KHM, Antikensammlung, Archive No. 23 ex 1830, Somenzari, Pl. VII)
- Figure 57. Drawing of the ash chest lid (from Muchar 1844)

VZOREC	KAT. ŠT.	Na	Mg	Al	К	Sc	V	Cr	Fe	Mn	Со	Cu	Zn	Rb
		ppm	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm
PET01	17	287	2,39	1468	916	0,5	10	3	0,12	35	0,9	1,5	8	2,6
PET02	29	111	0,50	218	111	0,3	9	1	0,06	46	0,6	1,5	8	0,3
PET04	22	188	46	1683	819	0,5	9	2	0,10	30	0,9	5,8	11	2,2
PET05	9	156	0,29	973	574	0,3	8	11	0,06	10	0,7	1,4	6	1,9
PET06	35	104	0,42	989	479	0,3	9	3	0,17	75	0,7	0,7	5	1,3
PET07	3	44	0,47	398	166	0,3	8	3	0,10	168	0,7	1,2	16	0,7
PET09	8	63	0,45	532	154	0,3	8	2	0,04	20	0,6	1,2	10	0,5
PET10	11	407	0,55	730	144	0,4	8	7	0,11	45	0,9	0,3	3	0,3
PET12	1	71	0,40	1113	734	0,5	11	3	0,07	31	0,8	1,0	11	2,9
PET15	18	498	0,31	649	100	0,4	8	2	0,09	35	1,0	0,6	5	0,2
PET16	30	233	0,15	312	100	0,4	4	2	0,04	29	0,5	0,2	2	0,1
PET17	16	291	1,36	1466	484	0,4	10	2	0,08	26	1,0	0,9	4	1,5
PET18	31	770	0,34	1483	307	0,4	8	2	0,08	38	0,9	0,4	3	1,3
PET27	10	305	1,22	2090	1470	0,4	12	6	0,28	243	1,0	1,0	11	5,8
PET28	15	126	1,06	304	108	0,4	10	2	0,09	38	0,9	0,2	3	0,4
PET30	14	182	0,23	1502	695	0,4	10	4	0,14	43	1,0	1,4	3	2,9
PET31	12	759	0,40	1823	629	0,4	9	2	0,10	35	1,0	0,9	9	5,9
PET32	13	775	0,24	975	484	0,4	14	2	0,36	65	0,9	2,1	12	1,7
PET36	28	314	0,50	1915	604	0,6	13	5	0,33	88	1,4	2,6	15	2,0
PET40	6	313	0,80	4725	2102	0,7	14	6	0,31	68	1,3	1,2	11	10,2
PET42	32	285	1,21	1184	256	0,4	10	2	0,14	66	1,1	0,8	27	3,0
PET43	33	167	0,87	977	100	0,4	9	3	0,13	40	1,0	1,1	8	0,1
PET44	5	207	1,15	682	551	0,4	10	3	0,09	35	1,0	0,8	8	1,7
MAR2	97	70	1,06	87	85	<2	<10	<2	0,10	32	0,6	0,2	<5	0,6
MAR15	45	<50	0,11	164	143	<2	<10	2	0,03	20	0,6	0,1	<5	0,4
PET11	76	97	0,33	174	113	0,3	8	2	0,04	16	0,7	1,7	9	0,3
PET13	80	559	0,85	6538	1322	1,3	12	2	0,22	115	0,7	13,3	56	5,3
PET14	48	116	0,30	1376	554	0,4	9	2	0,21	53	1,1	1,0	6	1,8
PET29	49	229	0,31	717	369	0,4	10	3	0,09	30	1,0	0,4	3	3,5
PET34	43	296	0,37	3694	1147	0,6	14	6	0,21	41	1,2	1,8	10	4,9
PET 51	51													
PET62	89													
PET69	64													
SMA2	92	201	0,66	2663	1178	0,9	11	10	0,17	73	0,8	1,2	8	5,5
CSR3	109	425	0,27	711	159	0,3	7	3	0,05	20	0,7	1,1	11	0,3
CSR4	105	41	0,45	95	81	0,3	7	7	0,06	17	0,7	11	14	0,1
LMJ95	74	413	261	1451	856	4	14	3	14	60	14	16	15	21

Tabela rezultatov analiz marmorja poetovionskih sarkofagov (PET01-PET44) in pepelnic in pepelnic (MAR2-CSR4), Harald W. Müller

VZOREC	KAT. ŠT.	Sr	Υ	Cd	Ва	La	Ce	Eu	Hf	Th	U	δ <sup>18</sup> Ο	δ <sup>13</sup> C
		ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm		
PET01	17	250	1,3	0,1	17	1,07	1,93	0,06	0,05	0,3	0,2	-7,78	0,26
PET02	29	293	0,7	0,1	9	0,32	0,48	0,02	0,05	0,1	0,1	-11,06	1,15
PET04	22	235	0,7	0,1	23	0,84	1,60	0,03	0,05	0,3	0,1	-6,64	1,26
PET05	9	200	0,7	0,1	55	0,69	1,18	0,04	0,05	0,2	0,1	-5,72	0,52
PET06	35	222	0,6	0,1	14	0,68	1,01	0,03	0,05	0,8	0,2	-6,29	1,04
PET07	3	185	0,8	0,1	26	0,66	1,46	0,04	0,05	0,2	0,2	-11,31	-0,17
PET09	8	200	0,4	0,1	5	0,28	0,38	<0,01	0,05	0,1	0,1	-6,84	2,08
PET10	11	196	0,4	0,1	8	0,47	0,85	0,02	0,05	0,2	0,1	-11,96	0,64
PET12	1	274	0,5	0,1	17	0,58	1,06	0,02	0,05	0,1	0,1	-5,74	0,92
PET15	18	274	0,6	0,1	14	0,45	0,67	0,03	0,17	0,8	0,11	-14,67	1,39
PET16	30	189	0,3	0,1	7	0,20	0,34	0,03	0,05	0,5	0,05	-17,21	0,13
PET17	16	199	1,4	0,1	11	0,98	1,59	0,05	0,09	0,5	0,13	-6,57	0,18
PET18	31	211	1,0	0,1	13	0,52	0,82	0,10	0,06	0,5	0,14	-13,05	0,49
PET27	10	322	2,2	0,1	64	2,07	3,70	0,22	0,05	0,5	0,57	-10,92	0,55
PET28	15	183	0,5	0,1	4	0,38	0,57	0,03	0,05	0,5	0,76	-7,16	0,17
PET30	14	163	0,8	0,1	74	0,95	1,77	0,09	0,05	0,5	0,15	-6,89	0,83
PET31	12	203	0,5	0,1	38	0,77	1,24	0,05	0,15	1,1	0,25	-6,27	71
PET32	13	248	0,3	0,1	87	0,26	0,42	0,07	0,07	0,6	0,18	-7,51	94
PET36	28	250	4,2	0,1	19	2,58	3,64	0,15	0,11	0,8	0,24	-11,79	1,30
PET40	6	182	1,7	0,1	86	2,19	4,36	0,13	0,10	0,6	0,19	-6,78	72
PET42	32	188	0,9	0,3	3	0,38	0,70	0,05	0,06	0,5	0,05	-6,77	1,02
PET43	33	171	0,8	0,1	4	0,60	0,99	0,03	0,05	0,5	13	-8,59	-0,14
PET44	5	358	0,6	0,1	12	0,65	1,06	0,03	0,05	0,5	0,08	-7,47	-0,08
MAR2	97	223	0,4	<0,1	7	0,6	0,35	<0,03	<0,1	0,9	0,05	-8,10	1,24
MAR15	45	142	0,1	<0,1	12	0,5	0,28	<0,03	<0,1	<0,5	0,12	-5,89	0,72
PET11	76	231	0,2	0,1	6	0,24	0,38	0,02	0,05	0,1	0,1	-12,30	1,10
PET13	80	273	1,3	0,1	24	1,60	2,82	0,08	0,05	0,2	1,7	-13,62	1,23
PET14	48	182	0,8	0,1	107	0,98	1,86	0,11	0,06	0,5	0,17	-6,01	0,76
PET29	49	200	0,4	0,1	21	0,42	0,77	0,03	0,06	0,5	0,16	-13,40	1,00
PET34	43	191	1,4	0,1	74	1,83	3,36	0,11	0,06	0,7	0,24	-6,50	0,67
PET 51	51											-6,28	1,72
PET62	89											-10,72	1,51
PET69	64											-657	1,25
SMA2	92	178	3,8	0,1	25	3,15	5,1	0,14	0,05	0,4	0,4	-9,17	1,65
CSR3	109	218	0,5	0,1	13	0,39	0,68	0,02	0,05	0,1	0,1	-14,32	7
CSR4	105	218	0,3	0,1	8	0,25	0,33	0,01	0,05	0,1	0,1	-10,74	122
LMJ95	74	424	5	1	17	45	51	3	5	5	44	-991	6

Pohorje Gummern Pohorje/Gummern





1a



1b




Table 2



2



3







5a



5b






Table 4





7a



7b



Table 5











Table 6




Table 7





19 22




20



Table 8





23







25 26 27






29




30a



Table 10










43a





43b 43c








Table 14





46b 46c



47a





47b 47c



47d



48a






48b 48c




49a



49b








49e 49f



50



51a





51b 51c

Table 18




52a



52b









55 56a











60a








Table 22















Table 24
















Table 26















Table 28



















Table 30













94a



94b








97




98a







100a



100b



Table 34


















Table 36



107



109



110
















Table 38






118a 118b



119a



119b










Table 40









126a



126b



127





